

**Collins Creek Stream Restoration Site
Monitoring Report – MY01
Orange County, NC
Basin 03030002 - Contract # D05011**



KCI
ASSOCIATES OF
NORTH CAROLINA, PA

KCI Associates of NC, Inc.
Landmark Center II, Suite 220
4601 Six Forks Road
Raleigh, NC 27609



NCDENR-EEP
1652 Mail Service Center
Raleigh, NC 27699-1652

December 2008



**Landmark Center II, Suite 220
4601 Six Forks Road
Raleigh, NC 27609
Phone: (919) 783-9214
Fax: (919) 783-9266**

**Design Engineer: Gary M. Mryncza, P.H., P.E.
Email: gmryncza@kci.com**

TABLE OF CONTENTS

1.0 PROJECT BACKGROUND 5
1.1 Project Objectives5
1.2 Project Structure, Restoration Type, and Approach5
1.3 Location and Setting5
1.4 Project History and Background.....8
1.5 Monitoring Plan View.....12
2.0 PROJECT CONDITIONS AND MONITORING RESULTS 20
2.1 Vegetation Assessment20
2.2 Stream Assessment20
 2.2.1 Bankfull Events.....20
 2.2.2 Quantitative Measures Summary Tables21

LIST OF TABLES

Table 1. Project Restoration Components.....8
Table 2. Project Activity and Reporting History8
Table 3. Project Contact Table.....10
Table 4. Project Background Table.....11
Table 5. Verification of Bankfull Events20
Table 6. Baseline Morphology and Hydraulic Summary21
Table 7. Morphology and Hydraulic Monitoring Summary30

LIST OF FIGURES

Figure 1. Vicinity Map7
Figure 2. Project Reaches9
Figure 3. Monitoring Plan View.....12

APPENDIX A – VEGETATION DATA

A1. Vegetation Data37
A2. Vegetation Monitoring Plot Photos43

APPENDIX B – GEOMORPHOLOGIC DATA

B1. Representative Stream Problem Area Photos52
B2. Stream Photos53

B3.	Cross-Section Plots	64
B4.	Longitudinal Profile	80
B5.	Pebble Count Plots	85
B6.	Stream Hydrograph.....	101

APPENDIX C – CURRENT CONDITIONS PLAN VIEW

C1.	Current Conditions Plan View	103
-----	------------------------------------	-----

EXECUTIVE SUMMARY

The Collins Creek Stream Restoration Site is located in the Piedmont physiographic province in Orange County, North Carolina. The project will provide mitigation for stream impacts within the 8-digit hydrologic cataloging unit 03030002 in the Cape Fear River Basin by restoring and enhancing 9,453 linear feet on an Unnamed Tributary to Collins Creek (UTCC) and other associated tributaries, generating 8,933 stream mitigation units (SMU's.) The goals of the project included improving water quality in this agricultural stream system and creating high-quality aquatic and terrestrial habitat along an interconnected forested riparian corridor. In order to reach these goals, the project objectives included restoring and enhancing 9,453 linear feet of stable stream channel with the appropriate pattern, profile, and dimension that can handle the hydrologic input from the surrounding drainages; planting a functional Piedmont Alluvial Forest floodplain community along with Mesic Mixed Hardwood Forest to develop an effective riparian buffer, and removing cattle and horses from the riparian areas through livestock exclusion fencing. This report describes the results from the findings of the first year of monitoring that took place in 2008.

The riparian buffer was planted with 17 different species of bare root trees and shrubs and four different species of live stakes. Fifteen vegetation monitoring plots were established during the as-built survey. Riparian vegetation must meet a minimum survival success rate of 320 stems/acre after five years. The plots were monitored following the CVS-EEP monitoring protocol and the first year monitoring counted an average of 701 stems per acre. Isolated invasive species were noted in the restored stream buffer and will continue to be monitored to determine if corrective action is necessary. The first year monitoring found the vegetation component of the project to be on track to meeting the success criterion.

The stream restoration included ten separate reaches, which were enhanced and restored based on a combination of Priority Levels 2 and 3. Rock cross vanes, step pools, and riffle grade controls were used to control grade throughout the stream profiles. The stream was restored to B4c and C4 stream types. First year monitoring found the majority of the project to be functioning as designed. The surveyed profiles and cross-sections indicate that the project reaches are stable. In early September 2008, Tropical Storm Hanna brought five inches of rain to the site. This storm event created greater than bankfull discharges on all of the project reaches. Considering that construction was only recently completed at the site, there was the potential for some damage associated with this event. Upon inspection, only T1A suffered any damage that would require repair. These repairs will be conducted before the 2009 growing season. In addition to tropical storm Hanna there were four other storm events that created bankfull conditions. The project is on track to meeting the success criteria of at least two bankfull events in five years with each occurring in different monitoring periods.

1.0 PROJECT BACKGROUND

1.1 Project Objectives

The goals and objectives of the restoration project are as follows:

Restoration Goals:

- Improve water quality by reducing nutrient and sediment inputs.
- Create high-quality aquatic and terrestrial habitat along an interconnected forested riparian corridor.

Restoration Objectives:

- Plant a functional Piedmont Alluvial Forest floodplain community along with Mesic Mixed Hardwood Forest to develop an effective riparian buffer.
- Restore stable stream reaches that can handle the hydrologic input from the surrounding drainages.
- Remove cattle and horses from the riparian areas through livestock exclusion fencing.

1.2 Project Structure, Restoration Type, and Approach


The project streams had become degraded primarily through poor grazing management and vegetation removal. Historic aerial photographs show that the land surrounding the streams has been in rangeland for at least 65 years and cattle and horses have had access to the stream up until the restoration construction. The streams had experienced bank erosion, which led to excessive sediment throughout the site. Bed degradation and aggradation were also evident throughout the different project reaches. All of the reaches exhibited areas of vertical instability. Restoration and enhancement of 9,453 linear feet of channel was accomplished utilizing a combination of Priority 2 and 3 approaches (Table 1). UTCC-1 (Station 10+00 to 15+00) was enhanced and UTCC-2 (Station 15+00 to 24+00) and UTCC-3 (Station 24+00 to 33+49) were restored using a Priority 2 approach. The enhancement and restoration of a C4 channel with a sinuosity of 1.34 was accomplished by building a bankfull channel with a higher width/depth ratio than the existing stream, connecting it to a floodplain (bank height ratio=1.0), and creating distinct bed features by adding pools and riffles to the profile. UTCC-1 was enhanced by altering the stream cross-section and profile. UTCC-2 and UTCC-3 were restored by altering the stream cross-section, profile, and planform. In some instances, restoration was accomplished within the same belt-width and in the location of the pre-restoration channel. In the locations where the stream stayed on-line, the stream had been so drastically degraded that there was no form to the channel and the design was able to preserve one streambank and create a new bank and pattern on the opposite side of the stream.

1.3 Location and Setting

The project site is located in a rural setting within the Carolina Slate Belt ecoregion of the Piedmont physiographic province. The site drains to the southeast with a contributing drainage area of approximately 2.6 square miles at the downstream project limits (Figure 3). The watershed's southern boundary runs along NC 54. The northern boundary is below the intersection of Dodsons Crossroads and Dairyland Road. The eastern and western boundaries of the watershed are formed by the topography of the rural landscape.








The project site is spread over three different parcels of private property. The site is located off of Dodsons Crossroads six miles west of Carrboro, North Carolina in Orange County. Specifically,

the site is approximately 800 feet north of the intersection of Dodsons Crossroads and NC 54 (Figure 1). The project is centered at approximately 35.9313 degrees north and 79.1788 degrees west (WGS84). To reach the site from Raleigh, proceed west on Interstate 40. Take Exit 273 and travel west on NC 54. Continue west on NC 54 as it joins NC 15-501 and then later splits off from NC 15-501. Approximately 7.5 miles after splitting off from NC 15-501, turn right onto Dodsons Crossroads. The project is accessible from a gravel driveway approximately 0.3 mile on the left.



Orange County, North Carolina

Figure 1. Vicinity Map

-  Project Site Location
-  Streams
-  Lakes and Reservoirs
-  Major Roads
-  Cities and Towns
-  Orange County
-  County Boundaries



1:63,360
1 inch equals 1 miles



1.4 Project History and Background

Table 1. Project Restoration Components										
Collins Creek Stream Restoration Site										
Project Segment / Reach ID	Pre-Restoration Linear Footage	Type	Approach	As - Built Footage	Eligible Footage*	Mitigation Ratio	Stream Mitigation Units	Stationing	Stream Mitigation Units*	
UTCC-1	500 lf	EI	P2	500 lf	500 lf	1.5	334 SMU	10+00 - 15+00	334 SMU	
UTCC-2	909 lf	R	P2	900 lf	851 lf	1.0	851 SMU	15+00 - 24+00	851 SMU	
UTCC-3	1,034 lf	R	P2	949 lf	898 lf	1.0	898 SMU	24+00 - 33+49	898 SMU	
T1-1	637 lf	R	P2	519 lf	519 lf	1.0	519 SMU	40+00 - 45+19	519 SMU	
T1-2	604 lf	R	P2	841 lf	774 lf	1.0	774 SMU	45+19 - 53+60	774 SMU	
T1-3	1,932 lf	R	P2	2,010 lf	1,894 lf	1.0	1,894 SMU	53+60 - 73+70	1,894 SMU	
T1A-1	192 lf	R	P2	240 lf	240 lf	1.0	240 SMU	80+00 - 82+40	240 SMU	
T1A-2	533 lf	R	P2/P3	560 lf	506 lf	1.0	506 SMU	82+40 - 88+00	506 SMU	
T1B	1,102 lf	R	P2	1,100 lf	1,100 lf	1.0	1,100 SMU	100+00 - 111+00	1,100 SMU	
T2	1,879 lf	R	P3	1,833 lf	1,817 lf	1.0	1,817 SMU	120+00 - 138+33	1,817 SMU	
Mitigation Unit Summations										
Stream (lf)	Riparian Wetland (Ac)		Nonriparian Wetland (Ac)		Total Wetland (Ac)			Buffer (Ac)		
3,405			0		0			0		

R = Restoration

P2 = Priority 2

P2/P3 = Combination of Priorities 2 and 3

EI = Enhancement I

P3 = Priority 3

* These lengths have been calculated by excluding the easement exceptions, including ford and culvert crossings for the landowner and culverted crossings under private driveways.

Table 2. Project Activity and Reporting History		
Collins Creek Stream Restoration Site		
Activity or Report	Data Collection Complete	Completion or Delivery
Restoration Plan	2005 - 2006	Nov 07
Final Design	2005 - 2006	Nov 07
Construction	N/A	Apr 08
Planting	N/A	Mar 08
Mitigation Plan / As-Built (Year 0 Monitoring - Baseline)	May - July 08	Oct 08
Monitoring Year 01	Oct 08	Dec 08









Figure 2. Project Reaches

-  Project Easement
-  Easement Exceptions
-  Other Streams
-  Project Parcel Boundaries



1:7,200
1 inch equals 600 feet





*Image Source: Orange County Land Records/GIS
Orthoimagery 2003*



Table 3. Project Contact Table	
Collins Creek Stream Restoration Site	
Design Firm	KCI Technologies, Inc. Landmark Center II, Suite 220 4601 Six Forks Rd. Raleigh, NC 27609 Contact: Mr. Gary Mryncza Phone: (919) 783-9214 Fax: (919) 783-9266
Construction Contractor	Environmental Technologies and Construction Landmark Center II, Suite 220 4601 Six Forks Rd. Raleigh, NC 27609 Contact: Mr. Ryan McDavitt Phone: (919) 783-9214 Fax: (919) 783-9266
Planting Contractor	H & J Forest Services PO Box 458 Holly Ridge, NC 28445 Phone: (910) 512-6754
Monitoring Performers	
MY-00 - MY-05	KCI Associates of NC Landmark Center II, Suite 220 4601 Six Forks Rd. Raleigh, NC 27609 Contact: Mr. Adam Spiller Phone: (919) 783-9214 Fax: (919) 783-9266

Table 4. Project Background Table Collins Creek Stream Restoration Site	
Project County	Orange County
Physiographic Region	Piedmont
Ecoregion	Carolina Slate Belt
Project River Basin	Cape Fear
USGS HUC for Project and Reference	03030002050060 (UT to Collins Creek) 03030002050060 (Collins Creek - reference) 03040103050050 (UT Back Creek - reference) 03030002060110 (Long Branch - reference) 03030003050010 (UT to Richland Creek - ref) 03040101090010 (UT Fisher River - reference)
NCDWQ Sub-basin for Project and Reference	03-06-04 (UT to Collins Creek) 03-06-04 (Collins Creek - reference) 03-07-09 (UT Back Creek - reference) 03-06-05 (Long Branch - reference) 03-06-10 (UT to Richland Creek - reference) 03-07-02 (UT Fisher River - reference)
Drainage Area	2.6 sq. mi.
Stream Order	First, Second, and Third Order
Watershed Type (Rural, Urban, Developing, etc.)	Rural
Watershed LULC Distribution	Urban 1% Ag-Row Crop 5% Ag-Livestock 5% Forested 88% Water/Wetlands 1%
Watershed impervious cover (%)	3%
Rosgen Classification of As-built (Stream)	C4 (UTCC, T1, T1A-1, T1B) B4c (T2)
NCDWQ Classification for Project	Class C, NSW
Within EEP Watershed Plan?	No
Any portion of the project segment upstream of a 303d listed segment?	Yes
Reasons for 303d Listing or Stressor	biological integrity impaired, potentially due to agriculture
Total project acreage of easement	27.8 Acres
Total planted acreage	23.0 Acres
WRC Class (Warm, Cool, Cold)	warm
Species of concern, endangered etc.	none
Pre-construction Beaver activity?	Historically, according to landowner
Dominant Soil Types	Congaree fine sandy loam series
% of Project Easement Fenced	80%



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	


SYMBOL	DESCRIPTION	DATE	APPROVED

SYMBOL	DESCRIPTION	DATE	APPROVED


KCI
TECHNOLOGIES
ENGINEERS • PLANNERS • SCIENTISTS
4601 SIX FORKS ROAD
RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
STREAM RESTORATION PROJECT**
CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
UTCC-1 & 2: STA. 10+00 - 21+90, T1-3: STA. 67+60 - 73+70

DATE: DECEMBER 2008
SCALE: 1"=40'
**MONITORING
PLAN VIEW**
SHEET 1 OF 8



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	



SEE SHEETS 7 -8 FOR TRIBUTARY #2

MATCHLINE - SEE SHEET 1


SYL	DESCRIPTION	DATE	APPROVED

SYL	DESCRIPTION	DATE	APPROVED

KCI
TECHNOLOGIES
ENGINEERS • PLANNERS • SCIENTISTS
4601 SIX FORKS ROAD
RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
STREAM RESTORATION PROJECT**
CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
UTCC-2 AND UTCC-3: STATION 21+90 TO STATION 33+50

DATE: DECEMBER 2008
SCALE: 1"=40'
**MONITORING
PLAN VIEW**
SHEET 2 OF 8



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	


SYMBOL	DESCRIPTION	DATE	APPROVED

COLLINS CREEK
STREAM RESTORATION PROJECT
CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
T1-1 AND T1-2: STATION 40+00 TO STATION 54+10


KCI
TECHNOLOGIES
ENGINEERS • PLANNERS • SCIENTISTS
4601 SIX FORKS ROAD
RALEIGH, NORTH CAROLINA 27609

DATE: DECEMBER 2008
SCALE: 1"=40'

MONITORING PLAN VIEW



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	



SYMBOL	DESCRIPTION	DATE	APPROVED

VEG PLOT #2

CROSS-SECTION #9

CROSS-SECTION #10

END T1 PROFILE

VEG PLOT #3

KCI
TECHNOLOGIES

ENGINEERS • PLANNERS • SCIENTISTS

4601 SIX FORKS ROAD
RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
STREAM RESTORATION PROJECT**

CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA


T1-3: STATION 54+10 TO STATION 67+60

DATE: DECEMBER 2008


SCALE: 1"=40'

**MONITORING
PLAN VIEW**

SHEET 4 OF 8



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	




SYMBOL	DESCRIPTION	DATE	APPROVED

REVISIONS

KCI
 TECHNOLOGIES
 ENGINEERS • PLANNERS • SCIENTISTS
 4601 SIX FORKS ROAD
 RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
 STREAM RESTORATION PROJECT**
 CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
 T1B: STATION 100+00 TO STATION 111+00

DATE: DECEMBER 2008
 SCALE: 1"=40'
**MONITORING
 PLAN VIEW**
 SHEET 6 OF 8




MATCHLINE - SEE SHEET 7

SEE SHEETS 1-2 FOR MAIN CHANNEL

SEE SHEETS 1 - 2 FOR MAIN CHANNEL

ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	



SYMBOL	DESCRIPTION	DATE	APPROVED

REVISIONS

KCI
TECHNOLOGIES
ENGINEERS • PLANNERS • SCIENTISTS
4601 SIX FORKS ROAD
RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
STREAM RESTORATION PROJECT**
CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
T2: STATION 129+12 TO STATION 138+33

DATE: DECEMBER 2008
SCALE: 1"=40'
**MONITORING
PLAN VIEW**
SHEET 8 OF 8

2.0 PROJECT CONDITIONS AND MONITORING RESULTS

2.1 Vegetation Assessment

The planted vegetation on the site is growing well. Due to the baseline vegetation monitoring occurring while the plants had not yet leafed out, some of the plants could not be identified initially and they were recorded as unknown. During the first year of monitoring, most of these plants were identified. Some of the previously unknown plants were dead, damaged, or missing and could not be identified during the first year monitoring. These plants were again recorded as unknown.

The floodplain, stream banks, and riparian buffer have isolated areas with sparse vegetation, but overall they are well vegetated. Some scattered populations of invasive species have been identified in the floodplain and surrounding areas, which included Chinese privet (*Ligistrum sinense*) and tropical soda apple (*Solanum viarum*). Asian dayflower (*Murdannia keisak*) was present within the channel in UTCC-3 and other isolated areas. Although they are not a problem at this time, these populations will continue to be monitored to determine if invasive control is required in the future.

The monitored vegetation plots within the stream revealed that the planted vegetation is growing well with an average of 706 stems/acre. The overall vegetation assessment found the site to be on track to meeting the vegetative success criteria. The vegetative monitoring results are displayed in Appendix A and the Current Conditions Plan View in Appendix C.

2.2 Stream Assessment

During the 2008 growing season, the flow in UTCC-3 was impeded by a debris blockage at the downstream limits of the site. The slow moving water allowed emergent vegetation to become established in the channel of this reach. The blockage has been removed and the location will continue to be monitored. The on-site stream gauge recorded five bankfull events throughout the growing season.

The stream assessment found the stream to be stable overall. Periods of high flow caused isolated bed degradation in T1A-1 and T1A-2. One of these areas is visible on the longitudinal profile of T1A. Overland flow has caused scour on the floodplain on the left side of T1B. It is expected that this issue will stabilize as vegetation becomes established on the floodplain. The rest of the project's stream banks, streambed, and floodplain have experienced little to no erosion throughout the project. The structures are performing well and as designed. The bed degradation will continue to be monitored to determine if corrective action are necessary.

The stream assessment monitoring is described in Appendix B and the Current Conditions Plan View in Appendix C.

2.2.1 Bankfull Events

Table 5. Verification of Bankfull Events			
Project Name: Collins Creek			
Date of Data Collection	Date of Occurrence	Method	Photo Number
10/1/08	7/5/2008	Stream Gauge	N/A
10/1/08	8/27/2008	Stream Gauge	N/A
10/1/08	9/6/2008	Stream Gauge	AP-1
10/1/08	9/10/2008	Stream Gauge	N/A
10/1/08	9/16/2008	Stream Gauge	N/A

2.2.2

Quantitative Measures Summary Tables

Table 6a. UTCC-1&2 Baseline Stream Summary
Collins Creek Stream Restoration Site

Parameter	Pre-Existing Condition					Reference Reach(es) Data					Design			As-built			
	Min	Mean	Med	Max	n	Min	Mean	Med	Max	n	Min	Max	Min	Max	Mean	Max	n
Dimension - Riffle																	
Bankfull Width (ft)	15.4	16.0		16.5	2	11.9	16		20.1	2	24.0			21.2		1	
Floodprone Width (ft)	>54			>55	2		>60			1	54			>65		1	
Bankfull Mean Depth (ft)	2.4	2.8		3.1	2	1.7	2.2		2.7	2	2.0			2.0		1	
Bankfull Max Depth (ft)	3.3	4.0		4.6	2	3.3	3.8		4.2	2	2.9			3.1		1	
Bankfull Cross-Sectional Area (ft ²)	40.4	43.8		47.1	2	32.4	32.9		33.4	2	47.0			42.5		1	
Width/Depth Ratio	5.0	6.0		6.9	2	4.4	16.5		12.1	2	12.0			10.6		1	
Entrenchment Ratio	>3.3			>3.5	2		>3			1	2.3			>3.1		1	
Bank Height Ratio	1.0	1.0		1.0	2	1	1.1		1.1	2	1.0			1.0		1	
Pattern																	
Channel Beltwidth (ft)	55			136		50			60		59	120	47			130	
Radius of Curvature (ft)	18			38		24			31		28	62	25			70	
Rc:Bankfull width (ft/ft)	1.1			2.5		1.2			2.6		1.2	2.6	1.2			3.3	
Meander Wavelength (ft)	79			286		77			138		91	275	70			270	
Meander Width Ratio	3.3			8.8		2.5			5.0		2.5	5.0	2.2			6.2	
Profile																	
Riffle Length (ft)															27	55	82
Riffle Slope (ft/ft)						0.0030			0.0080		0.0020	0.0050	0.0009		0.0019	0.0037	5
Pool Length (ft)						13			21		11	32	11		38	57	8
Pool Spacing (ft)						32			80		40	200	88		139	175	7
Substrate and Transport Parameters																	
SC% / Sa% / G% / C% / B% / Be%	48% / 17% / 30% / 5% / 0% / 0%					0% / 52% / 48% / 0% / 0% / 0%					7% / 57% / 32% / 3% / 0% / 1%						
d16 / d35 / d50 / d84 / d95 (mm)	0.062 / 0.06 / 0.1 / 20 / 61					0.656 / 1.17 / 1.9 / 16 / 26					0.12 / 0.28 / 0.42 / 11 / 45						
Additional Reach Parameters																	
Channel length (ft)				1,409			304					1,391			1,400		
Drainage Area (SM)				2.51			1.68					2.51			2.51		
Rosgen Classification				E4			C4/E4					C4			C4		
Sinuosity				1.27			1.25					1.25			1.28		
Water Surface Slope (ft/ft)				0.0020			0.0030					0.0019			0.0015		

**Table 6b. UTCC-3 Baseline Stream Summary
Collins Creek Stream Restoration Site**

Parameter	Pre-Existing Condition					Reference Reach(es) Data					Design			As-built			
	Min	Mean	Med	Max	n	Min	Mean	Med	Max	n	Min	Mean	Max	Min	Mean	Max	n
Dimension - Riffle																	
Bankfull Width (ft)	20.5				1	11.9	16		20.1	2	25.0			25.5	26.3	27.0	2
Floodprone Width (ft)	>60				1		>60			1	55			>74	>75	>76	2
Bankfull Mean Depth (ft)	2.4				1	1.7	2.2		2.7	2	2.0			1.9	2.0	2.1	2
Bankfull Max Depth (ft)	3.5				1	3.3	3.8		4.2	2	2.9			2.8	3.1	3.3	2
Bankfull Cross-Sectional Area (ft ²)	49.7				1	32.4	32.9		33.4	2	49.5			48.0	51.8	55.5	2
Width/Depth Ratio	8.5				1	4.4	16.5		12.1	2	12.5			13.1	13.3	13.5	2
Entrenchment Ratio	>2.9				1		>3			1	2.3			>2.7	>2.9	>3.0	2
Bank Height Ratio	1.1				1	1	1.1		1.1	2	1.0			1.0	1.0	1.0	2
Pattern																	
Channel Beltwidth (ft)	53			73		50			60		85		100	85		100	
Radius of Curvature (ft)	16			126		24			31		40		70	40		70	
Rc:Bankfull width (ft/ft)	0.8			6.1		1.2			2.6		1.6		2.8	1.5		2.7	
Meander Wavelength (ft)	96			164		77			138		205		260	205		260	
Meander Width Ratio	2.6			3.6		2.5			5.0		3.4		4.0	3.2		3.8	
Profile																	
Riffle Length (ft)														27	55	82	5
Riffle Slope (ft/ft)						0.0030			0.0080		0.0020		0.0050	0.0009	0.0019	0.0037	5
Pool Length (ft)						13			21		35		56	11	38	57	8
Pool Spacing (ft)						32			80		115		165	88	139	175	7
Substrate and Transport Parameters																	
SC% / Sa% / G% / C% / B% / Be%	48% / 17% / 30% / 5% / 0% / 0%					0% / 52% / 48% / 0% / 0% / 0%								21% / 45% / 31% / 2% / 0% / 0%			
d16 / d35 / d50 / d84 / d95 (mm)	0.062 / 0.06 / 0.1 / 20 / 61					0.656 / 1.17 / 1.9 / 16 / 26								0.062 / 0.11 / 0.32 / 17 / 35			
Additional Reach Parameters																	
Channel length (ft)	1,034					304					956			949			
Drainage Area (SM)	2.62					1.68					2.62			2.62			
Rosgen Classification	C4/E4					C4/E4					C4			C4			
Sinuosity	1.17					1.25					1.20			1.15			
Water Surface Slope (ft/ft)	0.0020					0.0030					0.0019			0.0017			

**Table 6c. T1-1 Baseline Stream Summary
Collins Creek Stream Restoration Site**

Parameter	Pre-Existing Condition				Reference Reach(es) Data				Design				As-built			
	Min	Mean	Med	Max	n	Min	Mean	Med	Max	n	Min	Mean	Max	Min	Max	n
Dimension - Riffle																
Bankfull Width (ft)	5.8	7.8	7.3	10.8	4	10.4	13.3		16.1	2	10.4				11.1	1
Floodprone Width (ft)	10			>38	4		150			2	>37				41.3	1
Bankfull Mean Depth (ft)	1.1	1.2	1.2	1.5	4	0.9	1.1		1.2	2	0.8				0.8	1
Bankfull Max Depth (ft)	1.6	2.0	2.0	2.3	4	1.4	1.6		1.7	2	1.2				1.3	1
Bankfull Cross-Sectional Area (ft ²)	8.6	8.9	8.8	9.3	4	12.5	13.5		14.4	2	8.2				8.4	1
Width/Depth Ratio	3.9	7.3	5.4	9.8	4	11.6	12.5		13.4	2	13.3				14.7	1
Entrenchment Ratio	1.0			>6.5	4	9.3	11.9		14.4	2	>3.6				3.7	1
Bank Height Ratio	2.0	2.2	2.2	2.4	4	1.0	1.1		1.1	2	1.0				1.0	1
Pattern																
Channel Beltwidth (ft)	44			78		135					20		50	25		40
Radius of Curvature (ft)	18			110		15			26		20		30	20		30
Rc: Bankfull width (ft/ft)	1.7			19.0		1.4			1.6		2.0		3.0	1.8		2.7
Meander Wavelength (ft)	135			250		70			120		70		125	75		115
Meander Width Ratio	4.1			13.4		10.2			13.0		2.0		5.0	2.3		10.4
Profile																
Riffle Length (ft)														19	41	83
Riffle Slope (ft/ft)	0.044					0.010			0.040		0.010		0.012	0.0039	0.0111	0.0214
Pool Length (ft)	10			20		31			108		10		30	8	22	44
Pool Spacing (ft)	32			43		43			181		40		90	48	88	169
Substrate and Transport Parameters																
SC% / Sa% / G% / C% / B% / Be%	31% / 31% / 37% / 0% / 0% / 0%					0% / 0% / 52% / 42% / 0% / 6%								8% / 20% / 72% / 0% / 0% / 0%		
d16 / d35 / d50 / d84 / d95 (mm)	0.062 / 0.14 / 0.24 / 12 / 21					12.3 / 35.5 / 53.7 / 114 / 172								0.41 / 3.2 / 7.4 / 20 / 27		
Additional Reach Parameters																
Channel length (ft)			637				712						595		519	
Drainage Area (SM)			0.12				0.63						0.12		0.12	
Rosgen Classification			G4c/E4				E4/C4						C4		C4	
Sinuosity			1.15				>1.5						1.25		1.15	
Water Surface Slope (ft/ft)			0.0073				0.0068						0.0075		0.0084	

**Table 6d. T1-2 Baseline Stream Summary
Collins Creek Stream Restoration Site**

Parameter	Pre-Existing Condition						Reference Reach(es) Data						Design			As-built		
	Min	Mean	Med	Max	n		Min	Mean	Med	Max	n	Min	Max	Min	Mean	Max	n	
Dimension - Riffle																		
Bankfull Width (ft)	5.7	7.9		10.1	2		10.4	13.3		16.1	2	12.0			11.7		1	
Floodprone Width (ft)	11.1	13.5		16.0	2			15.0			2	>40			41.6		1	
Bankfull Mean Depth (ft)	1.1	1.3		1.4	2		0.9	1.1		1.2	2	0.9			1.0		1	
Bankfull Max Depth (ft)	1.4	1.6		1.8	2		1.4	1.6		1.7	2	1.4			1.5		1	
Bankfull Cross-Sectional Area (ft ²)	8.2	9.5		10.8	2		12.5	13.5		14.4	2	11.2			11.5		1	
Width/Depth Ratio	4.1	6.7		9.2	2		11.6	12.5		13.4	2	13.3			11.9		1	
Entrenchment Ratio	1.1	2.0		2.8	2		9.3	11.9		14.4	2	>3.3			3.6		1	
Bank Height Ratio	2.0	2.1		2.1	2		1.0	1.1		1.1	2	1.0			1.0		1	
Pattern																		
Channel Beltwidth (ft)	42			83			135					40					66	
Radius of Curvature (ft)	17			34			15			26		20					30	
Rc: Bankfull width (ft/ft)	1.7			6			1.4			1.6		1.7					1.8	
Meander Wavelength (ft)	106			148			70			120		80					175	
Meander Width Ratio	4.2			14.6			10.2			13.0		3.3					4.0	
Substrate and Transport Parameters																		
Riffle Length (ft)															19	41	83	
Riffle Slope (ft/ft)	0.006			0.009			0.010			0.040		0.005			0.0111		0.0214	
Pool Length (ft)	7						31			108		12			22		44	
Pool Spacing (ft)							43			181		40			88		169	
Additional Reach Parameters																		
SC% / Sa% / G% / C% / B% / Be%	29% / 42% / 30% / 0% / 0% / 0%						0% / 0% / 52% / 42% / 0% / 6%						13% / 64% / 23% / 0% / 0% / 0%					
d16 / d35 / d50 / d84 / d95 (mm)	0.062 / 0.15 / 0.2 / 9 / 17						12.3 / 35.5 / 53.7 / 114 / 172						0.07 / 0.14 / 0.29 / 8.6 / 15					
Additional Reach Parameters																		
Channel length (ft)	604						712						767					
Drainage Area (SM)	0.18						0.63						0.18					
Rosgen Classification	G4c/E4						E4/C4						C4					
Sinuosity	1.21						>1.5						1.23					
Water Surface Slope (ft/ft)	0.0075						0.0068						0.0059					

**Table 6c. T1-3 Baseline Stream Summary
Collins Creek Stream Restoration Site**

Parameter	Pre-Existing Condition						Reference Reach(es) Data						Design										
	Min	Mean	Med	Max	n		Min	Mean	Med	Max	n		Min	Mean	Max	n							
Dimension - Riffle																							
Bankfull Width (ft)	7.7	10.2	10.9	11.9	3		14.8	16.8	18.8	2			15.0	17.8	20.8	2							
Floodprone Width (ft)	>55		>63	>70	3				>40	2			>40	57	65	2							
Bankfull Mean Depth (ft)	1.3	1.5	1.3	2.0	3		1.3	1.6	1.8	2			1.1	1.0	1.0	2							
Bankfull Max Depth (ft)	2.5	2.6	2.6	2.7	3		1.9	2.2	2.4	2			1.6	1.7	1.9	2							
Bankfull Cross-Sectional Area (ft ²)	14.5	15.0	15.1	15.5	3		25	25.1	25.1	2			16.9	17.2	20.0	2							
Width/Depth Ratio	3.9	7.2	8.2	9.4	3		8.8	11.3	13.8	2			13.3	18.5	21.6	2							
Entrenchment Ratio	>5.0		>5.9	>8.2	3				>2.5	2			>2.5	3.2	3.3	2							
Bank Height Ratio	1.2	1.2	1.2	1.3	3		1.2	1.4	1.5	2			1.0	1.0	1.0	2							
Pattern																							
Channel Beltwidth (ft)	39			86					60				30		75	85							
Radius of Curvature (ft)	14			55			16		87				30		70	60							
Re:Bankfull width (ft/ft)	1.2			7.1			0.9		5.9				2.0		4.7	3.4							
Meander Wavelength (ft)	60			476			66		191				115		250	240							
Meander Width Ratio	3.3			11.2					4.1				2.0		5.0	4.8							
Profile																							
Riffle Length (ft)															19	41	83						
Riffle Slope (ft/ft)			0.011				0.013		0.035				0.007	0.009	0.011	0.0214	13						
Pool Length (ft)	8			16			14		33				16	55	8	44	13						
Pool Spacing (ft)	23			100			50		105				70	140	48	169	12						
Substrate and Transport Parameters																							
SC% / Sa% / G% / C% / B% / Be%	56%	30%	14%	0%	0%		1%	27%	73%	0%	0%						5%	63%	31%	1%	0%	0%	
d16 / d35 / d50 / d84 / d95 (mm)	0.062	0.06	0.06	1.3	9.5		0.73	2.7	4.6	9.2	15							0.13	0.29	0.43	12	30	
Additional Reach Parameters																							
Channel length (ft)		1,932						432						2,010									
Drainage Area (SM)		0.49						1.49						0.49									
Rosgen Classification		E4						C4						C4									
Sinuosity		1.19												1.14									
Water Surface Slope (ft/ft)		0.0052						0.0099						0.0050									

**Table 6g. T1A-2 Baseline Stream Summary
Collins Creek Stream Restoration Site**

Parameter	Pre-Existing Condition					Reference Reach(es) Data					Design			As-built			
	Min	Mean	Med	Max	n	Min	Mean	Med	Max	n	Min	Max	Mean	Min	Max	Mean	n
Dimension - Riffle																	
Bankfull Width (ft)			4.5		1	9.0	9.5		10.0	2	7.6		9.7			9.7	1
Floodprone Width (ft)			6.7		1	13	17		20	2	15		>40			>40	1
Bankfull Mean Depth (ft)			1.2		1	1.1	1.2		1.2	2	0.8		0.5			0.5	1
Bankfull Max Depth (ft)			1.6		1	1.3	1.4		1.5	2	1.0		1.0			1.0	1
Bankfull Cross-Sectional Area (ft ²)			5.5		1	10.4	10.6		10.7	2	6.0		5.2			5.2	1
Width/Depth Ratio			3.8		1	8.0	9.0		10.0	2	9.6		18.1			18.1	1
Entrenchment Ratio			1.5		1	1.3	1.8		2.3	2	2.0		>4			>4	1
Bank Height Ratio			2.3		1			1.0		2	1.0		1.0			1.0	1
Pattern																	
Channel Beltwidth (ft)								45			34	38		30			60
Radius of Curvature (ft)						13			42		10	33		20			30
Rc:Bankfull width (ft/ft)						1.3			4.4		1.3	4.4		2.5			3.8
Meander Wavelength (ft)						93			136		68	114		90			150
Meander Width Ratio						4.5			5.0		4.5	5.0		3.8			7.6
Profile																	
Riffle Length (ft)														9	27		5
Riffle Slope (ft/ft)	0.019			0.077		0.013			0.028		0.016	0.035		N/A*	N/A*	N/A*	-
Pool Length (ft)	4		9			3			25		9	26		2	6		6
Pool Spacing (ft)	8		34			30			59		40	104		8	49		5
Substrate and Transport Parameters																	
SC% / Sa% / G% / C% / B% / Be%	7% / 19% / 57% / 4% / 0% / 13%					0% / 15% / 78% / 7% / 0% / 0%								32% / 58% / 10% / 0% / 0% / 0%			
d16 / d35 / d50 / d84 / d95 (mm)	0.564 / 5.31 / 9.9 / 35 / 62					2.0 / 4.2 / 6.9 / 30 / 70								0.062 / 0.071 / 0.14 / 0.48 / 1.1			
Additional Reach Parameters																	
Channel length (ft)		533				297						565				560	
Drainage Area (SM)		0.05				0.38						0.05				0.05	
Rosgen Classification		G4				B4c						B4c				C4/B4c	
Sinuosity		1.05				1.20						1.15				1.17	
Water Surface Slope (ft/ft)		0.0218				0.0130						0.0160				0.0135	

*Riffle slope not available, stream was dry when survey was completed.

Table 6h. T1B Baseline Stream Summary Collins Creek Stream Restoration Site																	
Parameter	Pre-Existing Condition					Reference Reach(es) Data					Design			As-built			
	Min	Mean	Med	Max	n	Min	Mean	Med	Max	n	Min	Max	Mean	Max	n		
Dimension - Riffle																	
Bankfull Width (ft)	5.9	6.0		6.0	2	10.4	13.3		16.1	2	10.4		11.1		1		
Floodprone Width (ft)			>70		2		150	150		2	>37		43		1		
Bankfull Mean Depth (ft)	1.4	1.6		1.7	2	0.9	1.1		1.2	2	0.8		0.8		1		
Bankfull Max Depth (ft)	2.0	2.1		2.1	2	1.4	1.6		1.7	2	1.2		1.4		1		
Bankfull Cross-Sectional Area (ft ²)	8.4	9.2		9.9	2	12.5	13.5		14.4	2	8.2		8.4		1		
Width/Depth Ratio	3.5	3.9		4.3	2	11.6	12.5		13.4	2	13.3		14.7		1		
Entrenchment Ratio			>11.7		2	9.3	11.9		14.4	2	>3.6		3.8		1		
Bank Height Ratio	1.0	1.4		1.7	2	1	1.1		1.1	2	1.0		1.0		1		
Pattern																	
Channel Beltwidth (ft)			110					135			30	80		25		70	
Radius of Curvature (ft)	54			125		14			25		20	40		20		40	
Rc:Bankfull width (ft/ft)	9			21.2		1.4			1.6		1.9	3.8		1.9		3.8	
Meander Wavelength (ft)			400			70			120		110	150		120		160	
Meander Width Ratio	18.3			18.6		10.2			13.0		2.9	7.7		2.4		6.7	
Profile																	
Riffle Length (ft)													49	42		55	
Riffle Slope (ft/ft)	0.0060			0.0080		0.0100			0.0400		0.0080	0.0200	0.0141	0.0059	0.0141	0.0219	
Pool Length (ft)	9			17		31			108		12	35	20	14	20	29	
Pool Spacing (ft)	13			18		43.5			181		61	111	86	80	86	93	
Substrate and Transport Parameters																	
SC% / Sa% / G% / C% / B% / Be%	8% / 66% / 26% / 0% / 0% / 0%					0% / 0% / 52% / 42% / 0% / 6%											17% / 60% / 23% / 0% / 0% / 0%
d16 / d35 / d50 / d84 / d95 (mm)	0.151 / 0.23 / 0.4 / 7 / 28					12.3 / 35.5 / 53.7 / 114 / 172											0.062 / 0.11 / 0.22 / 5.5 / 9.2
Additional Reach Parameters																	
Channel length (ft)	1,102						712						1,134				1,100
Drainage Area (SM)	0.24						0.63						0.24				0.24
Rosgen Classification	E4						C4						C4				C4
Sinuosity	1.12						>1.50						1.20				1.18
Water Surface Slope (ft/ft)	0.0084						0.0070						0.0077				0.0083

Table 6i. T2 Baseline Stream Summary Collins Creek Stream Restoration Site														
Parameter	Pre-Existing Condition				Reference Reach(es) Data				Design		As-built			
	Min	Mean	Med	Max	n	Min	Mean	Med	Max	n	Min	Mean	Max	n
Dimension - Riffle														
Bankfull Width (ft)	4.2	5.5	5.4	7.2	4	7.7	7.9	7.7	8.3	3	7.0	7.4		1
Floodprone Width (ft)	8	13	9	28	4	13	15	16	16	3	13	14		1
Bankfull Mean Depth (ft)	0.9	1.0	1.0	1.1	4	0.7	0.8	0.8	0.9	3	0.6	0.7		1
Bankfull Max Depth (ft)	1.3	1.4	1.5	1.5	4	1.1	1.3	1.3	1.4	3	1.0	1.2		1
Bankfull Cross-Sectional Area (ft ²)	4.0	5.3	5.4	6.4	4	6.1	6.4	6.2	7.0	3	4.8	5.2		1
Width/Depth Ratio	3.8	5.8	5.6	8.0	4	8.5	9.8	9.6	11.4	3	11.0	10.5		1
Entrenchment Ratio	1.3	2.4	1.8	4.6	4	1.6	1.9	2.1	2.1	3	1.9	1.8		1
Bank Height Ratio	1.3	2.1	2.3	2.8	4						1.0	1.0		1
Pattern														
Channel Beltwidth (ft)	22			50				22			14	20	25	40
Radius of Curvature (ft)	14			78		11			23		7	21	10	20
Rc:Bankfull width (ft/ft)	1.9			18.7		1.0			3.0		1.0	3.0	1.4	2.7
Meander Wavelength (ft)	50			306		49			59		32	54	50	65
Meander Width Ratio	3.1			15.0		2.0			2.9		2.0	2.9	3.4	5.4
Profile														
Riffle Length (ft)													11	18
Riffle Slope (ft/ft)	0.0160			0.0540		0.0250			0.0470		0.0170	0.0470	0.0186	0.0271
Pool Length (ft)	3			8		3			15		3	20	5	11
Pool Spacing (ft)	16			96		21			72		21	72	6	25
Substrate and Transport Parameters														
SC% / Sa% / G% / C% / B% / Be%	7% / 12% / 76% / 5% / 0% / 0%					1% / 27% / 64% / 6% / 1% / 0%					2% / 50% / 46% / 2% / 0% / 0%			
d16 / d35 / d50 / d84 / d95 (mm)	0.47 / 8.4 / 14 / 33 / 66					0.36 / 3.2 / 6.2 / 16 / 150					0.26 / 0.53 / 1.4 / 14 / 35			
Additional Reach Parameters														
Channel length (ft)		1,879					205				1,830			1,833
Drainage Area (SM)		0.07					0.16				0.07			0.07
Rosgen Classification		B4/E4/G4/G4c					B4c				B4/B4c			B4/B4c
Sinuosity		1.10-1.16					1.20				1.10-1.20			1.09
Water Surface Slope (ft/ft)		0.0147-0.0250					0.0120				0.0170-0.0250			0.0197

Table 7a. Morphology and Hydraulic Monitoring Summary
Project Name: Collins Creek

Parameter	Cross-Section 1 Riffle					Cross-Section 2 Pool					Cross-Section 3 Pool							
	UTCC-1					UTCC-1					UTCC-3							
	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5
Reach																		
Bankfull Width (ft)	21.2	21.9	>65	>65	43.6	2.0	2.0	3.1	3.1	10.6	11.0	>3.1	>3.0	1.0	1.0			
Floodprone Width (ft)	>65	>65	43.6	2.0	2.0	3.1	3.1	10.6	11.0	>3.1	>3.0	1.0	1.0					
Bankfull Cross-Sectional Area (ft ²)	21.2	21.9	>65	>65	43.6	2.0	2.0	3.1	3.1	10.6	11.0	>3.1	>3.0	1.0	1.0			
Bankfull Mean Depth (ft)	2.0	2.0	3.1	3.1	10.6	11.0	>3.1	>3.0	1.0	1.0								
Bankfull Max Depth (ft)	3.1	3.1	10.6	11.0	>3.1	>3.0	1.0	1.0										
Width/Depth Ratio	10.6	11.0	>3.1	>3.0	1.0	1.0												
Entrenchment Ratio	>3.1	>3.0	1.0	1.0														
Bank Height Ratio	1.0	1.0																
Substrate																		
d50 (mm)	0.4	0.2								0.4	7.7							
d84 (mm)	17.0	17.0								4.9	15.0							

Table 7b. Morphology and Hydraulic Monitoring Summary continued
Project Name: Collins Creek

Parameter	Cross-Section 4 Riffle					Cross-Section 5 Riffle					Cross-Section 6 Riffle							
	UTCC-3					UTCC-3					T1-1							
	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5
Reach																		
Bankfull Width (ft)	25.5	25.9	>76	>76	46.2	48.0	1.9	1.8	2.8	2.7	13.5	14.5	>3.0	>3.0	1.0	1.0		
Floodprone Width (ft)	>76	>76	46.2	48.0	1.9	1.8	2.8	2.7	13.5	14.5	>3.0	>3.0	1.0	1.0				
Bankfull Cross-Sectional Area (ft ²)	25.5	25.9	>76	>76	46.2	48.0	1.9	1.8	2.8	2.7	13.5	14.5	>3.0	>3.0	1.0	1.0		
Bankfull Mean Depth (ft)	1.9	1.8	2.8	2.7	13.5	14.5	>3.0	>3.0	1.0	1.0								
Bankfull Max Depth (ft)	2.8	2.7	13.5	14.5	>3.0	>3.0	1.0	1.0										
Width/Depth Ratio	13.5	14.5	>3.0	>3.0	1.0	1.0												
Entrenchment Ratio	>3.0	>3.0	1.0	1.0														
Bank Height Ratio	1.0	1.0																
Substrate																		
d50 (mm)	1.3	0.06								0.2	0.06							
d84 (mm)	24.0	11.0								1.0	9.2							

Table 7c. Morphology and Hydraulic Monitoring Summary continued

Project Name: Collins Creek

Parameter	Cross-Section 7 Riffle						Cross-Section 8 Pool					Cross-Section 9 Riffle						
	T1-2						T1-2					T1-3						
	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5
Reach																		
Bankfull Width (ft)	11.7	12.4					13.1	13.4					20.8	24.3				
Floodprone Width (ft)	42	42					-	-					>65	>65				
Bankfull Cross-Sectional Area (ft ²)	11.5	12.4					10.9	10.5					20.0	19.3				
Bankfull Mean Depth (ft)	1.0	1.0					0.8	0.8					1.0	0.8				
Bankfull Max Depth (ft)	1.5	1.7					1.8	1.7					1.9	2.0				
Width/Depth Ratio	11.9	12.4					-	-					21.6	30.6				
Entrenchment Ratio	3.6	3.4					-	-					>3.1	>3.0				
Bank Height Ratio	1.0	1.0					-	-					1.0	1.0				
Substrate																		
d50 (mm)	0.8	0.3					0.1	0.08					1.3	8.6				
d84 (mm)	13.0	15.0					0.3	0.3					24.0	21.0				

Table 7d. Morphology and Hydraulic Monitoring Summary continued

Project Name: Collins Creek

Parameter	Cross-Section 10 Pool						Cross-Section 11 Riffle					Cross-Section 12 Riffle						
	T1-3						T1-3					T1A-1						
	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5
Reach																		
Bankfull Width (ft)	22.3	21.6					14.8	14.6					7.9	7.7				
Floodprone Width (ft)	-	-					49	46					>40	>40				
Bankfull Cross-Sectional Area (ft ²)	31.4	30.8					14.3	11.3					2.5	1.7				
Bankfull Mean Depth (ft)	1.4	1.4					1.0	0.8					0.3	0.2				
Bankfull Max Depth (ft)	2.9	3.1					1.4	1.2					0.6	0.5				
Width/Depth Ratio	-	-					15.3	19.0					25.0	34.9				
Entrenchment Ratio	-	-					3.3	3.2					>5.1	>5.0				
Bank Height Ratio	-	-					1.0	1.0					1.0	1.0				
Substrate																		
d50 (mm)	0.2	0.6					0.7	12.0					0.1	0.1				
d84 (mm)	0.5	7.5					9.5	23.0					0.2	0.1				

Table 7e. Morphology and Hydraulic Monitoring Summary continued

Project Name: Collins Creek

Parameter	Cross-Section 13 Riffle					Cross-Section 14 Riffle					Cross-Section 15 Pool							
	T1A-2					T1A-2					T2							
	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5	MY0	MY1	MY2	MY3	MY4	MY5
Dimension																		
Bankfull Width (ft)	9.7	9.7					11.1	11.0										
Floodprone Width (ft)	>40	>40					43	53										
Bankfull Cross-Sectional Area (ft ²)	5.2	6.3					8.4	9.1										
Bankfull Mean Depth (ft)	0.5	0.6					0.8	0.8										
Bankfull Max Depth (ft)	0.9	1.2					1.4	1.5										
Width/Depth Ratio	18.1	14.9					14.7	13.3										
Entrenchment Ratio	>4.1	>4.0					3.8	4.8										
Bank Height Ratio	1.0	1.0					1.0	1.0										
Substrate																		
d50 (mm)	0.1	0.09					0.2	0.3										
d84 (mm)	0.5	0.1					5.5	6.3										

Table 7f. Morphology and Hydraulic Monitoring Summary continued

Project Name: Collins Creek

Parameter	Cross-Section 16 Riffle					
	T2					
	MY0	MY1	MY2	MY3	MY4	MY5
Dimension						
Bankfull Width (ft)	7.4	7.7				
Floodprone Width (ft)	13.5	14.4				
Bankfull Cross-Sectional Area (ft ²)	5.2	5.7				
Bankfull Mean Depth (ft)	0.7	0.7				
Bankfull Max Depth (ft)	1.2	1.3				
Width/Depth Ratio	10.5	10.4				
Entrenchment Ratio	1.8	1.9				
Bank Height Ratio	1.0	1.0				
Substrate						
d50 (mm)	0.9	9.3				
d84 (mm)	11.0	18.0				

Table 7g. Morphology and Hydraulic Monitoring Summary continued						
Project Name: Collins Creek						
Reach UTCC-1, 2, and 3						
Parameter	MY - 01 (2008)	MY - 02 (2009)	MY - 03 (2010)	MY - 04 (2011)	MY - 05 (2012)	
Profile						
Riffle Length (ft)	32	56	84			
Riffle Slope (ft/ft)		0.0013				
Pool Length (ft)	4	28	45			
Pool Spacing (ft)	29	121	158			
Additional Reach Parameters						
Water Surface Slope (ft/ft)	0.0008					
Rosgen Classification	C4					

* Pattern measurements will only be taken after MY-00 if it is visually apparent that the pattern has changed.

Table 7h. Morphology and Hydraulic Monitoring Summary continued						
Project Name: Collins Creek						
Reach T1-1, 2, and 3						
Parameter	MY - 01 (2008)	MY - 02 (2009)	MY - 03 (2010)	MY - 04 (2011)	MY - 05 (2012)	
Profile						
Riffle Length (ft)	13	32	79			
Riffle Slope (ft/ft)	0.0048	0.0168	0.0282			
Pool Length (ft)	7	25	43			
Pool Spacing (ft)	53	91	152			
Additional Reach Parameters						
Water Surface Slope (ft/ft)	0.0061					
Rosgen Classification	C4					

* Pattern measurements will only be taken after MY-00 if it is visually apparent that the pattern has changed.

Table 7i. Morphology and Hydraulic Monitoring Summary continued						
Project Name: Collins Creek						
Reach T1A-1, and 2						
Parameter	MY - 01 (2008)	MY - 02 (2009)	MY - 03 (2010)	MY - 04 (2011)	MY - 05 (2012)	
Profile						
Riffle Length (ft)	27	33	39			
Riffle Slope (ft/ft)	**	**	**			
Pool Length (ft)	6	9	12			
Pool Spacing (ft)	22	52	70			
Additional Reach Parameters						
Water Surface Slope (ft/ft)	N/A					
Rosgen Classification	C4					

* Pattern measurements will only be taken after MY-00 if it is visually apparent that the pattern has changed.

**Slope N/A due to no water in channel, riffles determined from profile

Table 7j. Morphology and Hydraulic Monitoring Summary continued						
Project Name: Collins Creek						
T1B						
Parameter	MY - 01 (2008)	MY - 02 (2009)	MY - 03 (2010)	MY - 04 (2011)	MY - 05 (2012)	
Profile						
Riffle Length (ft)	27	46	58			
Riffle Slope (ft/ft)	0.0086	0.0148	0.0239			
Pool Length (ft)	18	24	27			
Pool Spacing (ft)	79	86	93			
Additional Reach Parameters						
Water Surface Slope (ft/ft)	0.0079					
Rosgen Classification	C4					

* Pattern measurements will only be taken after MY-00 if it is visually apparent that the pattern has changed.

Table 7k. Morphology and Hydraulic Monitoring Summary continued
Project Name: Collins Creek

T2						
Reach		MY - 01 (2008)	MY - 02 (2009)	MY - 03 (2010)	MY - 04 (2011)	MY - 05 (2012)
Parameter						
Profile						
Riffle Length (ft)	17	28	45			
Riffle Slope (ft/ft)	0.0129	0.0251	0.0327			
Pool Length (ft)	6	14	25			
Pool Spacing (ft)	7	35	90			
Additional Reach Parameters						
Water Surface Slope (ft/ft)	0.02					
Rosgen Classification	B4c					

* Pattern measurements will only be taken after MY-00 if it is visually apparent that the pattern has changed.

Appendix A

Vegetation Data

Appendix A1: Vegetation Data

Table A1. Vegetation Metadata							
Project Name: Collins Creek							
Report Prepared By	Brian Roberts						
Date Prepared	10/28/2008 11:34						
Database Name	KCI_2008.mdb						
Database Location	M:\2007\12071067_2007 EEP OPEN END\Veg_database						
PROJECT SUMMARY-----							
Project Code	Project Name	Description	Length (ft)	Stream-to-Edge Width (ft)	Area (sq m)	Required Plots (calculated)	Sampled Plots
UTCC	Collins	This is a Full Delivery Stream Restoration in Orange County, North Carolina	6,808	50	63,242	15	15

Table A2. Vegetation Vigor by Species							
Project Name: Collins Creek							
	Species	4	3	2	1	0	Missing
	<i>Aronia arbutifolia</i>		11	7	9	2	
	<i>Betula nigra</i>	4	7	5	1		
	<i>Callicarpa americana</i>		2	2		1	
	<i>Carya ovata</i>		2	5	1		1
	<i>Cornus amomum</i>		8	9	3	5	1
	<i>Diospyros virginiana</i>	8	15	13	2		
	<i>Fraxinus pennsylvanica</i>		1	1			
	<i>Ilex decidua</i>		6	1	3		1
	<i>Ilex verticillata</i>			3	1		
	<i>Itea virginica</i>					1	2
	<i>Juglans nigra</i>	1	13	11	11	5	
	<i>Lindera benzoin</i>			1		2	
	<i>Platanus occidentalis</i>	14	7			1	
	<i>Quercus sp.</i>	4		2		5	1
	<i>Quercus falcata</i>	1	11	1	2	1	
	<i>Quercus michauxii</i>	2	1	3	2	1	
	<i>Quercus phellos</i>	1	3	1			
	<i>Salix nigra</i>	2		2	1		1
	<i>Salix sericea</i>		2	2		4	
	<i>Sambucus canadensis</i>		2	5	5	9	4
	<i>Symphoricarpos orbiculatus</i>	1	1	5			1
	Unknown	1		4	2	14	2
TOT:	22	39	92	83	43	51	14

Table A3. Damage by Species

Project Name: Collins Creek

	Species	All Damage Categories	(no damage)	Deer	Flood	Insects	Rodents
	<i>Aronia arbutifolia</i>	30	27	1	1	1	
	<i>Betula nigra</i>	17	16	1			
	<i>Callicarpa americana</i>	5	4	1			
	<i>Carya ovata</i>	9	9				
	<i>Cornus amomum</i>	29	28	1			
	<i>Diospyros virginiana</i>	38	38				
	<i>Fraxinus pennsylvanica</i>	2	2				
	<i>Ilex decidua</i>	11	11				
	<i>Ilex verticillata</i>	4	4				
	<i>Itea virginica</i>	3	3				
	<i>Juglans nigra</i>	41	40		1		
	<i>Lindera benzoin</i>	3	3				
	<i>Platanus occidentalis</i>	22	21				1
	<i>Quercus sp.</i>	12	12				
	<i>Quercus falcata</i>	16	15			1	
	<i>Quercus michauxii</i>	9	8	1			
	<i>Quercus phellos</i>	6	6				
	<i>Salix nigra</i>	6	6				
	<i>Salix sericea</i>	8	6	2			
	<i>Sambucus canadensis</i>	25	25				
	<i>Symphoricarpos orbiculatus</i>	8	8				
	Unknown	23	22		1		
TOT:	22	327	314	7	3	2	1

Table A4. Damage by Plot							
Project Name: Collins Creek							
	Plot	All Damage Categories	(no damage)	Deer	Flood	Insects	Rodents
	UTCC-A-0001-year:1	27	23	4			
	UTCC-A-0002-year:1	19	17			1	1
	UTCC-A-0003-year:1	17	15	1		1	
	UTCC-A-0004-year:1	16	14	2			
	UTCC-A-0005-year:1	28	28				
	UTCC-A-0006-year:1	19	16		3		
	UTCC-A-0007-year:1	17	17				
	UTCC-A-0008-year:1	27	27				
	UTCC-A-0009-year:1	17	17				
	UTCC-A-0010-year:1	31	31				
	UTCC-A-0011-year:1	26	26				
	UTCC-A-0012-year:1	27	27				
	UTCC-A-0013-year:1	18	18				
	UTCC-A-0014-year:1	21	21				
	UTCC-A-0015-year:1	17	17				
TOT:	15	327	314	7	3	2	1

Table A5. Stem Count by Plot and Species

Project Name: Collins Creek

	Species	Total Stems	# Plots	Avg # Stems	plot UTCC-A-0001-year:1	plot UTCC-A-0002-year:1	plot UTCC-A-0003-year:1	plot UTCC-A-0004-year:1	plot UTCC-A-0005-year:1	plot UTCC-A-0006-year:1	plot UTCC-A-0007-year:1	plot UTCC-A-0008-year:1	plot UTCC-A-0009-year:1	plot UTCC-A-0010-year:1	plot UTCC-A-0011-year:1	plot UTCC-A-0012-year:1	plot UTCC-A-0013-year:1	plot UTCC-A-0014-year:1	plot UTCC-A-0015-year:1
	<i>Aronia arbutifolia</i>	28	8	3.50	1	4	4	2	6	7	2					2			
	<i>Betula nigra</i>	17	8	2.12	2	6	1		3	1	1				2	1			
	<i>Callicarpa americana</i>	4	2	2.00				3			1								
	<i>Carya ovata</i>	8	5	1.60				1					1	1	2		3		
	<i>Cornus amomum</i>	23	7	3.29	3			3	6			5	1	3				2	
	<i>Diospyros virginiana</i>	38	11	3.45		3	5		3			1	1	3	8	7	2	3	2
	<i>Fraxinus pennsylvanica</i>	2	2	1.00						1	1								
	<i>Ilex decidua</i>	10	6	1.67						2	1	2	1	3	1				
	<i>Ilex verticillata</i>	4	4	1.00		1	1				1					1			
	<i>Juglans nigra</i>	36	9	4.00						1		5	11	3	3	3	4	2	4
	<i>Lindera benzoin</i>	1	1	1.00			1												
	<i>Platanus occidentalis</i>	21	8	2.62	2	4		1	2	3	4				1	4			
	<i>Quercus sp.</i>	6	3	2.00				2									3	1	
	<i>Quercus falcata</i>	15	9	1.67	2		1		1				1	3	2	1		2	2
	<i>Quercus michauxii</i>	8	4	2.00			2		1	1	4								
	<i>Quercus phellos</i>	6	3	2.00			1	3			2								
	<i>Salix nigra</i>	5	3	1.67	1							2						2	
	<i>Salix sericea</i>	4	2	2.00	3									1					
	<i>Sambucus canadensis</i>	12	4	3.00					3			3		4				2	
	<i>Symphoricarpos orbiculatu</i>	7	6	1.17			1					2	1		1	1	1		
	Unknown	7	5	1.40	2					1		1				2			1
TOT:	21	262	21		16	18	17	15	25	17	17	21	17	21	20	22	13	14	9

Table A6. Stem counts arranged by plot.																		
Project Name: Collins Creek																		
Species	Plots															Initial Totals	Year 1 Totals	Survival %
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15			
Shrubs																		
<i>Aronia arbutifolia</i>	1	4	4	2	6	7	2					2				31	28	90%
<i>Callicarpa americana</i>		0		3			1									5	4	80%
<i>Ilex decidua</i> *						2	1	2	1	3	1				0	9	10	111%
<i>Ilex verticillata</i>		1	1				1	0				1				6	4	67%
<i>Ilex virginica</i>												0	0	0		3	0	0%
<i>Lindera benzoin</i>	0		1							0						3	1	33%
<i>Symphoricarpos orbiculatas</i>			1					2	1		1	1	1	0		8	7	88%
Trees																		
<i>Betula nigra</i>	2	6	1		3	1	1			0	2	1			0	18	17	94%
<i>Carya ovata</i>				1					1	1	2		3		0	8	8	100%
<i>Cornus anomum</i>	3			3	6			5	1	3			0	2	0	32	23	72%
<i>Diospyros virginiana</i>	0	3	5	0	3		0	1	1	3	8	7	2	3	2	39	38	97%
<i>Fraxinus pennsylvanica</i>				0		1	1									2	2	100%
<i>Juglans nigra</i>						1		5	11	3	3	3	4	2	4	42	36	86%
<i>Platanus occidentalis</i>	2	4		1	2	3	4				1	4				22	21	95%
<i>Quercus falcata</i>	2	0	1		1				1	3	2	1	0	2	2	15	15	100%
<i>Quercus michauxii</i>	0		2		1	1	4			0				0		15	8	53%
<i>Quercus phellos</i> *	1		1	3			2									6	7	117%
<i>Quercus sp.</i>				2						0		0	3	1	0	8	6	75%
<i>Salix nigra</i>	1							2						2	0	6	5	83%
<i>Salix sericea</i>	3									1						8	4	50%
<i>Sambucus canadensis</i>	0				3			3		4				2		26	12	46%
Unknown	2					1		1		0	0	2			1	9	7	78%
Total	17	18	17	15	25	17	17	21	17	21	20	22	13	14	9	327	262	80%
Density	680	720	680	600	1000	680	680	840	680	840	800	880	520	560	360	888	701	79%

*Percentages greater than 100% are due to previously unknown species being positively identified

Table A7. Vegetation History (stems/acre)						
Project Name: Collins Creek						
Plot Number	MY-00	MY-01	MY-02	MY-03	MY-04	MY-05
1	1,080	680				
2	760	720				
3	800	680				
4	640	600				
5	1,160	1,000				
6	760	680				
7	680	680				
8	1,080	840				
9	680	680				
10	1,360	840				
11	960	800				
12	1,120	880				
13	720	520				
14	840	560				
15	680	360				

A2 - Vegetation Monitoring Plot Photos



Plot 1 Photo – 10/10/08 - MY 01



Plot 2 Photo – 10/10/08 - MY 01



Plot 3 Photo – 10/14/08 - MY 01



Plot 4 Photo – 10/14/08 - MY 01



Plot 5 Photo – 10/14/08 - MY 01



Plot 6 Photo – 10/14/08 - MY 01



Plot 7 Photo – 10/14/08 - MY 01



Plot 8 Photo – 10/16/08 - MY 01



Plot 9 Photo – 10/10/08 - MY 01



Plot 10 Photo – 10/14/08 - MY 01



Plot 11 Photo – 10/10/08 - MY 01



Plot 12 Photo – 10/10/08 - MY 01



Plot 13 Photo – 10/14/08 - MY 01



Plot 14 Photo – 10/14/08 - MY 01



Plot 15 Photo – 10/16/08 - MY 01

Appendix B

Geomorphologic Data

Appendix B1: Representative Stream Problem Area Photos



SP1 – Floodplain erosion taken near Station 107+00. 11/24/08 - MY 01



SP2 – Bed degradation taken near Station 80+50. 9/9/08 - MY 01

Appendix B2 –Stream Photo Station Photos



PP#1A – MY01 – 11/24/08



PP#1B – MY01 – 11/24/08



PP#1C – MY01 – 11/24/08



PP#2A – MY01 – 11/24/08



PP#2B – MY01 – 11/24/08



PP#2C – MY01 – 11/24/08



PP#2D – MY01 – 11/24/08



PP#3A – MY01 – 11/24/08



PP#3B – MY01 – 11/24/08



PP#4A – MY01 – 11/24/08



PP#4B – MY01 – 11/24/08



PP#5A – MY01 – 11/24/08



PP#5B – MY01 – 11/24/08



PP#5C – MY01 – 11/24/08



PP#6A – MY01 – 11/24/08



PP#6B – MY01 – 11/24/08



PP#7A – MY01 – 11/24/08



PP#7B – MY01 – 11/24/08



PP#8 – MY01 – 11/24/08



PP#9A – MY01 – 11/24/08



PP#9B – MY01 – 11/24/08



PP#10A – MY01 – 11/24/08



PP#10B – MY01 – 11/24/08



PP#10C – MY01 – 11/24/08



PP#11A – MY01 – 11/24/08



PP#11B – MY01 – 11/24/08



PP#12A – MY01 – 11/24/08



PP#12B – MY01 – 11/24/08



PP#13A – MY01 – 11/24/08



PP#13B – MY01 – 11/24/08



PP#13C – MY01 – 11/24/08



PP#14A – MY01 – 11/24/08



PP#14B – MY01 – 11/24/08



PP#15A – MY01 – 11/24/08



PP#15B – MY01 – 11/24/08



PP#16A – MY01 – 11/24/08



PP#16B – MY01 – 11/24/08



PP#17A – MY01 – 11/24/08



PP#17B – MY01 – 11/24/08



PP#18A – MY01 – 11/24/08



PP#18B – MY01 – 11/24/08



PP#18C – MY01 – 11/24/08



PP#20 – MY01 – 11/24/08



PP#21A – MY01 – 11/24/08



PP#21B – MY01 – 11/24/08



PP#22A – MY01 – 11/24/08



PP#22B – MY01 – 11/24/08



PP#23 – MY01 – 11/24/08



PP#24A – MY01 – 11/24/08



PP#24B – MY01 – 11/24/08



PP#25A – MY01 – 11/24/08



PP#25B – MY01 – 11/24/08



PP#26 – MY01 – 11/24/08



PP#27A – MY01 – 11/24/08



PP#27B – MY01 – 11/24/08



PP#28A – MY01 – 11/24/08



PP#28B – MY01 – 11/24/08



PP#29A – MY01 – 11/24/08



PP#29B – MY01 – 11/24/08



PP#30A – MY01 – 11/24/08



PP#30B – MY01 – 11/24/08



PP#31A – MY01 – 11/24/08



PP#31B – MY01 – 11/24/08



Bankfull Photo – Remnants of bankfull event on 9/6/08. Photo taken 9/9/08. - MY 01

B3 - Cross-Section Plots


River Basin:	Cape Fear
Watershed:	Collins Creek, UTCC-1
XS ID	XS-1, Riffle
Drainage Area (sq mi):	2.51
Date:	10/14/2008
Field Crew:	B. Roberts and A. French



Station	Elevation
0.0	507.68
2.4	507.61
6.2	507.43
10.3	506.74
13.7	506.15
20.7	506.05
25.4	506.04
27.5	505.47
29.5	504.53
30.5	503.91
31.7	503.43
33.2	503.08
34.4	503.07
35.7	503.15
37.2	503.13
38.7	503.06
40.0	502.99
41.3	503.46
42.4	504.05
44.0	504.83
46.1	505.71
48.2	506.39
50.9	506.82
54.1	506.96
57.8	506.65
62.3	506.35
64.2	506.25
65.4	506.10

SUMMARY DATA	
Bankfull Elevation:	506.3
Bankfull Cross-Sectional Area:	43.6
Bankfull Width:	21.9
Flood Prone Area Elevation:	509.4
Flood Prone Width:	>65
Max Depth at Bankfull:	3.1
Mean Depth at Bankfull:	2.0
W / D Ratio:	11.0
Entrenchment Ratio:	>3
Bank Height Ratio:	1.0

Stream Type C4




River Basin:	Cape Fear
Watershed:	Collins Creek, UTCC-1
XS ID	XS-2, Pool
Drainage Area (sq mi):	2.51
Date:	10/14/2008
Field Crew:	B. Roberts, A. French




Stream Type: C4

SUMMARY DATA	
Bankfull Elevation:	505.5
Bankfull Cross-Sectional Area:	88.0
Bankfull Width:	37.5
Flood Prone Area Elevation:	-
Flood Prone Width:	-
Max Depth at Bankfull:	4.3
Mean Depth at Bankfull:	2.3
W / D Ratio:	-
Entrenchment Ratio:	-
Bank Height Ratio:	-

Station	Elevation
0.0	507.14
1.2	507.12
6.1	507.00
8.7	506.89
11.1	506.72
13.8	506.23
16.6	505.85
22.9	505.57
26.2	505.81
28.1	505.83
30.0	505.11
30.4	505.02
32.9	503.71
34.5	502.88
35.0	502.36
36.1	501.81
38.0	501.40
39.7	501.22
41.6	501.37
44.0	501.62
45.6	501.85
48.0	502.11
50.8	502.26
52.6	502.71
54.5	503.37
56.3	503.69
57.6	503.94
59.5	504.61
62.1	505.24
66.2	505.49
75.1	505.81
83.8	506.12




River Basin:	Cape Fear
Watershed:	Collins Creek, UTCC-3
XS ID	XS-3, Pool
Drainage Area (sq mi):	2.62
Date:	10/15/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

SUMMARY DATA	
Bankfull Elevation:	503.6
Bankfull Cross-Sectional Area:	48.6
Bankfull Width:	25.4
Flood Prone Area Elevation:	-
Flood Prone Width:	-
Max Depth at Bankfull:	3.6
Mean Depth at Bankfull:	1.9
W / D Ratio:	-
Entrenchment Ratio:	-
Bank Height Ratio:	-

Station	Elevation
0.0	506.41
2.1	506.31
6.1	505.80
11.5	504.94
13.5	504.42
18.0	504.10
22.6	504.09
27.9	503.90
30.7	503.65
31.8	503.49
32.6	503.28
35.2	502.25
36.1	501.82
37.0	501.03
37.6	500.85
38.6	500.48
40.4	500.03
42.3	500.10
44.8	500.93
46.4	501.33
49.3	501.44
50.1	501.66
52.7	502.47
55.1	503.34
57.3	503.76
61.0	504.02
69.0	503.66
79.2	504.02




River Basin:	Cape Fear
Watershed:	Collins Creek, UTCC-3
XS ID	XS-4, Riffle
Drainage Area (sq mi):	2.62
Date:	10/15/2008
Field Crew:	B. Roberts, A. French



Station	Elevation
0.0	505.51
8.2	505.23
14.4	504.83
20.4	504.71
25.5	504.54
27.8	503.74
30.1	502.80
32.3	501.81
34.1	501.14
36.6	500.91
40.7	501.02
45.0	501.10
47.2	501.63
50.0	502.49
54.1	503.57
58.5	503.79
65.0	503.75
70.5	503.45
74.5	503.81
79.1	503.63

SUMMARY DATA	
Bankfull Elevation:	503.6
Bankfull Cross-Sectional Area:	46.2
Bankfull Width:	25.9
Flood Prone Area Elevation:	506.2
Flood Prone Width:	>76
Max Depth at Bankfull:	2.7
Mean Depth at Bankfull:	1.8
W / D Ratio:	14.5
Entrenchment Ratio:	>3
Bank Height Ratio:	1.0

Stream Type: C4




River Basin:	Cape Fear
Watershed:	Collins Creek, UTCC-3
XS ID	XS-5, Riffle
Drainage Area (sq mi):	2.62
Date:	10/15/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

Station	Elevation
0.0	504.35
7.4	504.23
13.9	503.93
19.5	503.67
24.2	503.31
26.5	502.39
27.7	501.82
28.4	501.48
29.2	501.07
30.6	500.45
31.5	500.20
33.1	499.96
35.3	500.01
37.1	500.13
39.8	500.31
42.2	500.32
44.2	500.87
45.3	501.47
47.7	502.41
49.8	502.95
54.2	503.30
60.3	503.36
67.5	503.37
74.0	503.34

SUMMARY DATA	
Bankfull Elevation:	503.2
Bankfull Cross-Sectional Area:	54.9
Bankfull Width:	28.2
Flood Prone Area Elevation:	506.4
Flood Prone Width:	>74
Max Depth at Bankfull:	3.2
Mean Depth at Bankfull:	1.9
W / D Ratio:	14.5
Entrenchment Ratio:	>3
Bank Height Ratio:	1.0




River Basin:	Cape Fear
Watershed:	Collins Creek, T1-1
XS ID	XS-6, Riffle
Drainage Area (sq mi):	0.12
Date:	10/14/2008
Field Crew:	B. Roberts and K. Vaughan



Stream Type C4

Station	Elevation
0.0	527.00
12.5	525.09
19.0	524.88
24.1	525.01
26.2	524.65
27.9	524.00
28.9	523.76
30.7	523.64
32.0	523.49
33.7	524.17
36.1	525.07
40.5	525.07
46.2	525.26
49.3	526.24
53.5	527.39
54.8	527.74
56.3	527.81
58.3	528.07
62.8	528.36

SUMMARY DATA	
Bankfull Elevation:	524.9
Bankfull Cross-Sectional Area:	8.5
Bankfull Width:	11.8
Flood Prone Area Elevation:	526.3
Flood Prone Width:	44.8
Max Depth at Bankfull:	1.4
Mean Depth at Bankfull:	0.7
W / D Ratio:	16.4
Entrenchment Ratio:	3.8
Bank Height Ratio:	1.0




River Basin:	Cape Fear
Watershed:	Collins Creek, T1-2
XS ID	XS-7, Riffle
Drainage Area (sq mi):	0.18
Date:	10/8/2008
Field Crew:	B. Roberts, A. French



Station	Elevation
0.0	522.84
4.1	522.31
7.4	522.84
9.6	522.43
12.9	521.29
17.3	520.25
23.3	520.31
27.4	520.24
29.0	519.60
30.4	519.04
33.3	518.73
34.7	518.54
35.8	518.52
36.6	518.73
37.7	519.31
38.7	519.97
40.0	520.18
43.2	520.19
49.3	520.28
55.2	522.21
60.6	523.72
66.1	523.49
72.2	523.70

SUMMARY DATA	
Bankfull Elevation:	520.2
Bankfull Cross-Sectional Area:	12.4
Bankfull Width:	12.4
Flood Prone Area Elevation:	521.8
Flood Prone Width:	42.1
Max Depth at Bankfull:	1.7
Mean Depth at Bankfull:	1.0
W / D Ratio:	12.4
Entrenchment Ratio:	3.4
Bank Height Ratio:	1.0

Stream Type C4




River Basin:	Cape Fear
Watershed:	Collins Creek, T1-2
XS ID	XS-8, Pool
Drainage Area (sq mi):	0.18
Date:	10/8/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

SUMMARY DATA	
Bankfull Elevation:	518.2
Bankfull Cross-Sectional Area:	10.5
Bankfull Width:	13.4
Flood Prone Area Elevation:	-
Flood Prone Width:	-
Max Depth at Bankfull:	1.7
Mean Depth at Bankfull:	0.8
W / D Ratio:	-
Entrenchment Ratio:	-
Bank Height Ratio:	-

Station	Elevation
0.0	520.53
4.5	520.02
9.0	519.34
16.2	518.59
23.1	518.56
30.3	518.41
32.6	518.26
35.1	517.88
37.9	517.43
39.9	517.14
40.5	516.98
41.3	516.70
42.0	516.49
42.7	516.73
43.8	517.29
44.7	517.68
46.2	518.25
47.9	518.60
54.1	518.77
57.2	519.14
61.0	520.38
65.4	522.24
69.3	522.10
72.6	522.25
74.9	522.74




River Basin:	Cape Fear
Watershed:	Collins Creek, T1-3
XS ID	XS-9, Riffle
Drainage Area (sq mi):	0.49
Date:	10/13/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

Station	Elevation
0.0	514.76
2.1	514.68
4.5	514.48
8.9	514.30
16.5	513.76
21.5	513.44
24.7	512.52
27.2	512.25
28.8	512.07
29.3	511.84
29.9	511.75
30.4	511.90
31.0	511.98
31.7	512.20
34.4	512.83
37.6	513.43
44.2	513.87
51.3	514.32
61.6	514.61
65.4	514.39

SUMMARY DATA		
Bankfull Elevation:		513.7
Bankfull Cross-Sectional Area:		19.3
Bankfull Width:		24.3
Flood Prone Area Elevation:		515.7
Flood Prone Width:		>65
Max Depth at Bankfull:		2.0
Mean Depth at Bankfull:		0.8
W / D Ratio:		30.6
Entrenchment Ratio:		>3
Bank Height Ratio:		1.0




River Basin:	Cape Fear
Watershed:	Collins Creek, T1-3
XS ID	XS-10, Pool
Drainage Area (sq mi):	0.49
Date:	10/13/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

Station	Elevation
0.0	514.51
0.8	514.50
4.3	513.82
5.4	513.55
7.0	513.01
9.9	512.63
15.1	512.33
19.9	512.01
22.5	511.86
24.1	511.22
25.8	510.34
26.6	509.71
27.1	509.12
27.8	508.84
28.8	508.74
30.0	508.86
31.7	509.24
33.5	509.86
34.3	510.20
35.3	510.29
36.6	510.68
37.5	510.70
40.6	511.40
44.8	511.85
48.8	512.37
55.7	513.13
60.6	513.19
64.9	513.13
67.8	513.28

SUMMARY DATA	
Bankfull Elevation:	511.8
Bankfull Cross-Sectional Area:	30.8
Bankfull Width:	21.6
Flood Prone Area Elevation:	-
Flood Prone Width:	-
Max Depth at Bankfull:	3.1
Mean Depth at Bankfull:	1.4
W / D Ratio:	-
Entrenchment Ratio:	-
Bank Height Ratio:	-




River Basin:	Cape Fear
Watershed:	Collins Creek, T1-3
XS ID	XS-11, Riffle
Drainage Area (sq mi):	0.49
Date:	10/14/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

SUMMARY DATA	
Bankfull Elevation:	506.1
Bankfull Cross-Sectional Area:	11.2
Bankfull Width:	14.6
Flood Prone Area Elevation:	507.3
Flood Prone Width:	46.3
Max Depth at Bankfull:	1.2
Mean Depth at Bankfull:	0.8
W / D Ratio:	19.0
Entrenchment Ratio:	3.2
Bank Height Ratio:	1.0

Station	Elevation
0.0	510.26
2.0	510.07
3.7	509.69
6.7	508.61
10.0	507.56
12.7	506.70
16.9	506.53
20.1	506.23
21.8	505.76
23.2	505.12
24.8	505.19
26.7	505.18
27.7	505.22
28.7	505.11
29.7	504.89
30.8	505.03
32.0	505.09
34.2	505.89
35.9	506.25
38.8	506.49
42.3	506.48
45.7	506.73
50.6	506.78
55.4	506.99
58.7	507.61
61.5	508.18
63.0	508.38




River Basin:	Cape Fear
Watershed:	Collins Creek, T1A-1
XS ID	XS-12, Riffle
Drainage Area (sq mi):	0.04
Date:	10/14/2008
Field Crew:	B. Roberts, A. French



Station	Elevation
0.0	536.96
3.3	536.77
6.9	536.62
13.5	536.07
19.4	535.54
24.4	535.35
26.2	535.45
28.8	535.26
29.7	535.09
30.2	535.24
30.9	535.21
31.5	534.91
32.0	534.83
33.5	535.12
35.1	535.39
38.9	535.52
41.7	535.62
47.0	535.36
51.3	535.29
54.5	535.23
55.2	535.15

SUMMARY DATA	
Bankfull Elevation:	535.4
Bankfull Cross-Sectional Area:	1.7
Bankfull Width:	7.7
Flood Prone Area Elevation:	535.9
Flood Prone Width:	>40
Max Depth at Bankfull:	0.5
Mean Depth at Bankfull:	0.2
W / D Ratio:	34.9
Entrenchment Ratio:	>5
Bank Height Ratio:	1.0

Stream Type: C4




River Basin:	Cape Fear
Watershed:	Collins Creek, T1A-2
XS ID	XS-13, Riffle
Drainage Area (sq mi):	0.05
Date:	10/14/2008
Field Crew:	B. Roberts, A. French




Stream Type C4

Station	Elevation
0.0	528.21
0.7	528.44
3.8	528.01
8.5	527.88
12.6	527.87
18.6	527.83
20.8	527.77
21.8	527.54
22.8	527.12
24.5	526.95
25.2	526.74
25.6	526.82
26.0	526.64
27.1	526.52
28.3	526.95
29.0	527.04
30.3	527.53
30.8	527.64
33.3	527.66
38.3	527.57
43.0	527.57
45.2	527.32

SUMMARY DATA	
Bankfull Elevation:	527.7
Bankfull Cross-Sectional Area:	6.3
Bankfull Width:	9.7
Flood Prone Area Elevation:	528.9
Flood Prone Width:	>40
Max Depth at Bankfull:	1.2
Mean Depth at Bankfull:	0.6
W / D Ratio:	14.9
Entrenchment Ratio:	>4
Bank Height Ratio:	1.0




River Basin:	Cape Fear
Watershed:	Collins Creek, T1B
XS ID	XS-14, Riffle
Drainage Area (sq mi):	0.24
Date:	10/8/2008
Field Crew:	B. Roberts, A. French



Stream Type C4

Station	Elevation
0.0	524.16
6.9	523.98
9.7	523.60
12.5	522.99
19.6	522.70
25.9	522.72
27.9	522.28
29.5	521.55
30.5	521.31
31.3	521.17
32.5	521.13
33.2	521.17
34.4	521.60
36.3	522.41
39.1	522.87
45.8	523.13
50.1	524.19
54.3	524.62
58.2	524.01

SUMMARY DATA		
Bankfull Elevation:		522.6
Bankfull Cross-Sectional Area:		9.1
Bankfull Width:		11.0
Flood Prone Area Elevation:		524.1
Flood Prone Width:		53.0
Max Depth at Bankfull:		1.5
Mean Depth at Bankfull:		0.8
W / D Ratio:		13.3
Entrenchment Ratio:		4.8
Bank Height Ratio:		1.0




River Basin:	Cape Fear
Watershed:	Collins Creek, T2
XS ID	XS-15, Pool
Drainage Area (sq mi):	0.07
Date:	10/16/2008
Field Crew:	B. Roberts, A. French



Stream Type B4c

SUMMARY DATA	
Bankfull Elevation:	515.0
Bankfull Cross-Sectional Area:	12.0
Bankfull Width:	11.3
Flood Prone Area Elevation:	-
Flood Prone Width:	-
Max Depth at Bankfull:	2.1
Mean Depth at Bankfull:	1.1
W / D Ratio:	-
Entrenchment Ratio:	-
Bank Height Ratio:	-

Station	Elevation
0.0	516.50
5.0	516.44
10.8	516.25
17.6	516.42
19.3	516.23
21.2	515.88
22.7	515.35
24.0	514.90
25.7	514.35
26.8	513.96
27.9	513.76
28.4	513.44
29.2	513.01
30.1	512.90
30.7	512.94
31.2	513.01
31.2	513.37
32.3	513.89
34.1	514.66
36.0	515.38
37.9	516.10
41.5	516.41
44.8	516.93
52.0	517.42
54.7	517.90
60.3	518.32




River Basin:	Cape Fear
Watershed:	Collins Creek, T2
XS ID	XS-16, Riffle
Drainage Area (sq mi):	0.07
Date:	10/16/2008
Field Crew:	B. Roberts, A. French



Stream Type B4c


Station	Elevation
0.0	516.38
4.3	515.89
9.3	515.86
14.6	516.07
19.3	516.12
21.0	516.00
22.8	515.81
25.1	514.96
27.0	514.10
27.9	513.77
28.4	513.61
28.7	513.33
29.4	513.29
30.0	513.19
30.4	513.01
31.0	513.10
31.5	513.03
31.9	513.34
32.8	513.72
33.5	514.01
35.5	514.75
37.7	515.58
39.5	515.82
43.2	516.00
47.5	516.25
53.5	516.57
60.8	516.94
65.4	517.19

SUMMARY DATA	
Bankfull Elevation:	514.3
Bankfull Cross-Sectional Area:	5.7
Bankfull Width:	7.7
Flood Prone Area Elevation:	515.6
Flood Prone Width:	14.4
Max Depth at Bankfull:	1.3
Mean Depth at Bankfull:	0.7
W / D Ratio:	10.4
Entrenchment Ratio:	1.9
Bank Height Ratio:	0.5





Appendix B4: Longitudinal Profile


Longitudinal Profile Main Stem UTCC MY01 Stations 21+13 - 32+17



**Longitudinal Profile
Tributary 1 UTCC MY-01
Stations 53+25 - 65+00**




**Longitudinal Profile
Tributary 1A UTCC MY-01
Stations 83+80 - 86+80**




As-Built
 MY-01
 Water Surface*
 Bankfull
 WS Slope
 BKF Slope

*No WS due to no flow in channel during survey.

**Longitudinal Profile
Tributary 1B UTCC MY-01
Stations 106+00 - 109+00**



**Longitudinal Profile
Tributary 2 UTCC MY01
Stations 132+50 - 138+50**




B5 - Pebble Count Plots

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	Count	
Silt/Clay	< 0.062	14	S/C
Very Fine	.062 - .125	26	S
Fine	.125 - .25	16	A
Medium	.25 - .50	1	N
Coarse	.50 - 1		D
Very Coarse	1 - 2		S
Very Fine	2 - 4		
Fine	4 - 5.7	2	G
Fine	5.7 - 8	3	R
Medium	8 - 11.3	8	A
Medium	11.3 - 16	13	V
Coarse	16 - 22.6	11	E
Coarse	22.6 - 32	1	L
Very Coarse	32 - 45	1	S
Very Coarse	45 - 64	1	
Small	64 - 90	1	C
Small	90 - 128	3	O
Large	128 - 180		B
Large	180 - 256		L
Small	256 - 362		B
Small	362 - 512		L
Medium	512 - 1024		D
Lrg- Very Lrg	1024 - 2048		R
Bedrock	>2048		BDRK
			Total
			101

Note:

Particle Size Distribution
Collins Creek
XS 1 Riffle




Size (mm)	Count
D16	0.066
D35	0.11
D50	0.2
D65	9.3
D84	17
D95	44

Size Distribution	
mean	1.1
dispersion	44.0
skewness	0.47

Type	Percentage
silt/clay	14%
sand	43%
gravel	40%
cobble	4%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	7
Very Fine	.062 - .125	S	
Fine	.125 - .25	A	
Medium	.25 - .50	N	3
Coarse	.50 - 1	D	19
Very Coarse	1 - 2	S	4
Very Fine	2 - 4	G	9
Fine	4 - 5.7	R	9
Medium	5.7 - 8	A	21
Medium	8 - 11.3	V	14
Coarse	11.3 - 16	E	8
Coarse	16 - 22.6	L	4
Very Coarse	22.6 - 32	S	1
Very Coarse	32 - 45		
Very Coarse	45 - 64		
Small	64 - 90	C	1
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100

Particle Size Distribution
Collins Creek
XS 2 Pool




Size (mm)	Count
D16	1.2
D35	4.4
D50	7.7
D65	9.9
D84	15
D95	24

Size Distribution	
mean	4.2
dispersion	4.2
skewness	-0.25

Type	Percentage
silt/clay	7%
sand	65%
gravel	25%
cobble	0%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:


Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062		57
Very Fine	.062 - .125	S	7
Fine	.125 - .25	A	5
Medium	.25 - .50	N	
Coarse	.50 - 1	D	4
Very Coarse	1 - 2	S	
Very Fine	2 - 4		3
Fine	4 - 5.7	G	1
Fine	5.7 - 8	R	3
Medium	8 - 11.3	A	4
Medium	11.3 - 16	V	2
Coarse	16 - 22.6	E	11
Coarse	22.6 - 32	L	3
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100



Size (mm)		Size Distribution		Type	
D16	0.062	mean	0.8	silt/clay	57%
D35	0.062	dispersion	89.2	sand	16%
D50	0.062	skewness	0.75	gravel	27%
D65	0.14			cobble	0%
D84	11			boulder	0%
D95	21			bedrock	0%
				hardpan	0%
				wood/det	0%
				artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062		59
Very Fine	.062 - .125	S	16
Fine	.125 - .25	A	1
Medium	.25 - .50	N	1
Coarse	.50 - 1	D	
Very Coarse	1 - 2	S	
Very Fine	2 - 4		2
Fine	4 - 5.7	G	
Fine	5.7 - 8	R	3
Medium	8 - 11.3	A	3
Medium	11.3 - 16	V	2
Coarse	16 - 22.6	E	7
Coarse	22.6 - 32	L	3
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	1
Small	90 - 128	O	1
Large	128 - 180	B	
Large	180 - 256	L	2
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			101




Size (mm)	Count
D16	0.062
D35	0.062
D50	0.062
D65	0.083
D84	11
D95	28

Size Distribution	
mean	0.8
dispersion	2.9
skewness	-0.14

Type	Percentage
silt/clay	58%
sand	18%
gravel	20%
cobble	4%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062		57
Very Fine	.062 - .125	S	18
Fine	.125 - .25	A	4
Medium	.25 - .50	N	
Coarse	.50 - 1	D	
Very Coarse	1 - 2	S	
Very Fine	2 - 4		
Fine	4 - 5.7	G	1
Fine	5.7 - 8	R	1
Medium	8 - 11.3	A	9
Medium	11.3 - 16	V	5
Coarse	16 - 22.6	E	4
Coarse	22.6 - 32	L	2
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			101



Size (mm)	
D16	0.062
D35	0.062
D50	0.062
D65	0.087
D84	9.2
D95	17


Size Distribution	
mean	0.8
dispersion	74.7
skewness	0.74

Type	Percentage
silt/clay	56%
sand	22%
gravel	22%
cobble	0%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:

Cross-Section 1 Riffle - MY01 (N/A)			
Particle	Millimeter		Count
Silt/Clay	< 0.062	S/C	
Very Fine	.062 - .125	S	
Fine	.125 - .25	A	
Medium	.25 - .50	N	
Coarse	.50 - 1	D	
Very Coarse	1 - 2	S	
Very Fine	2 - 4		
Fine	4 - 5.7	G	
Fine	5.7 - 8	R	
Medium	8 - 11.3	A	
Medium	11.3 - 16	V	
Coarse	16 - 22.6	E	
Coarse	22.6 - 32	L	
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
		Total	0

Particle Size Distribution
Collins Creek
XS 6 Riffle



As Built


Size (mm)	
D16	0.062
D35	0.078
D50	0.15
D65	0.25
D84	0.44
D95	1.3

Size Distribution	
mean	0.2
dispersion	2.7
skewness	0.05

Type	
silt/clay	30%
sand	67%
gravel	3%
cobble	0%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	16
Very Fine	.062 - .125	S	30
Fine	.125 - .25	A	3
Medium	.25 - .50	N	15
Coarse	.50 - 1	D	2
Very Coarse	1 - 2	S	
Very Fine	2 - 4		4
Fine	4 - 5.7	G	
Fine	5.7 - 8	R	1
Medium	8 - 11.3	A	2
Medium	11.3 - 16	V	14
Coarse	16 - 22.6	E	8
Coarse	22.6 - 32	L	3
Very Coarse	32 - 45	S	1
Very Coarse	45 - 64		1
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100




Size (mm)	
D16	0.062
D35	0.097
D50	0.26
D65	0.71
D84	15
D95	22

Size Distribution	
mean	1.0
dispersion	30.9
skewness	0.37

Type	
silt/clay	16%
sand	50%
gravel	34%
cobble	0%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:


Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	41
Very Fine	.062 - .125	S	24
Fine	.125 - .25	A	17
Medium	.25 - .50	N	9
Coarse	.50 - 1	D	1
Very Coarse	1 - 2	S	1
Very Fine	2 - 4		
Fine	4 - 5.7	G	1
Fine	5.7 - 8	R	1
Medium	8 - 11.3	A	1
Medium	11.3 - 16	V	1
Coarse	16 - 22.6	E	1
Coarse	22.6 - 32	L	1
Very Coarse	32 - 45	S	1
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100



Size (mm)	D16	D35	D50	D65	D84	D95
Size (mm)	0.062	0.062	0.081	0.13	0.29	8
Size Distribution	mean	0.1	dispersion	2.4	skewness	0.27
Type	silt/clay	41%	sand	52%	gravel	7%
	cobble	0%	boulder	0%	bedrock	0%
	hardpan	0%	wood/det	0%	artificial	0%

Note:


Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	
Very Fine	.062 - .125	S	14
Fine	.125 - .25	A	5
Medium	.25 - .50	N	1
Coarse	.50 - 1	D	5
Very Coarse	1 - 2	S	11
Very Fine	2 - 4		4
Fine	4 - 5.7	G	2
Fine	5.7 - 8	R	5
Medium	8 - 11.3	A	14
Medium	11.3 - 16	V	12
Coarse	16 - 22.6	E	13
Coarse	22.6 - 32	L	10
Very Coarse	32 - 45	S	3
Very Coarse	45 - 64		1
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100



Size (mm)		Size Distribution		Type	
D16	0.16	mean	1.8	silt/clay	0%
D35	1.9	dispersion	28.1	sand	36%
D50	8.6	skewness	-0.46	gravel	64%
D65	12			cobble	0%
D84	21			boulder	0%
D95	31			bedrock	0%
				hardpan	0%
				wood/det	0%
				artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	8
Very Fine	.062 - .125	S	13
Fine	.125 - .25	A	13
Medium	.25 - .50	N	14
Coarse	.50 - 1	D	12
Very Coarse	1 - 2	S	7
Very Fine	2 - 4		6
Fine	4 - 5.7	G	7
Fine	5.7 - 8	R	4
Medium	8 - 11.3	A	4
Medium	11.3 - 16	V	3
Coarse	16 - 22.6	E	3
Coarse	22.6 - 32	L	2
Very Coarse	32 - 45	S	2
Very Coarse	45 - 64		
Small	64 - 90	C	1
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	10
Total			109




Size (mm)	
D16	0.095
D35	0.26
D50	0.55
D65	1.5
D84	7.5
D95	22

Size Distribution	
mean	0.8
dispersion	9.7
skewness	0.14

Type	
silt/clay	7%
sand	54%
gravel	28%
cobble	1%
boulder	0%
bedrock	9%
hardpan	0%
wood/det	0%
artificial	0%

Note:


Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	2
Very Fine	.062 - .125	S	
Fine	.125 - .25	A	
Medium	.25 - .50	N	4
Coarse	.50 - 1	D	7
Very Coarse	1 - 2	S	4
Very Fine	2 - 4		4
Fine	4 - 5.7	G	4
Fine	5.7 - 8	R	3
Medium	8 - 11.3	A	19
Medium	11.3 - 16	V	27
Coarse	16 - 22.6	E	13
Coarse	22.6 - 32	L	12
Very Coarse	32 - 45	S	5
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100



Size (mm)		Size Distribution		Type	
D16	3.4	mean	8.8	silt/clay	2%
D35	9.6	dispersion	2.7	sand	11%
D50	12	skewness	-0.15	gravel	87%
D65	15			cobble	0%
D84	23			boulder	0%
D95	32			bedrock	0%
				hardpan	0%
				wood/det	0%
				artificial	0%

Note:


Cross-Section 1 Riffle - MY01 (N/A)			
Particle	Millimeter	Count	
Silt/Clay	< 0.062	S/C	
Very Fine	.062 - .125	S	
Fine	.125 - .25	A	
Medium	.25 - .50	N	
Coarse	.50 - 1	D	
Very Coarse	1 - 2	S	
Very Fine	2 - 4		
Fine	4 - 5.7	G	
Fine	5.7 - 8	R	
Medium	8 - 11.3	A	
Medium	11.3 - 16	V	
Coarse	16 - 22.6	E	
Coarse	22.6 - 32	L	
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
		Total	0



Size (mm)		Size Distribution		Type	
D16	0.068	mean	0.1	silt/clay	7%
D35	0.081	dispersion	1.4	sand	93%
D50	0.094	skewness	0.03	gravel	0%
D65	0.11			cobble	0%
D84	0.14			boulder	0%
D95	0.21			bedrock	0%
				hardpan	0%
				wood/det	0%
				artificial	0%

Note:

Cross-Section 1 Riffle - MY01 (N/A)			
Particle	Millimeter	Count	
Silt/Clay	< 0.062	S/C	
Very Fine	.062 - .125	S	
Fine	.125 - .25	A	
Medium	.25 - .50	N	
Coarse	.50 - 1	D	
Very Coarse	1 - 2	S	
Very Fine	2 - 4		
Fine	4 - 5.7	G	
Fine	5.7 - 8	R	
Medium	8 - 11.3	A	
Medium	11.3 - 16	V	
Coarse	16 - 22.6	E	
Coarse	22.6 - 32	L	
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
		Total	0




Size (mm)	
D16	0.068
D35	0.081
D50	0.094
D65	0.11
D84	0.14
D95	0.21

Size Distribution	
mean	0.1
dispersion	1.4
skewness	0.03

Type	
silt/clay	7%
sand	93%
gravel	0%
cobble	0%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	1
Very Fine	.062 - .125	S	13
Fine	.125 - .25	A	27
Medium	.25 - .50	N	26
Coarse	.50 - 1	D	13
Very Coarse	1 - 2	S	
Very Fine	2 - 4		1
Fine	4 - 5.7	G	2
Fine	5.7 - 8	R	6
Medium	8 - 11.3	A	6
Medium	11.3 - 16	V	4
Coarse	16 - 22.6	E	
Coarse	22.6 - 32	L	1
Very Coarse	32 - 45	S	
Very Coarse	45 - 64		
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100




Size (mm)	
D16	0.13
D35	0.21
D50	0.32
D65	0.47
D84	6.3
D95	11

Size Distribution	
mean	0.9
dispersion	11.1
skewness	0.35

Type	
silt/clay	1%
sand	79%
gravel	20%
cobble	0%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	4
Very Fine	.062 - .125	S	20
Fine	.125 - .25	A	10
Medium	.25 - .50	N	13
Coarse	.50 - 1	D	2
Very Coarse	1 - 2	S	3
Very Fine	2 - 4		
Fine	4 - 5.7	G	2
Fine	5.7 - 8	R	4
Medium	8 - 11.3	A	7
Medium	11.3 - 16	V	9
Coarse	16 - 22.6	E	10
Coarse	22.6 - 32	L	9
Very Coarse	32 - 45	S	5
Very Coarse	45 - 64		1
Small	64 - 90	C	
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	1
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100




Size (mm)	
D16	0.094
D35	0.26
D50	1.3
D65	11
D84	22
D95	37

Size Distribution	
mean	1.4
dispersion	15.4
skewness	0.03

Type	
silt/clay	4%
sand	48%
gravel	47%
cobble	1%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:

Cross-Section 1 Riffle - MY01			
Particle	Millimeter	S/C	Count
Silt/Clay	< 0.062	S/C	8
Very Fine	.062 - .125	S	
Fine	.125 - .25	A	19
Medium	.25 - .50	N	
Coarse	.50 - 1	D	
Very Coarse	1 - 2	S	2
Very Fine	2 - 4		8
Fine	4 - 5.7	G	3
Fine	5.7 - 8	R	
Medium	8 - 11.3	A	21
Medium	11.3 - 16	V	20
Coarse	16 - 22.6	E	7
Coarse	22.6 - 32	L	7
Very Coarse	32 - 45	S	3
Very Coarse	45 - 64		1
Small	64 - 90	C	1
Small	90 - 128	O	
Large	128 - 180	B	
Large	180 - 256	L	
Small	256 - 362	B	
Small	362 - 512	L	
Medium	512 - 1024	D	
Lrg- Very Lrg	1024 - 2048	R	
Bedrock	>2048	BDRK	
Total			100



Size (mm)	Count
D16	0.17
D35	3.4
D50	9.3
D65	12
D84	18
D95	32


Size Distribution	
mean	1.7
dispersion	28.3
skewness	-0.51

Type	Percentage
silt/clay	8%
sand	21%
gravel	70%
cobble	1%
boulder	0%
bedrock	0%
hardpan	0%
wood/det	0%
artificial	0%

Note:



B6 - Stream Hydrograph

UT to Collins Creek
Gauge 1 Stage Stream Hydrograph
05/23/08 to 10/01/08



Appendix C

Current Conditions Plan View



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	


SYMBOL	DESCRIPTION	DATE	APPROVED

REVISIONS



KCI
TECHNOLOGIES
ENGINEERS • PLANNERS • SCIENTISTS
4601 SIX FORKS ROAD
RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
STREAM RESTORATION PROJECT**
CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
UTCC-1 & 2: STA. 10+00 - 21+90, T1-3: STA. 67+60 - 73+70

DATE: DECEMBER 2008
SCALE: 1"=40'
**CURRENT
CONDITIONS
PLAN VIEW**
SHEET 1 OF 8



- ROCK CROSS VANE
- CONSTRUCTED RIFFLE
- STONE TOE PROTECTION
- STEP POOL STRUCTURE
- ROCK OUTLET



SEE SHEETS 3, 4, AND 1 FOR TRIBUTARY #1


SEE SHEETS 3, 4, AND 1 FOR TRIBUTARY #1

SYMBOL	DESCRIPTION	DATE	APPROVED


KCI
 TECHNOLOGIES
 ENGINEERS • PLANNERS • SCIENTISTS
 4601 SIX FORKS ROAD
 RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
 STREAM RESTORATION PROJECT**
 CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
 T1B: STATION 100+00 TO STATION 111+00

DATE: DECEMBER 2008
 SCALE: 1"=40'
**CURRENT
 CONDITIONS
 PLAN VIEW**
 SHEET 6 OF 8



ROCK CROSS VANE	
CONSTRUCTED RIFFLE	
STONE TOE PROTECTION	
STEP POOL STRUCTURE	
ROCK OUTLET	



SYMBOL	DESCRIPTION	DATE	APPROVED

REVISIONS

KCI
 TECHNOLOGIES
 ENGINEERS • PLANNERS • SCIENTISTS
 4601 SIX FORKS ROAD
 RALEIGH, NORTH CAROLINA 27609

**COLLINS CREEK
 STREAM RESTORATION PROJECT**
 CHAPEL HILL, ORANGE COUNTY, NORTH CAROLINA
 T2: STATION 129+12 TO STATION 138+33

DATE: DECEMBER 2008
 SCALE: 1"=40'
**CURRENT
 CONDITIONS
 PLAN VIEW**
 SHEET 8 OF 8