

# Freedom Park (Little Sugar Creek) Monitoring Report Year 6 (2010)

Mecklenburg County, North Carolina

USGS HUC: 03050103

Project ID No. 141



Prepared for:



**NCDENR-Ecosystem Enhancement Program**

1652 Mail Service Center

Raleigh, North Carolina 27699-1652

Submitted November 2010

Revised March 2011

## Executive Summary

The Freedom Park Stream Restoration project falls within USGS hydrologic unit **03050103**. The project stream lies within an urban setting of the City of Charlotte that is comprised predominantly of residential and commercial uses. Prior to restoration work, the project stream (Little Sugar Creek) had been destabilized through historic channelization and dredging. Also, prior to restoration work, the channel consisted of a concrete lining.

HDR Engineering designed the restoration plans and restoration was completed in 2003. Baker Engineering prepared maintenance plans and Fluvial Solutions completed the maintenance construction in early 2008. The maintenance was in response to some areas of localized instability that had developed in this large, flashy, urban system. KHA had previously completed 5 years worth of geomorphic monitoring that is documented in the 2009 monitoring report and, other than these localized areas of instability, the documented data indicated general stability of the channel. Floodplain vegetation is generally performing well, but streambank vegetation has had difficulty establishing in some areas of prior scour (~6% of the channel banks), although vegetation is continuing to advance. The maintenance also included supplemental planting in the winter/spring 2008-2009 with some additional supplements of woody stems and live stakes scheduled for winter 2010/2011 in order to address several remaining pockets of low stem density. During the late growing season of 2010, KHA assessed six (6) vegetation plots for the Year 6 monitoring. The mean planted stem density equaled 479 stems per acre, exceeding the success criteria. Steel bollards with signage were cemented into the ground to demarcate the easement boundary and support long term stewardship. The project is planned to be offered for regulatory closure in fall 2011.

## TABLE OF CONTENTS

### FIGURES

FIGURE 1	PROJECT SETTING
FIGURE 2	CURRENT CONDITIONS PLAN VIEW UPPER
FIGURE 3	CURRENT CONDITIONS PLAN VIEW MIDDLE
FIGURE 4	CURRENT CONDITIONS PLAN VIEW LOWER

### PROJECT TABLES


TABLE I	PROJECT RESTORATION COMPONENTS
TABLE II	PROJECT ACTIVITY AND REPORTING HISTORY
TABLE III	PROJECT CONTACT TABLE
TABLE IV	PROJECT BACKGROUND TABLE


### APPENDICES

APPENDIX A	VEGETATION MONITORING DATA
------------	----------------------------

# FIGURES





<b>Title</b>		Project Setting		
<b>Prepared For:</b> 	<b>Project</b>	Freedom Park (Little Sugar Creek) Stream Restoration Monitoring Year 6 – 2010 Mecklenburg County, North Carolina		
		<b>Date</b>	<b>Project Number</b>	<b>Figure</b>
		11/15/10	141	1






<b>Title</b>	Current Conditions Plan View Upper (2007 Aerial)		
<b>Prepared For:</b> 	<b>Project</b>	Freedom Park (Little Sugar Creek) Stream Restoration Monitoring Year 6 – 2010 Mecklenburg County, North Carolina	
	<b>Date</b>	11/15/10	<b>Project Number</b> 141
			<b>Figure</b> 2






<b>Title</b>		Current Conditions Plan View Middle (2007 Aerial)		
<b>Prepared For:</b> 	<b>Project</b>	Freedom Park (Little Sugar Creek) Stream Restoration Monitoring Year 6 – 2010 Mecklenburg County, North Carolina		
	<b>Date</b>	11/15/10	<b>Project Number</b>	141
		<b>Figure</b>		3





<b>Title</b>		Current Conditions Plan View Lower (2007 Aerial)		
<b>Prepared For:</b> 	<b>Project</b>	Freedom Park (Little Sugar Creek) Stream Restoration Monitoring Year 6 – 2010 Mecklenburg County, North Carolina		
	<b>Date</b>	11/15/10	<b>Project Number</b>	141
				<b>Figure</b>
				4



# PROJECT TABLES



**Table I. Project Restoration Components**  
**Little Sugar Creek Stream Restoration Site (EEP Project #141)**

Project Segment or Reach ID	Existing Feet / Acres	Type	Approach	Footage or Acreage		Mitigation Ratio	Mitigation Units	Stationing		Comment
Main	4,200	R	P2 / P3	4,425	lf	1:1	4,425	0+00.0	- 44+50.0	
<b>Mitigation Unit Summaries</b>										
Stream (lf)	Riparian Wetland (Ac.)	Non-Riparian Wetland (Ac.)	Total Wetland (Ac.)	Buffer (Ac.)		Comment				
4,425	--	--	--	--						

R = Restoration      P1 = Priority I  
 EI = Enhancement    P2 = Priority II  
 EII = Enhancement    P3 = Priority III  
 S = Stabilization      SS = Stream Bank stabilization



**Table II. Project Activity and Reporting History**  
**Little Sugar Creek Stream Restoration Site (EEP Project #141)**

<b>Activity or Report</b>	<b>Scheduled Completion</b>	<b>Data Collection Complete</b>	<b>Actual Completion or Delivery</b>	<b>Comments</b>
<b>Restoration Plan</b>			Oct-02	
<b>Final Design – 90%</b>				
<b>Construction</b>	2003		Sept-03	
<b>Temporary S&amp;E mix applied to entire project area</b>	2003		Sept-03	
<b>Permanent seed mix applied</b>	2003		Sept-03	
<b>Containerized and B&amp;B plantings for reach/segments 1&amp;2</b>	2004		June-04	
<b>Mitigation Plan / As-built (Year 0 Monitoring –</b>	2004		Spring 04	Performed by NCSU
<b>Year 1 monitoring</b>	2005	Oct-05	Nov-05	Performed by SEC, PA
<b>Year 2 Monitoring</b>	2006	Oct-06	Jan-07	Performed by KHA, Inc.
<b>Year 3 Monitoring</b>	2007	Nov-07	Feb-08	Performed by KHA, Inc.
<b>Repair</b>	2008		Winter-08	Plans prepared Baker Engineer, Construction performed by Fluvial Solutions
<b>Year 4 Monitoring</b>	2008	Oct-08	May-09	Performed by KHA, Inc.
<b>Year 5 Monitoring</b>	2009	Sept-09	November-09	Performed by KHA, Inc.
<b>Year 6 Monitoring</b>	2010	Sept-10	November-10	Performed by KHA, Inc.



<b>Table III. Project Contact Table</b>		
<b>Little Sugar Creek Stream Restoration Site (EEP Project #141)</b>		
<b>Designer</b>	128 South Tryon St., Suite 1400	
HDR Engineering, Inc. of the Carolinas	Charlotte, NC 28202	
<b>Primary Designer POC</b>		
<b>Construction Contractor</b>	5100 North I-85, Suite 7	
SEI Environmental	Charlotte, NC 28206	
<b>Primary Contractor POC</b>		
<b>Planting Contractor</b>		
<b>Planting contractor POC</b>		
<b>Seeding Contractor</b>		
<b>Planting contractor POC</b>		
<b>Seed Mix Sources</b>		
<b>Nursery Stock Suppliers</b>		
<b>Monitoring Performers</b>	PO Box 33068	
Kimley-Horn and Associates	Raleigh, NC 27636	
<b>Stream Monitoring POC</b>	Daren Pait	(919) 677-2000
<b>Vegetation Monitoring POC</b>	Daren Pait	(919) 677-2000

**Table IV. Project Background Table  
Little Sugar Creek Stream Restoration Site (EEP Project #141)**

<b>Project County</b>	Mecklenburg
<b>Drainage Area</b>	13.6 square miles
<b>Drainage impervious cover estimate (%)</b>	75%
<b>Stream Order</b>	3
<b>Physiographic Region</b>	Piedmont
<b>Ecoregion</b>	Charlotte Belt
<b>Rosgen Classification of As-built</b>	C4
<b>Cowardin Classification</b>	N/A
<b>Dominant soil types</b>	Cecil, Monacan
<b>Reference site ID</b>	N/A
<b>USGS HUC for Project and Reference</b>	03050103
<b>NCDWQ Sub-basin for Project and Reference</b>	03-08-34
<b>NCDWQ classification for Project and Reference</b>	C
<b>Any portion of any project segment 303d listed?</b>	No
<b>Any portion of any project segment upstream of a 303d listed segment?</b>	No
<b>Reasons for 303d listing or stressor</b>	No
<b>% of project easement fenced</b>	0%



APPENDIX A  
VEGETATION MONITORING DATA

**Table I. Vegetative Metadata  
Little Sugar Creek Stream Restoration Site (EEP Project #141)**

Report Prepared By	Joshua Allen
Date Prepared	11/9/2010 12:04
database name	141_Freedom Park.mdb
database location	K:\RAL_Environmental\011795 Freedom Park Monitoring FPARK\FPARK VEGETATION
computer name	DD83075
file size	62599168
DESCRIPTION OF WORKSHEETS IN THIS DOCUMENT-----	
Metadata	Description of database file, the report worksheets, and a summary of project(s) and project data.
Proj, planted	Each project is listed with its PLANTED stems per acre, for each year. This excludes live stakes.
Proj, total stems	Each project is listed with its TOTAL stems per acre, for each year. This includes live stakes, all planted stems, and all natural/volunteer stems.
Plots	List of plots surveyed with location and summary data (live stems, dead stems, missing, etc.).
Vigor	Frequency distribution of vigor classes for stems for all plots.
Vigor by Spp	Frequency distribution of vigor classes listed by species.
Damage	List of most frequent damage classes with number of occurrences and percent of total stems impacted by each.
Damage by Spp	Damage values tallied by type for each species.
Damage by Plot	Damage values tallied by type for each plot.
ALL Stems by Plot and spp	A matrix of the count of total living stems of each species (planted and natural volunteers combined) for each plot; dead and missing stems are excluded.
PROJECT SUMMARY-----	
Project Code	141
project Name	Freedom Park
Description	Riparian Buffer Restoration
River Basin	
length(ft)	
stream-to-edge width (ft)	
area (sq m)	
Required Plots (calculated)	
Sampled Plots	0



**Table II. Vegetation Vigor by Species**  
**Little Sugar Creek Stream Restoration Site (EEP Project**  
**#141)**

	<b>Species</b>	<b>4</b>	<b>3</b>	<b>2</b>	<b>1</b>	<b>0</b>	<b>Missing</b>
	Alnus serrulata			1			
	Betula nigra	13	2				
	Cornus amomum	5	2				
	Fraxinus pennsylvanica	8		1			
	Quercus falcata	2					1
	Quercus michauxii	1					
	Quercus phellos	3					
	Salix nigra	4	4	1			1
	Sambucus canadensis			6			
	Morus rubra	4					
	Platanus occidentalis	3			1		
	Populus deltoides	3					2
	Acer rubrum			1			
	Unknown	6					
<b>TOT:</b>	14	52	8	10	1		4

**Table III. Vegetation Damage by Species  
Little Sugar Creek Stream Restoration Site (EEP Project #141)**

	<i>Species</i>	<i>All Damage Categories</i>	<i>(no damage)</i>	<i>Diseased</i>	<i>Flood</i>
	Acer rubrum	1	1		
	Alnus serrulata	1			1
	Betula nigra	15	15		
	Cornus amomum	7	7		
	Fraxinus pennsylvanica	9	9		
	Morus rubra	4	4		
	Platanus occidentalis	4	3	1	
	Populus deltoides	5	5		
	Quercus falcata	3	3		
	Quercus michauxii	1	1		
	Quercus phellos	3	3		
	Salix nigra	10	5		5
	Sambucus canadensis	6	6		
	Unknown	6	6		
	TOT: 14	75	68	1	6



**Table IV. Vegetation Damage by Plot  
Little Sugar Creek Stream Restoration Site (EEP Project  
#141)**

	<i>plot</i>	<i>All Damage Categories</i>	<i>(no damage)</i>	<i>Diseased</i>	<i>Flood</i>
	141-01-0001-year:4	6	6		
	141-01-0002-year:4	23	17		6
	141-01-0003-year:4	18	18		
	141-01-0004-year:4	11	11		
	141-01-0005-year:4	15	15		
	141-01-0006-year:4	2	1	1	
TOT:	6	75	68	1	6

**Table V. Stem Count by Plot and Species  
Little Sugar Creek Stream Restoration Site (EEP Project #141)**

Species	Total Planted Stems	# plots	avg# stems	plot 141-01-0001-year:4	plot 141-01-0002-year:4	plot 141-01-0003-year:4	plot 141-01-0004-year:4	plot 141-01-0005-year:4	plot 141-01-0006-year:4	
Acer rubrum	1	1	1						1	
Alnus serrulata	1	1	1		1					
Betula nigra	15	4	3.75	3	4	6		2		
Cornus amomum	7	1	7		7					
Fraxinus pennsylvanica	9	2	4.5				7	2		
Morus rubra	4	2	2			1		3		
Platanus occidentalis	4	4	1	1		1		1	1	
Populus deltoides	3	1	3		3					
Quercus falcata	2	2	1				1	1		
Quercus michauxii	1	1	1			1				
Quercus phellos	3	3	1	1			1	1		
Salix nigra	9	3	3	1	6	2				
Sambucus canadensis	6	1	6			6				
Unknown	6	3	2			1	1	4		
TOT:	14	71	14		6	21	18	10	14	2



Table VI. Vegetative Problem Areas			
Little Sugar Creek Stream Restoration Site (EEP Project #141)			
Feature/Issue	Station # / Range	Probable Cause	Photo #
<b>2010</b>			
Bare Bank	--	--	
Bare Bench	--	--	
Bare Floodplain	--	--	
Invasive/Exotic Populations	--	--	
<b>2009</b>			
Bare Bank	--	--	
Bare Bench	--	--	
Bare Floodplain	--	--	
Invasive/Exotic Populations	--	--	
<b>2008</b>			
Bare Bank	520 - 700 (Right Bank)	Excessive bank stresses during yearly flooding events	VP1
	520 - 700 (Left Bank)	Excessive bank stresses during yearly flooding events	
	1,690 - 1,750 (Left Bank)	Excessive bank stresses during yearly flooding events	VP2
	2,030 - 2,110 (Left Bank)	Excessive bank stresses during yearly flooding events	
	2,220 - 2,330 (Right Bank)	Excessive bank stresses during yearly flooding events	
	2,220 - 2,330 (Left Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
Bare Bench	--	--	
Bare Flood Plain	1,070 - 1,250 (Right Floodplain)	Cleared for staging area for channel maintenance	VP3
	4,000 - 4,250 (Right Floodplain)	Cleared for staging area for channel maintenance	
Invasive/Exotic Populations	--	--	
<b>2007</b>			
Bare Bank	100 - 350 (Right Bank)	Excessive bank stresses during yearly flooding events	
	400 - 700 (Right Bank)	Excessive bank stresses during yearly flooding events	
	750 - 775 (Right Bank)	Excessive bank stresses during yearly flooding events	
	800 - 850 (Right Bank)	Excessive bank stresses during yearly flooding events	
	930 - 950 (Right Bank)	Excessive bank stresses during yearly flooding events	
	1,690 - 1,750 (Left Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
	2,070 - 2,130 (Right Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
	2,250 - 2,600 (Left Bank)	Excessive bank stresses during yearly flooding events	
	2,280 - 2,335 (Right Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
	2,600 - 2,700 (Left Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
	3,010 - 3,070 (Left Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
	3,120 - 3,190 (Right Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
Bare Bench	--	--	
Bare Flood Plain	1,250 - 1,580 (Left Floodplain)	Cleared area exhibiting successional growth including invasives from local sources	
	2,065 - 2,200 (Left Bank)	Excessive bank stresses during yearly flooding events or invasive treatment	
Invasive/Exotic Populations	1,250 - 1,580 (Left Floodplain)	Cleared area exhibiting successional growth including invasives from local sources	
<b>2006</b>			
Bare Bank	410 - 1,140 (Both Banks)	Excessive bank stresses during yearly flooding events	
	1,690 - 1,750 (Left Bank)		
	2,065 - 2,350 (Both Banks)		
Bare Bench	--	--	
Bare Flood Plain	1,250 - 1,580 (Left Floodplain)	Cleared area exhibiting successional growth	
Invasive/Exotic Populations	35 - 1,030 (Both Banks)	Local source colonization after bank scour	
	1,240 - 1,860 (Left Bank)		
	1,250 - 1,580 (Left Floodplain)	Cleared area exhibiting successional growth including invasives from local sources	
	1,950 - 2,190 (Left Bank)		
	2,210 - 2,380 (Right Bank)		
	2,680 - 3,065 (Left Bank)		
	2,690 - 3,555 (Right Bank)		
3,555 - 3,790 (Left Bank)			
<b>2005</b>			
Bare Bank	2,100 - 2,175	Overbank flow / Compacted soils	
	2,560 - 2,735	Overbank flow / Compacted soils	
<b>2004</b>			
General	2,500 - 2,800	Left bank has poor herbaceous success	
	3,100 - 3,200	Left bank has poor herbaceous success	
	3,400 - 3,500	Right bank has poor herbaceous success	
	3,700 - 4,479	Both banks have poor herbaceous success	
	throughout	Poor hardwood tree and live stake establishment	





VQ1: Vegetation Quad 1  
Taken: 2005



VQ1: Vegetation Quad 1  
Taken: 10/19/2006





VQ1: Vegetation Quad 1  
Taken: 10/16/2007



VQ1: Vegetation Quad 1  
Taken: 11/03/2008





VQ1: Vegetation Quad 1  
Taken: 2009



VQ1: Vegetation Quad 1  
Taken: 2010





VQ2: Vegetation Quad 2  
Taken: 2005



VQ2: Vegetation Quad 2  
Taken: 10/19/2006





VQ2: Vegetation Quad 2  
Taken: 10/16/2007



VQ2: Vegetation Quad 2  
Taken: 11/03/2008





VQ2: Vegetation Quad 2  
Taken: 2009



VQ2: Vegetation Quad 2  
Taken: 2010





VQ3: Vegetation Quad 3  
Taken: 2005



VQ3: Vegetation Quad 3  
Taken: 10/19/2006





VQ3: Vegetation Quad 3  
Taken: 10/16/2007



VQ3: Vegetation Quad 3  
Taken: 11/03/2008





VQ3: Vegetation Quad 3  
Taken: 2009



VQ3: Vegetation Quad 3  
Taken: 2010





VQ4: Vegetation Quad 4  
Taken: 2005



VQ4: Vegetation Quad 4  
Taken: 10/19/2006





VQ4: Vegetation Quad 4  
Taken: 10/16/2007



VQ4: Vegetation Quad 4  
Taken: 11/03/2008





VQ4: Vegetation Quad 4  
Taken: 2009



VQ4: Vegetation Quad 4  
Taken: 2010





VQ5: Vegetation Quad 5  
Taken: 10/19/2006



VQ5: Vegetation Quad 5  
Taken: 10/16/2007





VQ5: Vegetation Quad 5  
Taken: 11/03/2008



VQ5: Vegetation Quad 5  
Taken: 2009





VQ5: Vegetation Quad 5  
Taken: 2010





VQ6: Vegetation Quad 6  
Taken: 10/19/2006



VQ6: Vegetation Quad 6  
Taken: 10/16/2007





VQ6: Vegetation Quad 6  
Taken: 11/03/2008



VQ6: Vegetation Quad 6  
Taken: 2009





VQ6: Vegetation Quad 6  
Taken: 2010