

# Little Alamance Creek (Burlington Park) Stream Restoration 2013 Monitoring Report Monitoring Year 2 of 5

Alamance County, NC  
Cape Fear River Basin  
Cataloging Unit: 03030002  
NCEEP Project Number: 92372  
NCEEP Contract Number: 4998



## Submitted To:

North Carolina Department of Environment and Natural Resources  
Ecosystem Enhancement Program  
1652 Mail Service Center  
Raleigh, NC 27699-1652

**FINAL** – 2013 Monitoring Report – Year 2 of 5

Project Construction Completed: 2012  
Data Collection for Monitoring Year 2 of 5  
Report Submitted: January 2014



**Little Alamance Creek (Burlington Park) Stream Restoration  
2013 Monitoring Report  
Monitoring Year 2 of 5**

**Alamance County, NC  
Cape Fear River Basin**

**Submitted to:**  
**North Carolina Department of Environment and Natural Resources**  
**Ecosystem Enhancement Program**  
1652 Mail Service Center  
Raleigh, NC 27699-1652

**Prepared by:**  
**EEE Consulting, Inc.**  
601 Cascade Pointe Lane, Suite 101  
Cary, NC 27513

**Project Manager:**  
Ray Bode, PWS  
(919) 650-2463 ext. 225  
rbode@eee-consulting.com

January 2014

**FINAL**

**TABLE OF CONTENTS**

**1. Executive Summary/Project Abstract.....2**  
**2. Methodology.....4**  
     **2.1 Stream Survey Methodology.....4**  
     **2.2 Vegetation Survey Methodology.....4**  
**3. References.....5**

**APPENDICES, FIGURES, and TABLES**

Appendix A: Project Vicinity Map and Background Tables

- Figure 1: Vicinity Map
- Table 1: Project Components and Mitigation Credits
- Table 2: Project Activity and Reporting History
- Table 3: Project Contacts Table
- Table 4: Project Attribute Table

Appendix B: Visual Assessment Data

- Figure 2: Current Condition Plan View
- Figure 3: Conservation Easement Marked Posts
- Figure 4: Final Conservation Easement Plat
- Figure 5: Conservation Easement Coordinate List
- Table 5: Visual Stream Morphology Stability Assessment
- Table 6: Vegetation Condition Assessment
- Photo Log 1: Established Photo Stations
- Photo Log 2: Vegetation Plot Photos

Appendix C: Vegetation Plot Data

- Table 7: Vegetation Plot Success by Project Asset Type
- Table 8: CVS Stem Count Total and Planted with/without Livestakes by Plot and Species

Appendix D: Stream Survey Data

- Figure 6: Cross Section with Annual Overlays
- Figure 7: Longitudinal Profiles with Annual Overlays
- Figure 8: Pebble Counts with Annual Overlays
- Table 9: Stream Bank Erosion Pin Data Table
- Table 10a: Baseline Stream Data Summary
- Table 10b: Baseline Stream Data Summary (Substrate, Bed, Bank, and Hydrologic Containment Parameter Distributions)
- Table 11a: Monitoring – Cross-Section Morphology Data Table
- Table 11b: Monitoring – Stream Reach Morphology Data Table

Appendix E: Hydrologic Data

- Table 12: Verification of Bankfull Events
- Figure 9: Monthly Rainfall Data

## 1.0 EXECUTIVE SUMMARY / PROJECT ABSTRACT

The primary goals of this stream restoration project focus on improving water quality, enhancing flood attenuation, and restoring aquatic habitat. These goals will be accomplished by the following objectives:

- Reducing non-point sources of pollution associated with former lawn maintenance in the park area by providing a vegetative buffer adjacent to Little Alamance Creek and its unnamed tributary (UT) and the installation of stormwater best management practices to treat surface runoff. The riparian buffer will remain in a State-owned conservation easement in perpetuity.
- Reducing sedimentation on-site and in downstream receiving waters through a reduction of bank erosion associated with current vegetation maintenance practices and by providing a forested vegetative buffer adjacent to Little Alamance Creek and its tributary.
- Reestablishing stream stability and the capacity to transport watershed flows and sediment loads by restoring stable dimension, pattern, and profile.
- Promoting floodwater attenuation through increased flood storage capacity by construction of bankfull benches along Little Alamance Creek and its tributary.
- Improving aquatic habitat by enhancing stream bed variability.

The Site consists of 1,293 linear feet of enhanced (Level I and II) channel along Little Alamance Creek and its UT. The project is located in City Park in the City of Burlington, Alamance County, North Carolina (Figure 1). The surrounding land use is recreational and the project is easily accessible by the public. Little Alamance Creek and its UT are located in the 8-digit Hydrologic Unit Code (HUC) 03030002; the 14-digit Local Watershed Unit HUC 03030002-040010; and the North Carolina Division of Water Quality (NCDWQ) Subbasin 03-06-03 (NCDWQ, 2005). The project lies within the Southern Outer Piedmont ecoregion of the Piedmont physiographic province of NC (Griffith *et al.*, 2002). The North Carolina Ecosystem Enhancement Program (NCEEP) has identified the Cape Fear HUC 03030002, and in particular Little Alamance Creek, in their Local Watershed Plan as needing repair along with conservation opportunities. Watersheds in this plan exhibit the need and opportunity for stream and riparian buffer restoration (NCDENR, 2001). In 2000, Little Alamance Creek was listed as impaired by the NCDWQ due to poor stream biological ratings (NCEEP, 2008).

Little Alamance Creek was originally planted in April, 2012. On September 11, 2012, the site was inspected by NCEEP and vegetative sampling reported higher mortality than contractually permissible. Of the 15 inspection plots, 6 did not meet the 80 percent survival warranty. The areas identified as needing supplemental planting were re-planted on December 12, 2012. Monitoring Year 1 efforts showed that the site is currently meeting vegetation success criteria of 320 stems per acre at most plot locations. However, monitoring year 2 efforts report the majority of the site is not meeting the success criteria. Monitoring in year 1 occurred in March and was



therefore difficult to distinguish between volunteer and planted stems as there were no leaves on the plants. This made identification difficult. Only vegetation plots 1 and 6 have met the 320 stems per acre requirement (Appendix C; Table 7). Volunteer species are establishing on site as expected and thus increasing the overall stems per acre. Volunteer species have increased the stems per acre over 320 for all plots except vegetation plot 5, 7, and 8. Several invasive species were identified throughout the project reach. These species include white mulberry (*Morus alba*), tree of heaven (*Ailanthus altissima*), Chinese privet (*Ligustrum sinense*), Japanese privet (*Ligustrum japonicum*). Mostly these species occurred at very low density as single isolated stems and therefore do not impose a treat. Only areas with a cluster of stems were noted and recorded. Three areas were identified with invasive species in the conservations easement (Figure 2) in monitoring year 1. Along the upper reaches of the UT, multiflora rose (*Rosa multiflora*) was observed. These areas are negligible in size and are represented as point features. Along the upper reach of the mainstem, Chinese privet (*Ligustrum sinense*) was observed. This area was also negligible in size and is represented as a point feature. Three additional problems were identified in monitoring year 2 efforts (Figure 2). These sites were observed in Year 1, but have grown to warrant reporting. In vegetation plot 1, by cross section 2, several stems of Chinese privet and white mulberry was identified. English ivy (*Hedera helix*) was also noted. By cross section 9, several stems of multiflora rose was identified along both the right and left bank. Downstream of vegetation plot 8, along the left bank, virginsbower (*Clematis terniflora*) was observed in unusually high density. Overall, the presence of invasive species is minor, covering approximately 7 percent of the planted easement. These areas will continue to be monitored in the upcoming monitoring years. In addition, evidence of recent beaver activity (fresh chews and tracks) were observed throughout the entire length of the project reach. No other problems areas were observed.

In general, the Little Alamance Creek Stream Restoration Site is in very good condition. All structures are intact and performing as intended. The Monitoring Year 1 and 2 thalweg has not deviated from the design thalweg. Monitoring year 1 identified one area along the UT downstream of cross section 14 that had lateral bank erosion for approximately 75 feet (Figure 2). In monitoring year 2, this area was noted to be increasing in severity. In 2013, there were several heavy rain events that caused high flow and flooding (Appendix E). As a result, several new stream problem areas have occurred (Figure 2). Immediately downstream of cross section 1, the left bank displayed lateral bank erosion for approximately 100 feet. This was observed in Monitoring Year 1, but the storm events have increased the severity of erosion to warrant reporting. Immediately downstream of cross section 9, the left bank displayed lateral bank erosion for approximately 30 feet. At the confluence of the UT and mainstem, a mid-channel bar has formed. There was also lateral bank erosion at the confluence along the left bank for approximately 50 feet. Minor changes in the mainstem bed profile have occurred during Monitoring Year 2. These changes are likely a result of substrate mobilization during the large flood events. This type of substrate movement is characteristic of natural geomorphic processes and does not appear to pose a risk for vertical incision or lateral bank erosion. These areas will continue to be monitored. Along the UT, two pools displayed significant aggradation as seen on the longitudinal profile graphic. These areas will continue to be monitored in the upcoming monitoring years. No other problems areas were observed. Two crest gauges were installed

during Monitoring Year 1; one gauge along the mainstem of Little Alamance Creek and one gauge along the UT. These gauges were checked in Monitoring Year 2 (Appendix E).

Wetland mitigation is not a part of this project.

Summary information/data related to the occurrence of items such as beaver or encroachment and statistics related to performance of various project and monitoring elements can be found in the tables and figures in the report appendices. Narrative background and supporting information formerly found in these reports can be found in the Baseline Monitoring Report (formerly Mitigation Plan) and in the Mitigation Plan (formerly the Restoration Plan). These documents are available on NCEEP's website. All raw data supporting the tables and figures in the appendices is available from NCEEP upon request.

## 2.0 METHODOLOGY

All monitoring methodologies follow NCEEP's 2011 *Monitoring Requirements and Performance Standards for Stream and/or Wetland Mitigation* (NCEEP, 2011). This monitoring report is consistent with NCEEP's *Monitoring Report Template Version 1.5* adopted June 8, 2012. GPS data was collected using sub-meter accuracy Trimble Geo XH handheld unit. Stream and vegetation problems areas were identified and noted in the field on As-Built Plan Sheets prepared by ARCADIS G&M of North Carolina (ARCADIS, 2012). Twenty permanent photo stations were established during the project set up by EEE Consulting, Inc. (EEE) and photographs were taken from these locations (Figure 2). Photographs were taken at a high resolution using a Sony Cyber-shot 14.1 megapixel digital camera.

### 2.1 STREAM SURVEY METHODOLOGY

Prior to Year 1 monitoring efforts, EEE established eight permanent riffle cross-sections and six permanent pool cross sections (Figure 2). GPS points were collected on both banks of each established cross section. The entire length of mitigation, 2,725 linear feet of stream profile, was surveyed. Stream monitoring and geomorphological surveys were performed consistent with the USACE 2003 *Stream Mitigation Guidelines* and the USDA 1994 Forest Service Manual *Stream Channel Reference Sites: An Illustrated Guide to Field Technique* (USACE, 2003; Harrelson *et al*, 1994). Stream survey data was collected using a Nikon total station with a Recon data logger and is georeferenced in NAD83-State Plane Feet-FIPS3200. The data were analyzed using RIVERMorph. Pebble counts were conducted consistent with the 1954 Wolman Pebble Count technique (modified by Rosgen, 1996). A random sample of 100 pebbles from each cross section was collected within the wetted perimeter of the channel. Samples were not taken from the banks. Photographs were taken at each cross section. A photo was taken from the left bank looking towards the right bank.

### 2.2 VEGETATION SURVEY METHODOLOGY

Prior to Year 1 monitoring efforts, EEE established eight vegetation plots per the CVS-EEP vegetation monitoring protocol (Figure 2). Five plots are 10 meters by 10 meters in size and 2

plots, (VP 6 and 7) are 20 meters by 5 meters in size. GPS points were collected all four corners of each established vegetation plot. Vegetation monitoring was performed in accordance with the 2008 CVS-EEP Protocol for Recording Vegetation for Level 1-2 Plot Sampling Only, Version 4.2 (Lee *et al*, 2008). Level 2 sampling was performed for each vegetation plot. Each corner of the vegetation plot was marked with steel electrical metallic tubing (EMT) driven into the ground. Because the project is within a public park, minimal flagging was used to mark the stems and the vegetation plot corner pins. Minimal orange flagging was used to mark only planted stems during vegetation counts. Photographs were taken at each vegetation plot from the southwest corner facing the northeast corner.

### 3.0 REFERENCES

- ARCADIS G&M of North Carolina, 2012. As-Built Survey of Little Alamance Creek Stream Restoration. Prepared for the NC Ecosystem Enhancement Program.
- Griffith, Glenn, J. Omemik, J. Comstock, 2002. Ecoregions of North Carolina Regional Descriptions. U.S. Department of Agriculture, Natural Resources Conservation Service. Corvallis. OR.
- Harrelson, Cheryl C., C.L. Rawlins, John P. Potyondy, 1994. US Department of Agriculture, Forest Service. Stream Channel Reference Sites: An Illustrated Guide to Field Technique. Available URL: [http://www.fs.fed.us/rm/pubs\\_rm/rm\\_gtr245.pdf](http://www.fs.fed.us/rm/pubs_rm/rm_gtr245.pdf). [Date Accessed: 4 January 2013].
- Lee, Michael T., R. K. Peet, S. D. Roberts, and T. R. Wentworth. 2006. CVS-EEP Protocol for Recording Vegetation, Version 4.0 Available URL: <http://cvs.bio.unc.edu/methods.htm>. [Date Accessed: 4 January 2013].
- NC Division of Water Quality, 2005. Cape Fear River Basin Water Quality Plan. Available URL: <http://portal.ncdenr.org/web/wq/ps/bpu/basin/capefear/2005>. [Date Accessed: 4 January 2013].
- NC Department of Environment and Natural Resources, 2001. Watershed Restoration Plan for the Cape Fear River Basin. Prepared by: NCDENR, NCDWQ, and NCWRP. Available URL: [http://www.nceep.net/services/restplans/cape\\_fear\\_2001.pdf](http://www.nceep.net/services/restplans/cape_fear_2001.pdf). [Date Accessed: 4 January 2013].
- NC Ecosystem Enhancement Program, 2008. Little Alamance, Travis, & Tickle Creek Watershed Report & Project Atlas: An Ecosystem Enhancement Program Funded Local Watershed Plan Phase III. Prepared by Piedmond Triad Council of Governments. Available URL: [http://www.ptcog.org/planning\\_services/environmental\\_planning/documents/water\\_LATTPHaseIII.pdf](http://www.ptcog.org/planning_services/environmental_planning/documents/water_LATTPHaseIII.pdf). [Date Accessed: 4 January 2013].
- NC Ecosystem Enhancement Program, 2011. Monitoring Requirements and Performance Standards for Stream and/or Wetland Mitigation. Available URL: [http://portal.ncdenr.org/c/document\\_library/get\\_file?p1\\_id=1169848&folderId=2288101&name=D\\_LFE-39234.pdf](http://portal.ncdenr.org/c/document_library/get_file?p1_id=1169848&folderId=2288101&name=D_LFE-39234.pdf). [Date Accessed: 4 January 2013].
- RIVERMorph Stream Restoration Software, Version 5.1.0. Rivermorph LLC.
- Rosgen, D.L., 1996. Applied River Morphology. Wildland Hydrology, Pagosa Springs. CO.

US Army Corps of Engineers, 2003. Stream Mitigation Guidelines. Prepared by: USACE, NCDWQ, USEPA, NCWRC. Available URL: [http://www.in.gov/idem/files/headwater\\_nc\\_stream\\_mitigation\\_guide.pdf](http://www.in.gov/idem/files/headwater_nc_stream_mitigation_guide.pdf). [Date Accessed: 4 January 2013].

## Appendix A: Project Vicinity Map and Background Tables

Figure 1: Project Vicinity Map

Table 1: Project Components and Mitigation Credits


Table 2: Project Activity and Reporting History

Table 3: Project Contacts Table

Table 4: Project Attribute Table



Directions to the Site:  
 From Raleigh, take I-40W to exit 145 for NC 49 toward Burlington/Downtown/Liberty  
 Turn right into NC 49 North / Maple Avenue  
 Turn left onto Chapel Hill Road  
 Turn right onto Pinecrest Street  
 Turn right onto Overbrook Street  
 Take second right to stay on Overbrook Street  
 Slight right to stay on Overbrook Street



Source: USDA Digital Raster Graphic Mosaic of Alamance County, NC; 2012

**Legend**

- Project Reach
- Streams
- 12 Digit HUC




Figure 1: Vicinity Map  
 Little Alamance Creek (Burlington Park) Stream Restoration  
 Alamance County  
 NCEP Project Number: 92372

EEE Consulting, Inc.  
 Cary, NC

Monitoring Year 2 of 5  
 January 2014



**Table 1. Project Components and Mitigation Credits  
Little Alamance Creek (Burlington Park) / #92372**

Mitigation Credits									
Type	Stream		Riparian Wetland		Non-riparian Wetland		Buffer	Nitrogen Nutrient Offset	Phosphorous Nutrient Offset
	R	RE	R	RE	R	RE			
Totals	1293	0							
Project Components									
Project Component -or- Reach ID	Stationing/Location *		Existing Footage/Acreage		Approach (PI, PII etc.)	Restoration -or- Restoration Equivalent	Restoration Footage or Acreage**	Mitigation Ratio	
Reach I (EII)	10+25-10+75		32.5		PIII	R	13	2.5:1	
Reach I (EI)	10+75-11+75 12+25-15+00		412.5		—	R	206	1.5:1	
Reach II –Tributary (EI)	10+25-14+75		432.5		PIII	R	204	1.5:1	
Reach III (EII)	15+50-19+00		327.5		—	R	106	2.5:1	
Reach IV (EI)	19+30-21+25 21+60-26+25		632.5		PIII	R	328	1.5:1	
Reach V (EII)	26+50-27+25		57.5		—	R	15	2.5:1	
Reach VI (EII)	27+25-28+50		102.5		—	R	20	2.5:1	
Reach VI (EI)	31+75-33+00		147.5		—	R	83	1.5:1	
Reach VI (R)	28+50-31+50		278		PI	R	220	1:1	
Reach VII (EII)	33+50-36+50		315		—	R	98	2.5:1	
Component Summation									
Restoration Level	Stream Credit Length** (linear feet)	Riparian Wetland (acres)		Non-riparian Wetland (acres)	Buffer (square feet)	Upland (acres)			
		Riverine	Non-Riverine						
Restoration	220								
Enhancement									
Enhancement I	821								
Enhancement II	252								
Creation									
Preservation									
High Quality Preservation									
BMP Elements									
Element	Location	Purpose/Function		Notes					
LS	Reach 1								
LS	Reach 4								
<b>BMP Elements</b> BR = Bioretention Cell; SF = Sand Filter; SW = Stormwater Wetland; WDP = Wet Detention Pond; DDP = Dry Detention Pond; FS = Filter Strip; S = Grassed Swale; LS = Level Spreader; NI = Natural Infiltration Area; FB = Forested Buffer									

\*Stationing/Location is not exact, but based on the stationing provided in the Record Drawings dated 10/2012.

\*\*Credit Length is based on nearest point method determined by EEP staff. Reduced credits reflect pre-existing sewer & water easements and reduced buffer widths.

**Table 2. Project Activity and Reporting History  
Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372)**

**Elapsed Time Since Grading Complete: 2 yrs 1 month**

**Elapsed Time Since Planting Complete: 2 yrs 1 month**

**Number of Reporting Years<sup>1</sup>: 2**

<b>Activity or Deliverable</b>	<b>Data Collection Complete</b>	<b>Completion or Delivery</b>
Institution Date	Nov-06	N/A
Categorical Exclusion	Sep-07	N/A
404 Permit Date	Apr-08	N/A
Restoration Plan	Jan-08	N/A
Final Design – Construction Plans	Sep-10	N/A
Construction	Feb-12	Apr-12
Seeding, bare roots, and live stake planting	Feb-12	Apr-12
Bare Root - Supplemental Planting	N/A	Dec-12
Mitigation Plan / As-built (Year 0 Monitoring - baseline)	N/A	N/A
Year 1 Monitoring	Mar-13	Jun-13
Year 2 Monitoring	Nov-14	Jan-14
Year 3 Monitoring	TBD	TBD
Year 4 Monitoring	TBD	TBD
Year 5 Monitoring	TBD	TBD

Due to contracting delays, no baseline data was collected for this project. Although there are no baseline cross sections to compare with MY1 (2013) measurements, the 2013 cross sections will serve as an adequate baseline for the remaining monitoring period. Similarly, no baseline vegetation data was collected until March 2013, approximately 13 months after planting occurred in February 2012.

Bolded items are examples of those items that are not standard, but may come up and should be included

Non-bolded items represent events that are standard components over the course of a typical project.

The above are obviously not the extent of potential relevant project activities, but are just provided as example as part of this exhibit.

If planting and morphology are on split monitoring schedules that should be made clear in the table

**Table 3. Project Contacts Table**  
**Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372)**

<b>Designer</b>	ARCADIS G&M of North Carolina, Inc 801 Corporate Drive, Suite 300 Raleigh, NC 27607
Primary project design POC	Robert Lepsic (919) 854-1282 ext. 195
<b>Construction Contractor</b>	Shamrock Environmental Corporation 6106 Corporate Park Drive Browns Summit, NC 27214
Construction contractor POC	(336) 375-1989
<b>Survey Contractor</b>	Turner Land Surveying, PLLC 3201 Glenridge Drive Raleigh, NC 27604
Survey contractor POC	Elisabeth Turner (919) 875-1378
<b>Planting Contractor</b>	Carolina Wetland Services 550 East Westinghouse Boulevard Charlotte, NC 28273
Planting contractor POC	(704) 527-1177
<b>Seeding Contractor</b>	Information Not available
Contractor point of contact	POC name and phone
<b>Seed Mix Sources</b>	Information Not available
<b>Nursery Stock Suppliers</b>	Native, Inc. (704) 527-1177
<b>Monitoring Performers</b>	EEE Consulting, Inc. 601 Cascade Pointe Lane Suite 101 Cary, NC 27513
Stream Monitoring POC	Ray Bode, PWS (919) 650-2463 ext. 225
Vegetation Monitoring POC	Tina Sekula, PWS (919) 650-2463 ext. 223

**Table 4. Project Attribute Table**  
**Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372)**

Project Information							
Project Name	Little Alamance Creek (Burlington Park) Stream Restoration						
County	Alamance County						
Project Area (acres)	7.06 acres						
Project Coordinates (latitude and longitude)	36.083566 ; -79.454233						
Project Watershed Characteristics							
Physiographic Province	Piedmont						
River Basin	Cape Fear						
USGS Hydrologic Unit 8-digit: 03030002	USGS Hydrologic Unit 14-digit: 3030002040010						
DWQ Sub-basin	03-06-03						
Project Drainage Area (acres)	2690 acres						
Project Drainage Area Percentage of Impervious Area	40 percent						
CGIA Land Use Classification	Forest Land						
Reach Summary Information							
Parameters	Reach I	Trib	Reach III	Reach IV	Reach V	Reach VI	Reach VII
Length of Reach (linear feet)	445 lf	432.5 lf	327.5 lf	632.5 lf	57.5 lf	528 lf	315 lf
Valley Classification	Type VIII	Type VIII	Type VIII	Type VIII	Type VIII	Type VIII	Type VIII
Drainage area (acres)	2600 ac	124 ac	2630 ac	2650 ac	2655 ac	2680 ac	2690 ac
NCDWQ Stream Identification Score	47.5	33	47.5	47.5	47.5	47.5	47.5
NCDWQ Water Quality Classification	WS-V;NSW	WS-V;NSW	WS-V;NSW	WS-V;NSW	WS-V;NSW	WS-V;NSW	WS-V;NSW
Morphological Description (stream type)	C/E5/1	E4/1	C/E5/1	C/E5/1	C/E5/1	C/E5/1	C/E5/1
Evolutionary Trend	C4/1	C4/1	C4/1	C4/1	C4/1	C4/1	C4/1
Underlying Mapped Soils	Cecil fine sandy loam (CbC2)						
Drainage Class	Well drained						
Soil Hydric Class	Non-Hydric						
Slope	6 to 10 percent slopes						
FEMA Classification	AE Floodzone	No Study	AE Floodzone	AE Floodzone	AE Floodzone	AE Floodzone	AE Floodzone
Native Vegetation Community	Mixed Mesic Forest						
Percent composition of exotic invasive vegetation	5 percent						
Regulatory Considerations							
Regulation	Applicable?	Resolved?	Supporting Documentation				
Waters of the United States - Section 404	Yes	Yes	Nationwide Permit 27 (Action ID SAW-2008-01198 )				
Waters of the United States - Section 401	Yes	Yes	Nationwide Permit 27 (Action ID SAW-2008-01198 )				
Endangered Species Act	No	N/A	N/A				
Historic Preservation Act	No	N/A	N/A				
Coastal Zone Management Act (CZMA)/ Coastal Area Management Act (CAMA)	No	N/A	N/A				
FEMA Floodplain Compliance	Yes	Yes	FEMA Floodplain Consistency Checklist (Categorical Exclusion)				
Essential Fisheries Habitat	No	N/A	N/A				



## Appendix B: Visual Assessment Data

Figure 2: Current Condition Plan View

Figure 3: Conservation Easement Marked Posts

Figure 4: Final Conservation Easement Plat


Figure 5: Conservation Easement Coordinate List

Table 5: Visual Stream Morphology Stability Assessment

Table 6: Vegetation Condition Assessment

Photo Log 1: Established Photo Stations

Photo Log 2: Vegetation Monitoring Plot Photos



Source: USDA FSA NAIP Aerial Photograph North Carolina 2012

Veg Plot SW Corner	Latitude	Longitude
1	36.082439988	-79.456324099
2	36.083243440	-79.456564421
3	36.083136923	-79.455737460
4	36.082799516	-79.455317425
5	36.083474857	-79.455096845
6	36.083809437	-79.452847391
7	36.083482988	-79.452740202
8	36.082870312	-79.451806985

XS Pins	X	Y	XS Pins	X	Y
1 LT	36.083434822400	-79.456434322100	8 LT	36.083781004500	-79.452795534100
1 RT	36.083288774000	-79.456479096900	8 RT	36.083649585800	-79.452946669000
2 LT	36.083255852600	-79.455878029400	9 LT	36.083747714100	-79.452739263800
2 RT	36.083107328000	-79.456039660700	9 RT	36.083611010500	-79.452856235800
3 LT	36.083095444000	-79.455736123000	10 LT	36.083629805400	-79.452557535900
3 RT	36.082978864100	-79.455903359700	10 RT	36.083502341700	-79.452590178100
4 LT	36.083255035400	-79.454862386800	11 LT	36.082318048600	-79.456590293700
4 RT	36.083245857200	-79.454650758400	11 RT	36.082240928000	-79.456485794000
5 LT	36.084066109200	-79.453325103200	12 LT	36.082403342300	-79.456427765400
5 RT	36.083930338000	-79.453290470100	12 RT	36.082303040000	-79.456373839200
6 LT	36.083893647700	-79.452956931200	13 LT	36.082438153700	-79.456359426500
6 RT	36.083792325100	-79.453114194900	13 RT	36.082389676100	-79.456198681800
7 LT	36.083823409000	-79.452864854500	14 LT	36.082581815700	-79.456025302200
7 RT	36.083721650900	-79.453013892000	14 RT	36.082490083700	-79.455969614400

**Legend**

- Crest Gauges
- Photostations
- Invasive Species
- Bank Instability
- Existing Crossings
- Cross Sections
- Conservation Easement
- Contours (4ft)
- Designed Centerline
- MY1 Thalweg
- MY2 Thalweg
- Designed Top of Bank
- Structures
- VP Criteria Not Met
- VP Criteria Met
- Utility Easement





Figure 2: Current Condition Plan View  
 Little Alamance Creek (Burlington Park) Stream Restoration  
 Alamance County  
 NCEEP Project Number: 92372



EEE Consulting, Inc.  
 Cary, NC

Monitoring Year 2 of 5  
 January 2014





**Property Information:**  
 Owner: City of Burlington  
 Alamance County Parcel ID# 8864790671  
 Alamance County Tax Map # 104-442-217

**Deed References:** Deed Book 98 Page 220  
 Deed Book 136 Page 46

**Reference Boundary Survey Plat prepared by**  
 City of Burlington Engineering Department  
 Entitled Final Plat Property of, City of Burlington  
 City Park Map #1, Dated September 14, 1995

**Conservation Easement Notes:**  
 Total Area in Conservation Easement: 6.98 Acres ±  
 0.25 Acres± in Temporary Construction Easement

All corners of the Conservation Easement are marked with Rebar and Aluminum NCEEP Caps, unless noted.

**LEGEND**

- Existing Iron Pipe
- New Iron Pipe
- Man Hole
- Monument
- Power Pole
- Utility Line

**LINE TABLE**

Line #	Bearing	Distance
Tie L-1	S 39°26'01" W	60.99'

GPS CO-ORDINATES  
 PROVIDED BY ARCADIS  
 N 84926.62  
 E 1864965.29

**CURVE TABLE**

Curve #	Bearing	Chord	Radius	Arc
C-1	N 82°35'42" W	28.28'	100.00'	28.38'
C-2	N 69°24'31" W	17.63'	100.00'	17.65'
C-3	N 46°32'36" W	61.15'	100.00'	62.15'

**LINE TABLE**

Line #	Bearing	Distance
L-1	N 70°36'20" E	36.93'
L-2	N 69°20'21" E	46.63'
L-3	N 59°47'13" E	57.06'
L-4	S 43°59'57" E	41.68'
L-5	S 60°52'02" E	40.00'
L-6	S 66°12'35" W	56.03'
L-7	S 37°12'39" W	64.04'
L-8	S 67°18'44" W	43.27'
L-9	N 51°42'28" W	51.48'
L-10	N 49°25'20" W	63.45'
L-11	N 04°58'22" W	38.00'
L-12	N 29°35'00" E	54.44'
L-13	S 32°05'35" E	46.29'
L-14	N 00°16'40" E	42.66'
L-15	N 50°23'34" E	27.84'
L-16	N 69°21'29" E	58.74'
L-17	S 71°40'25" E	7.97'
L-18	N 66°26'32" E	8.90'
L-19	N 63°50'04" E	20.72'
L-20	S 71°13'11" E	27.32'
L-21	S 56°14'03" E	12.12'
L-22	N 88°59'18" E	41.52'
L-23	S 83°12'35" E	86.33'
L-24	N 81°39'06" E	66.07'
L-25	S 63°06'28" E	67.20'
L-26	S 00°33'50" W	42.52'
L-27	S 34°22'35" W	46.94'
L-28	S 82°55'27" W	40.80'
L-29	N 44°24'47" E	49.65'
L-30	S 84°59'13" W	62.40'
L-31	S 54°17'14" E	48.24'
L-32	N 81°18'07" W	50.71'
L-33	S 39°38'58" W	41.12'
L-34	N 04°26'24" W	28.11'

**Certificate of Accuracy**

State of North Carolina, County of Alamance  
 I, Douglas R. Yarbrough, certify that under my direction and supervision this map was drawn from an actual field land survey made by me; that the error of closure as calculated by latitudes and departures is: 1: 10,000 for the perimeter and 1:10,000 for plotting of interior lot lines; that the boundaries not surveyed are shown as broken lines plotted from deed information found in deed book 136, page 46; that this map was prepared in accordance with GS 47-30 as amended; that the survey was requested by the owner or his duly authorized agent; that all required monuments and markers have been installed; that all new lines calculated from data not obtained in the field are indicated by a "C"; and that this plat is within the Jurisdiction of the City of Burlington.

Witness my hand and seal this 5th day of May, 2008.

Douglas R. Yarbrough, Professional Land Surveyor L-3395

I, Douglas R. Yarbrough, Professional Land Surveyor, L-3395, Certify To one of the following:  
 A. This survey creates a subdivision of land within the area of a county or municipality that has an ordinance that regulates parcels of land.  
 B. This survey is located in such portion of a county or municipality that is designated as to an ordinance that regulates parcels of land.  
 C. Any one of the following:  
 1. That the survey is of an existing parcel or parcels of land and does not create a new street or change an existing street;  
 2. That the survey is of an existing building or other structure, or natural feature, such as a watercourse; or  
 3. The survey is a control survey.  
 D. This survey is of another category, such as the recombination of existing parcels, a court-ordered survey, or other exception to the definition of subdivision.  
 E. The information available to the surveyor is such that the surveyor is unable to make a determination to the best of his or her professional ability as to provisions contained in 1-4 above.

Douglas R. Yarbrough, Professional Land Surveyor, L-3395

**Certificate of Ownership and Dedication**

I, (we) hereby certify that I (we) am (are) the owner(s) of the property, shown and described hereon, which was conveyed to me (us) by deed as recorded in deed book 136, page 46, and that I (we) hereby acknowledge this plat and allotment to be my(our) free act and deed and do hereby dedicate to public use as streets, rights-of-way, and easements forever, all areas so shown or indicated on said plat.

Witness my hand and official stamp or seal, this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Notary Public  
 My commission expires \_\_\_\_\_

**Planning Director Certification**

NO APPROVAL REQUIRED UNDER SECTION 33-1 OF THE CODE OF ORDINANCES OF THE CITY OF BURLINGTON.

PLANNING DIRECTOR \_\_\_\_\_

**City of Burlington Certification**

Recommended by the Burlington Planning and Zoning Commission on the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Chairman of Planning and Zoning Commission \_\_\_\_\_

Approved by the Burlington City Council on the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_ provided that the plat be recorded within sixty (60) days of final approval.  
 City Clerk \_\_\_\_\_

**Review Officer Certification**

State of North Carolina, County of Alamance

I, \_\_\_\_\_, Review Officer of Alamance County, certify that the map or plat to which this certification is affixed meets all statutory requirements for recording.

Review Officer \_\_\_\_\_ Date \_\_\_\_\_

**Final Plat**  
**Conservation Easement for**  
**the State of North Carolina,**  
**Ecosystem Enhancement Program,**  
**Little Alamance Creek at Burlington Park**  
**SPO#001-AAAG EEP#92372**

BURLINGTON TOWNSHIP ALAMANCE COUNTY NORTH CAROLINA

DATE: 05/01/2008 SCALE 1" = 100'

LANDMARK SURVEYING, INC. - 109 EAST HARDEN STREET - GRAHAM, NC 27253  
 PHONE: (336) 229-6275 - FACSIMILE: (336) 227-5919 - EMAIL: dylanmark@triad.rr.com  
 Job Number: 08-04-01 - Drawing Name: Y080401 NCEEP Little Alamance Creek  
 Field Crew: DWM & RMW - Drawn By: DRY - Checked By: \_\_\_\_\_

Revisions: 05/20/08 Revisions to Conservation Easement Boundaries, after 05/08/2008 walk-through with C.O.B. Representatives & NCEEP Staff.  
 06/20/08 Revisions to Conservation Easement Boundaries, after 06/05/2008 2nd walk-through with C.O.B. Representatives & NCEEP Staff.  
 07/15/08 Revisions to Conservation Easement Boundary Area "B" as per meeting with C.O.B. Representatives and NCEEP Staff.




Property Information:  
 Owner: City of Burlington  
 Alamance County Parcel ID# 8864790671  
 Alamance County Tax Map # 104-442-217

Deed References: Deed Book 98 Page 220  
 Deed Book 136 Page 46  
 Reference Boundary Survey Plat prepared by  
 City of Burlington Engineering Department  
 Entitled Final Plat Property of, City of Burlington  
 City Park Map #1, Dated September 14, 1995

Conservation Easement Notes:  
 Total Area in Conservation Easement: 6.98 Acres ±  
 0.25 Acres ± in Temporary Construction Easement


All corners of the Conservation Easement are marked  
 with Rebar and Aluminum NCEEP Caps, unless noted.

LEGEND  
 Existing Iron Pipe  
 New Iron Pipe  
 Man Hole  
 Monument  
 Power Pole  
 Utility Line



Line #	Bearing	Distance
Tie L-1	S 39°26'01" W	60.99'

GPS CO-ORDINATES  
 PROVIDED BY RCADIS  
 N 84926.62  
 E 1864965.29



Line #	Bearing	Distance
L-1	N 70°36'20" E	36.93'
L-2	N 69°20'21" E	46.63'
L-3	N 59°47'13" E	57.06'
L-4	S 43°59'51" E	41.68'
L-5	S 60°52'02" E	40.00'
L-6	S 66°12'35" W	56.03'
L-7	S 37°12'39" W	64.04'
L-8	S 67°18'44" E	43.27'
L-9	N 51°42'28" W	51.48'
L-10	N 49°25'20" W	63.45'
L-11	N 04°58'22" E	38.00'
L-12	N 29°35'00" E	54.44'
L-13	S 32°05'35" E	46.29'
L-14	N 00°16'40" E	42.66'
L-15	N 50°22'34" E	27.84'
L-16	N 69°21'29" E	58.74'
L-17	N 71°40'25" E	7.97'
L-18	N 66°26'32" E	8.90'
L-19	N 63°50'04" E	20.72'
L-20	N 71°13'11" E	27.32'
L-21	S 56°14'03" E	12.12'
L-22	N 88°59'18" E	41.52'
L-23	S 83°12'35" E	86.33'
L-24	N 81°39'06" E	66.07'
L-25	S 63°06'28" E	67.20'
L-26	S 00°33'50" W	42.52'
L-27	S 34°22'35" W	46.94'
L-28	S 82°55'27" W	40.80'
L-29	N 44°24'47" E	49.65'
L-30	S 84°59'13" W	62.40'
L-31	S 54°17'14" E	48.24'
L-32	N 81°18'07" W	50.71'
L-33	S 39°38'58" W	41.12'
L-34	N 04°26'24" W	28.11'

Curve #	Bearing	Chord	Radius	Arc
C-1	N 82°35'42" W	28.28'	100.00'	28.38'
C-2	N 69°24'31" W	17.63'	100.00'	17.65'
C-3	N 46°32'56" W	61.15'	100.00'	62.15'

**Certificate of Accuracy**

State of North Carolina, County of Alamance  
 I, Douglas R. Yarbrough, certify that under my direction and supervision this map was drawn from an actual field land survey made by me; that the error of closure as calculated by latitudes and departures is: 1:10,000 for the perimeter and 1:10,000 for plotting of interior lot lines; that the boundary not surveyed and not shown as broken lines plotted from deed information found in deed book L-3395, page 25; that this map was prepared in accordance with GS 47-30 as amended; that the survey was requested by the owner or his duly authorized agent; that all required monuments and markers have been installed; that all new lines calculated from data not obtained in the field are indicated by a "C"; and that this plat is within the jurisdiction of the City of Burlington.

Witness my hand and seal this 5th day of May, 2008.

*Douglas R. Yarbrough*  
 Douglas R. Yarbrough, Professional Land Surveyor, L-3395



**Certificate of Ownership and Dedication**

I, (we) hereby certify that I (we) am (are) the owner(s) of the property, shown and described hereon, which was conveyed to me (us) by deed as recorded in deed book 136, page 46, and that I (we) hereby acknowledge this plat and allotment to be my(our) free act and deed and do hereby dedicate to public use as streets, rights-of-way, and easements forever, all areas so shown or indicated on said plat.

OWNER: *Ronnie K. Wall* Date: 2-5-09

OWNER: \_\_\_\_\_ Date: \_\_\_\_\_

OWNER: \_\_\_\_\_ Date: \_\_\_\_\_

**Planning Director Certification**

NO APPROVAL REQUIRED UNDER SECTION 33-1 OF THE CODE OF ORDINANCES OF THE CITY OF BURLINGTON.

*[Signature]* 2-6-09  
 PLANNING DIRECTOR

**City of Burlington Certification**

Recommended by the Burlington Planning and Zoning Commission on the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Chairman of Planning and Zoning Commission

**Review Officer Certification**

State of North Carolina, County of Alamance

I, *J. David Shaffer*, Review Officer of Alamance County, certify that the map or plat to which this certification is affixed meets all statutory requirements for recording.

2/6/09

1. Douglas R. Yarbrough, Professional Land Surveyor, L-3395, Certify to one of the following:

A. This survey creates a subdivision of land within the area of a county or municipality that has an ordinance that regulates parcels of land.

B. This survey is located in such portion of a county or municipality that is recognized as an ordinance that regulates parcels of land.


C. Any one of the following:

1. That the survey is of an existing parcel or parcels of land and does not create a new street or change an existing street.
2. That the survey is of an existing building or other structure, or natural feature such as a watercourse; or
3. That the survey is a control survey.

D. This survey is of another category, such as the recombination of existing parcels in a court-ordered survey, or other exception to the definition of subdivision.

E. The information available to the surveyor is such that the surveyor is unable to make a determination to the best of his or her professional ability as to whether the plat is within the jurisdiction of the City of Burlington.

*Douglas R. Yarbrough*  
 Douglas R. Yarbrough, Professional Land Surveyor, L-3395



**Final Plat  
 Conservation Easement for  
 the State of North Carolina,  
 Ecosystem Enhancement Program,  
 Little Alamance Creek at Burlington Park  
 SPO#001-AAAG EEP#92372**

BURLINGTON TOWNSHIP ALAMANCE COUNTY NORTH CAROLINA

DATE: 05/01/2008 SCALE 1" = 100'

LANDMARK SURVEYING, INC. - 109 EAST HARDEN STREET - GRAHAM, NC 27253  
 PHONE: (336) 229-6275 - FACSIMILE: (336) 227-5919 - EMAIL: dylanmark@triad.rr.com  
 Job Number: 08-04-01 - Drawing Name: Y080401 NCEEP Little Alamance Creek  
 Field Crew: DWM & RMW - Drawn By: DRY - Checked By: \_\_\_\_\_

Revisions: 05/20/08 Revisions to Conservation Easement Boundaries, after 05/08/02008 walk-through with C.O.B. Representatives & NCEEP Staff.  
 06/20/08 Revisions to Conservation Easement Boundaries, after 06/05/02008 - 2nd walk-through with C.O.B. Representatives & NCEEP Staff.  
 07/15/08 Revisions to Conservation Easement Boundary Area "B" as per meeting with C.O.B. Representatives and NCEEP Staff.

138082

Figure 5: Conservation Easement Coordinate List

AREA "A"

NORTH	EAST	Point #
849579.51554	1864926.55171	395
849591.77729	1864961.38155	298
849608.22978	1865005.01204	299
849636.94197	1865054.31867	294
849589.39149	1865164.49481	129
849486.98274	1865107.29342	130
849513.45974	1865001.41137	131
849579.51554	1864926.55171	395

AREA "B"

NORTH	EAST	Point #
849559.40556	1865193.45108	134
849557.84265	1865237.72626	35
849479.25598	1865422.79011	136
849353.03468	1865393.66448	137
849291.86683	1865358.17065	105
849225.45240	1865275.15897	106
849221.25010	1865257.53874	140
849198.64891	1865206.27156	384
849147.64645	1865167.54338	107
849081.54893	1865093.68513	292
849087.74837	1865077.18420	293
849176.03999	1865035.54448	144
849199.39922	1865024.52791	385
849235.42971	1865096.89567	148
849299.41895	1865225.41897	149
849408.35898	1865232.57548	301
849467.50926	1865142.23314	151
849559.40556	1865193.45108	134

AREA "C"

NORTH	EAST	Point #
849462.56616	1865462.71229	152
849435.13638	1865526.69686	153
849482.39703	1865579.69130	155
849462.88378	1865657.23514	156
849442.70621	1865703.37024	157
849329.27516	1865707.26253	158
849260.03559	1865644.92151	159
849240.35724	1865576.32112	160
849321.13162	1865434.07191	396
849339.57571	1865437.80714	161
849462.56616	1865462.71229	152

AREA "D"

NORTH	EAST	Point #
849523.67028	1865531.49915	162
849606.54503	1865505.41990	300
849687.60418	1865479.86867	163
849646.26097	1865642.17633	164
849599.23801	1865668.60583	165
849480.56349	1865700.07636	166
849523.67028	1865531.49915	162



AREA "E"

NORTH	EAST	Point #
849734.94933	1865506.74625	386
849777.61339	1865506.95303	168
849795.36536	1865528.39325	169
849816.07420	1865583.36623	411
849813.56859	1865590.93079	172
849817.12503	1865599.08756	173
849826.26238	1865617.68539	174
849817.46632	1865643.55279	175
849810.73250	1865653.62464	176
849811.46562	1865695.14176	108
849801.25856	1865780.86612	410
849810.85135	1865846.23666	409
849780.45763	1865906.16581	180
849737.93964	1865905.74732	181
849699.19996	1865879.24506	182
849694.17460	1865838.75955	183
849689.79904	1865727.49867	312
849685.47681	1865617.58282	184
849734.94933	1865506.74625	386

AREA "F"

NORTH	EAST	Point #
849815.92160	1865940.90924	110
849824.39775	1865999.70351	109
849710.30838	1866007.56636	187
849704.65272	1865941.40823	388
849815.92160	1865940.90924	110

AREA "G"

NORTH	EAST	Point #
849811.20595	1866037.84131	189
849795.76690	1866075.73608	338
849767.10290	1866116.74370	191
849696.12266	1866262.27953	390
849631.25699	1866395.27823	391
849625.14242	1866407.81537	79 MH
849617.01962	1866417.32501	392
849561.30036	1866482.55746	393
849497.45831	1866557.29954	195
849490.28422	1866410.67696	196
849556.17669	1866325.00704	197
849591.11839	1866204.02424	404
849632.65737	1866156.80372	346
849702.64017	1866057.68956	199
849811.20595	1866037.84131	189

AREA "H"

NORTH	EAST	Point #
849465.79522	1866531.05945	200
849450.23363	1866542.12494	201
849390.76406	1866563.46603	202
849352.71701	1866583.54506	401
849315.71724	1866580.20684	203
849204.47066	1866564.90566	402
849156.80929	1866462.67261	403
849229.09022	1866442.93365	375
849332.80632	1866481.41733	399
849405.63461	1866455.34439	400
849462.25590	1866412.85336	210
849465.79522	1866531.05945	200

Table 5  
 Reach ID  
 Assessed Length

**Visual Stream Morphology Stability Assessment**  
 Mainstem  
 2275 lf

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjusted % for Stabilizing Woody Vegetation
1. Bed	1. Vertical Stability (Riffle and Run units)	1. <u>Aggradation</u> - Bar formation/growth sufficient to significantly deflect flow laterally (not to include point bars)			0	0	100%			
		2. <u>Degradation</u> - Evidence of downcutting			0	0	100%			
	2. Riffle Condition	1. <u>Texture/Substrate</u> - Riffle maintains coarser substrate	6	6			100%			
	3. Meander Pool Condition	1. <u>Depth</u> Sufficient (Max Pool Depth : Mean Bankfull Depth $\geq$ 1.6)	4	4			100%			
		2. <u>Length</u> appropriate (>30% of centerline distance between tail of upstream riffle and head of downstream riffle)	4	4			100%			
	4. Thalweg Position	1. Thalweg centering at upstream of meander bend (Run)	4	4			100%			
		2. Thalweg centering at downstream of meander (Glide)	4	4			100%			
	<b>Totals</b>					3	180			
2. Bank	1. Scoured/Eroding	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			3	180	96%	1	100	98%
	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does <b>NOT</b> include undercuts that are modest, appear sustainable and are providing habitat.			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
<b>Totals</b>					3	180	100%	1	100	100%
3. Engineered Structures	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	6	6			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill.	0	0			100%			
	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	6	6			100%			
	3. Bank Protection	Bank erosion within the structures extent of influence does <u>not</u> exceed 15%. (See guidance for this table in EEP monitoring guidance document)	0	0			100%			
	4. Habitat	Pool forming structures maintaining ~ Max Pool Depth : Mean Bankfull Depth ratio $\geq$ 1.6 Rootwads/logs providing some cover at base-flow.	4	4			100%			

Table 5  
 Reach ID  
 Assessed Length

**Visual Stream Morphology Stability Assessment**  
 Unnamed Tributary  
 450 lf

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjusted % for Stabilizing Woody Vegetation
1. Bed	1. Vertical Stability (Riffle and Run units)	1. <u>Aggradation</u> - Bar formation/growth sufficient to significantly deflect flow laterally (not to include point bars)			0	0	100%			
		2. <u>Degradation</u> - Evidence of downcutting			0	0	100%			
	2. Riffle Condition	1. <u>Texture/Substrate</u> - Riffle maintains coarser substrate	2	2			100%			
	3. Meander Pool Condition	1. <u>Depth</u> Sufficient (Max Pool Depth : Mean Bankfull Depth $\geq$ 1.6)	2	2			100%			
		2. <u>Length</u> appropriate (>30% of centerline distance between tail of upstream riffle and head of downstream riffle)	2	2			100%			
	4. Thalweg Position	1. Thalweg centering at upstream of meander bend (Run)	2	2			100%			
		2. Thalweg centering at downstream of meander (Glide)	2	2			100%			
<b>Totals</b>										
2. Bank	1. Scoured/Eroding	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			1	75	99%	0	0	99%
	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does <b>NOT</b> include undercuts that are modest, appear sustainable and are providing habitat.			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
<b>Totals</b>										
3. Engineered Structures	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	2			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill.	1	1			100%			
	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	2			100%			
	3. Bank Protection	Bank erosion within the structures extent of influence does <u>not</u> exceed 15%. (See guidance for this table in EEP monitoring guidance document)	1	1			100%			
	4. Habitat	Pool forming structures maintaining ~ Max Pool Depth : Mean Bankfull Depth ratio $\geq$ 1.6 Rootwads/logs providing some cover at base-flow.	2	2			100%			

**Table 6**

**Vegetation Condition Assessment**

**Planted Acreage<sup>1</sup>**

**7.06 ac**

Vegetation Category	Definitions	Mapping Threshold	CCPV Depiction	Number of Polygons	Combined Acreage	% of Planted Acreage	
<b>1. Bare Areas</b>	Very limited cover of both woody and herbaceous material.	0.1 acres	N/A	0	0.00	0.0%	
<b>2. Low Stem Density Areas</b>	Woody stem densities clearly below target levels based on MY3, 4, or 5 stem count criteria.	0.01 acres	Red veg plot polygons	6	0.06	0.8%	
				<b>Total</b>	6	0.06	0.8%
<b>3. Areas of Poor Growth Rates or Vigor</b>	Areas with woody stems of a size class that are obviously small given the monitoring year.	0.25 acres	N/A	0	0.00	0.0%	
				<b>Cumulative Total</b>	6	0.06	0.8%

**Easement Acreage<sup>2</sup>**

**7.06 ac**

Vegetation Category	Definitions	Mapping Threshold	CCPV Depiction	Number of Polygons	Combined Acreage	% of Easement Acreage
<b>4. Invasive Areas of Concern<sup>4</sup></b>	Areas or points (if too small to render as polygons at map scale).	1000 SF	Yellow Point	7 points	0.50	7.1%
<b>5. Easement Encroachment Areas<sup>3</sup></b>	Areas or points (if too small to render as polygons at map scale).	none	N/A	0	0.00	0.0%

<sup>1</sup> = Enter the planted acreage within the easement. This number is calculated as the easement acreage minus any existing mature tree stands that were not subject to supplemental planting of the understory, the channel acreage, crossings or any other elements not directly planted as part of the project effort.

<sup>2</sup> = The acreage within the easement boundaries.

<sup>3</sup> = Encroachment may occur within or outside of planted areas and will therefore be calculated against the overall easement acreage. In the event a polygon is cataloged into items 1, 2 or 3 in the table and is the result of encroachment, the associated acreage should be tallied in the relevant item (i.e., item 1,2 or 3) as well as a parallel tally in item 5.

<sup>4</sup> = Invasives may occur in or out of planted areas, but still within the easement and will therefore be calculated against the overall easement acreage. Invasives of concern/interest are listed below. The list of high concern species are those with the potential to directly outcompete native, young, woody stems in the short-term (e.g. monitoring period or shortly thereafter) or affect the community structure for existing, more established tree/shrub stands over timeframes that are slightly longer (e.g. 1-2 decades). The low/moderate concern group are those species that generally do not have this capacity over the timeframes discussed and therefore are not expected to be mapped with regularity, but can be mapped, if in the judgement of the observer their coverage, density or distribution is suppressing the viability, density, or growth of planted woody stems. Decisions as to whether remediation will be needed are based on the integration of risk factors by EEP such as species present, their coverage, distribution relative to native biomass, and the practicality of treatment. For example, even modest amounts of Kudzu or Japanese Knotweed early in the projects history will warrant control, but potentially large coverages of Microstegium in the herb layer will not likely trigger control because of the limited capacities to impact tree/shrub layers within the timeframes discussed and the potential impacts of treating extensive amounts of ground cover. Those species with the "watch list" designator in gray shade are of interest as well, but have yet to be observed across the state with any frequency. Those in *red italics* are of particular interest given their extreme risk/threat level for mapping as points where isolated specimens are found, particularly early in a projects monitoring history. However, areas of discrete, dense patches will of course be mapped as polygons. The symbology scheme below was one that was found to be helpful for symbolizing invasives polygons, particularly for situations where the condition for an area is somewhere between isolated specimens and dense, discrete patches. In any case, the point or polygon/area feature can be symbolized to describe things like high or low concern and species can be listed as a map inset, in legend items if the number of species are limited or in the narrative section of the executive summary.



Photo Log 1: Established Photo Stations



Photo Station 1, rail line at bollard 172, facing east; April 3, 2013



Photo Station 1, rail line at bollard 172, facing east; October 15, 2013



Photo Station 2, level spreader at bollard 410, facing east; April 3, 2013



Photo Station 2, level spreader at bollard 410, facing east; October 15, 2013



Photo Station 3, rail line discharge, facing south; April 3, 2013



Photo Station 3, rail line discharge, facing south; October 15, 2013





Photo Station 4, discharge at bollard 312, facing west; April 3, 2013



Photo Station 4, discharge at bollard 312, facing west; October 15, 2013



Photo Station 5, view of easement facing northwest; April 3, 2013



Photo Station 5, view of easement facing northwest; October 15, 2013



Photo Station 6, VP 7 at bollard 401, facing west; April 3, 2013



Photo Station 6, VP 7 at bollard 401, facing west; October 15, 2013





Photo Station 7, XS 1, facing right bank;  
March 27, 2013



Photo Station 7, XS 1, facing right bank;  
October 15, 2013



Photo Station 8, XS 2, facing right bank;  
March 27, 2013



Photo Station 8, XS 2, facing right bank;  
October 15, 2013



Photo Station 9, XS 3, facing right bank;  
March 27, 2013



Photo Station 9, XS 3, facing right bank;  
October 15, 2013





Photo Station 10, XS 4, facing right bank;  
April 3, 2013



Photo Station 10, XS 4, facing right bank;  
October 15, 2013



Photo Station 11, XS 5, facing right bank;  
March 27, 2013



Photo Station 11, XS 5, facing right bank;  
October 15, 2013



Photo Station 12, XS 6, facing right bank;  
April 3, 2013




Photo Station 12, XS 6, facing right bank;  
October 15, 2013





Photo Station 13, XS 7, facing right bank;  
April 3, 2013



Photo Station 13, XS 7, facing right bank;  
October 15, 2013



Photo Station 14, XS 8, facing right bank;  
April 3, 2013



Photo Station 14, XS 8, facing right bank;  
October 15, 2013



Photo Station 15, XS 9, facing right bank;  
April 3, 2013



Photo Station 15, XS 9, facing right bank;  
October 15, 2013





Photo Station 16, XS 10, facing right bank;  
April 3, 2013



Photo Station 16, XS 10, facing right bank;  
October 15, 2013



Photo Station 17, XS 11, facing right bank;  
April 3, 2013



Photo Station 17, XS 11, facing right bank;  
October 15, 2013



Photo Station 18, XS 12, facing right bank;  
April 3, 2013



Photo Station 18, XS 12, facing right bank;  
October 15, 2013





Photo Station 19, XS 13, facing right bank;  
April 3, 2013



Photo Station 19, XS 13, facing right bank;  
October 15, 2013



Photo Station 20, XS 14, facing right bank;  
April 3, 2013



Photo Station 20, XS 14, facing right bank;  
October 15, 2013



Photo Log 2: Vegetation Monitoring Plot Photos



Veg Plot 1, view from southwest corner;  
March 27, 2013



Veg Plot 1, view from southwest corner;  
October 15, 2013



Veg Plot 2, view from southwest corner;  
March 27, 2013



Veg Plot 2, view from southwest corner;  
October 15, 2013



Veg Plot 3, view from southwest corner;  
March 27, 2013



Veg Plot 3, view from southwest corner;  
October 15, 2013





Veg Plot 4, view from southwest corner;  
March 27, 2013



Veg Plot 4, view from southwest corner;  
October 15, 2013



Veg Plot 5, view from southwest corner;  
March 27, 2013



Veg Plot 5, view from southwest corner;  
October 15, 2013



Veg Plot 6, view from southwest corner;  
April 3, 2013



Veg Plot 6, view from southwest corner;  
October 15, 2013





Veg Plot 7, view from southwest corner;  
April 3, 2013



Veg Plot 7, view from southwest corner;  
October 15, 2013



Veg Plot 8, view from southwest corner;  
April 3, 2013



Veg Plot 8, view from southwest corner;  
October 15, 2013

## Appendix C: Vegetation Plot Data

Table 7: Vegetation Plot Success by Project Asset Type

Table 8: CVS Stem Count Total and Planted with/without Livestakes by  
Plot and Species

**Table 7: Little Alamance (#92372)**

**Year 2 (15-Oct-2013)**

Vegetation Plot Summary Information

Plot #	Riparian Buffer Stems <sup>1</sup>	Stream/Wetland Stems <sup>2</sup>	Live Stakes	Invasives	Volunteers <sup>3</sup>	Total <sup>4</sup>	Unknown Growth Form
1	n/a	8	0	1	6	13	0
2	n/a	5	0	0	12	17	0
3	n/a	5	0	1	50	54	0
4	n/a	7	0	0	6	13	0
5	n/a	2	0	0	5	7	0
6	n/a	11	0	0	8	19	0
7	n/a	2	1	0	3	6	0
8	n/a	3	0	0	0	3	0

**Wetland/Stream Vegetation Totals**

(per acre)

Plot #	Stream/Wetland Stems <sup>2</sup>	Volunteers <sup>3</sup>	Total <sup>4</sup>	Success Criteria Met?
1	324	243	526	Yes, barely
2	202	486	688	No
3	202	2023	2185	No
4	283	243	526	No
5	81	202	283	No
6	445	324	769	Yes
7	81	121	243	No
8	121	0	121	No
<b>Project Avg</b>	<b>218</b>	<b>455</b>	<b>668</b>	<b>No</b>

**Riparian Buffer Vegetation Totals**

(per acre)

Plot #	Riparian Buffer Stems <sup>1</sup>	Success Criteria Met?
1	n/a	
2	n/a	
3	n/a	
4	n/a	
5	n/a	
6	n/a	
7	n/a	
8	n/a	
<b>Project Avg</b>	<b>n/a</b>	

**Stem Class characteristics**

<sup>1</sup>Buffer

Stems Native planted hardwood trees. Does NOT include shrubs. No pines. No vines.

<sup>2</sup>Stream/Wetland

Stems Native planted woody stems. Includes shrubs, does NOT include live stakes. No vines

<sup>3</sup>Volunteers Native woody stems. Not planted. No vines.

<sup>4</sup>Total Planted + volunteer native woody stems. Includes live stakes. Excl. exotics. Excl. vines.

Table 8: EEP Project Code 92372. Project Name: Little Alamance

Scientific Name	Common Name	Species Type	Current Plot Data (MY2 2013)																		Annual Means														
			92372-01-0001			92372-01-0002			92372-01-0003			92372-01-0004			92372-01-0005			92372-01-0006			92372-01-0007			92372-01-0008			MY2 (2013)			MY1 (2013)					
			PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T			
Acer negundo	boxelder	Tree																												1					
Acer rubrum	red maple	Tree																												2					
Asimina triloba	pawpaw	Tree									3	3	3														5	5	5						
Baccharis halimifolia	eastern baccharis	Shrub																											1						
Betula nigra	river birch	Tree					2	2	2																					7					
Carpinus caroliniana	American hornbeam	Tree																												7					
Carya alba	mockernut hickory	Tree																												8					
Carya cordiformis	bitternut hickory	Tree																												8					
Carya glabra	pignut hickory	Tree																												8					
Carya illinoensis	pecan	Tree																												8					
Carya ovata	shagbark hickory	Tree																												8					
Castanea mollissima	Chinese chestnut	Exotic																												8					
Celtis laevigata	sugarberry	Tree																												8					
Cercis canadensis	eastern redbud	Tree																												8					
Cornus amomum	silky dogwood	Shrub																												8					
Cornus florida	flowering dogwood	Tree																												8					
Diospyros virginiana	common persimmon	Tree																												8					
DONTKNOW: unsure record																														8					
Euonymus americanus																														8					
Fraxinus americana	white ash	Tree																												8					
Fraxinus pennsylvanica	green ash	Tree																												8					
Hamamelis virginiana	American witchhazel	Tree																												8					
Ilex opaca	American holly	Tree																												8					
Ligustrum	privet	Exotic																												8					
Ligustrum lucidum	glossy privet	Exotic																												8					
Ligustrum sinense	Chinese privet	Exotic																												8					
Liquidambar styraciflua	sweetgum	Tree																												8					
Morus alba	white mulberry	Exotic																												8					
Morus rubra	red mulberry	Tree																												8					
Photinia	chokeberry																													8					
Platanus occidentalis	American sycamore	Tree																												8					
Prunus serotina	black cherry	Tree																												8					
Quercus	oak	Tree																												8					
Quercus coccinea	scarlet oak	Tree																												8					
Quercus nigra	water oak	Tree																												8					
Quercus pagoda	cherrybark oak	Tree																												8					
Quercus palustris	pin oak	Tree																												8					
Quercus velutina	black oak	Tree																												8					
Salix nigra	black willow	Tree																												8					
Sambucus canadensis	Common Elderberry	Shrub																												8					
Ulmus rubra	slippery elm	Tree																												8					
Viburnum dentatum	southern arrowwood	Shrub																												8					
Viburnum nudum	possumhaw	Shrub																												8					
Viburnum prunifolium	blackhaw	shrub																												8					
Stem count			8	8	14	5	5	17	5	5	55	7	7	13	2	2	7	11	11	19	2	3	6	3	3	3	3	3	3	43	44	134	69	70	160
size (ares)			1			1			1			1			1			1			1			1			8			8					
size (ACRES)			0.02			0.02			0.02			0.02			0.02			0.02			0.02			0.02			0.20			0.20					
Species count			6	6	9	4	4	8	3	3	7	5	5	8	1	1	4	6	6	11	2	2	4	2	2	2	14	14	27	15	16	31			
Stems per ACRE			323.7	323.7	566.6	202.3	202.3	688	202.3	202.3	2226	283.3	283.3	526.1	80.94	80.94	283.3	445.2	445.2	768.9	80.94	121.4	242.8	121.4	121.4	121.4	217.5	222.6	677.8	349	354.1	809.4			

## Appendix D: Stream Survey Data

Figure 6: Cross Sections with Annual Overlays

Figure 7: Longitudinal Profiles with Annual Overlays

Figure 8: Pebble Counts with Annual Overlays

Table 9: Stream Bank Erosion Pin Data Table


Table 10a: Baseline Stream Data Summary

Table 10b: Baseline Stream Data Summary (Substrate, Bed, Bank, and  
Hydrologic Containment Parameter Distributions)


Table 11a: Monitoring – Cross Section Morphology Data Table

Table 11b: Monitoring – Stream Reach Morphology Data Table

Little Alamance Creek (Burlington Park) Stream Restoration  
EEP No. 92372  
Reach 1, XS 1  
Riffle  
Station 11+58.48




Little Alamance Creek (Burlington Park) Stream Restoration  
EEP No. 92372  
Reach 1, XS 2  
Pool  
Station 13+23.79





Little Alamance Creek (Burlington Park) Stream Restoration  
 EEP No. 92372  
 Reach 1, XS 3  
 Pool  
 Station 13+62.29




# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 4, XS 4

Riffle

Station 19+69.54



# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 6, XS 5

Riffle

Station 27+95.78

○ XS 5 (2013)

◆ Bankfull Indicators


▼ Water Surface Points

△ XS 5 (2012)

Wbkf = 17.4

Dbkf = 2.2

Abkf = 38.3




# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 6, XS 6

Pool

Station 28+83.61




# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 6, XS 7


Pool

Station 29+17.31






Little Alamance Creek (Burlington Park) Stream Restoration  
EEP No. 92372  
Reach 6, XS 8  
Riffle  
Station 29+35.63



Little Alamance Creek (Burlington Park) Stream  
Restoration  
EEP No. 92372  
Reach 6, XS 9  
Riffle  
Station 29+57.75




# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 6, XS 10

Riffle

Station 30+56.75



# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 2, XS 11

Pool

Station 10+50.94

○ XS 11 (2013)

◆ Bankfull Indicators


▼ Water Surface Points

△ XS 11 (2012)

Wbkf = 20.4

Dbkf = 1.4

Abkf = 28.6



# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 2, XS 12

Riffle

Station 11+03.18

○ XS 12 (2013)

◆ Bankfull Indicators


▼ Water Surface Points

△ XS 12 (2012)

Wbkf = 10.3


Dbkf = .83

Abkf = 8.5





Little Alamance Creek (Burlington Park) Stream Restoration  
EEP No. 92372  
Reach 2, XS 13  
Pool  
Station 11+49.64



# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 2, XS 14

Riffle

Station 12+50.43

○ XS 14 (2013)

◆ Bankfull Indicators


▼ Water Surface Points

△ XS 14 (2012)


Wbkf = 10.3

Dbkf = 1.67

Abkf = 17.1



Little Alamance Creek (Burlington Park) Stream Restoration  
EEP No. 92372  
Main Stem  
Station 0+0.00 to 29+68.44




# Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Tributary

Station 10+0.00 to 14+40.85



# Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 1, XS 1      Riffle      Station 11+58.48

D50: 3.63 mm

D84: 25.73 mm

D95: 218 mm





Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 1, XS 1


Riffle

Station 11+58.48

D50: 3.63 mm

D84: 25.73 mm

D95: 218 mm



# Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 4, XS 4 Riffle Station 19+69.54

D50: 6.21 mm

D84: 19.96 mm

D95: 77.0 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 4, XS 4    Riffle    Station 19+69.54

D50: 6.21 mm

D84: 19.96 mm

D95: 77.0 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 5 Riffle Station 27+95.78

D50: 7.49 mm

D84: 31.41 mm

D95: 192.67 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 5 Riffle Station 27+95.78

D50: 7.49 mm

D84: 31.41 mm

D95: 192.67 mm





# Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 8 Riffle Station 29+35.63

D50: 3.73 mm

D84: 16.0 mm

D95: 40.67 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 8 Riffle Station 29+35.63

D50: 3.73 mm

D84: 16.0 mm

D95: 40.67 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 9 Riffle Station 29+57.75

D50: 4.73 mm

D84: 36.88 mm

D95: 64.0 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 9 Riffle Station 29+57.75

D50: 4.73 mm

D84: 36.88 mm

D95: 64.0 mm





Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 10 Riffle Station 30+56.75

D50: 5.36 mm

D84: 29.65 mm

D95: 90.0 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 6, XS 10 Riffle Station 30+56.75

D50: 5.36 mm

D84: 29.65 mm

D95: 90.0 mm



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 2, XS 12 Riffle Station 11+03.18

D50: 7.42 mm

D84: 52.6 mm

D95: Bedrock



Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 2, XS 12 Riffle Station 11+03.18

D50: 7.42 mm

D84: 52.6 mm

D95: Bedrock





Little Alamance Creek (Burlington Park) Stream Restoration


EEP No. 92372

Reach 2, XS 14 Riffle Station 12+50.43

D50: 4.0 mm

D84: 16.0 mm

D95: 45.0 mm



Little Alamance Creek (Burlington Park) Stream Restoration

EEP No. 92372

Reach 2, XS 14 Riffle Station 12+50.43

D50: 4.0 mm

D84: 16.0 mm

D95: 45.0 mm




Table 9: Stream Bank Erosion Pin Data Table

Per discussions with NCEEP, bank pins are not required and therefore were not installed by EEE Consulting.

Table 10a. Baseline Stream Data Summary  
 Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Mainstem (2275 lf)

Parameter	Gauge <sup>2</sup>	Regional Curve			Pre-Existing Condition						Reference Reach(es) Data						Design			Monitoring Baseline						
		LL	UL	Eq.	Min	Mean	Med	Max	SD <sup>5</sup>	n	Min	Mean	Med	Max	SD <sup>5</sup>	n	Min	Med	Max	Min	Mean	Med	Max	SD <sup>5</sup>	n	
<b>Dimension and Substrate - Riffle Only</b>																										
Bankfull Width (ft)					31.8	36.2		42.5				15.1						36.2		19.3	26.3		36.6			
Floodprone Width (ft)					70	94		120				30						>80		47.2	52.7		65.7			
Bankfull Mean Depth (ft)					2.2	2.6		2.9				1.6						2.6		2.09	2.53		3.08			
<sup>1</sup> Bankfull Max Depth (ft)					3.9	4		4.1				2.6						4		2.96	3.61		4.6			
Bankfull Cross Sectional Area (ft <sup>2</sup> )					79.3	95		125				24.3						95		40.83	68.78		112.77			
Width/Depth Ratio					11.6	14		17				9.3						13.8		7.85	10.31		12.26			
Entrenchment Ratio					2.1	2.6		3.8				2						>2.2		1.645	2.079		2.488			
<sup>1</sup> Bank Height Ratio					1	1.2		1.4				1						1		0.32	0.66		0.83			
<b>Profile</b>																										
Riffle Length (ft)																				62	159.33	137.16	353.24	119.9	5	
Riffle Slope (ft/ft)					0.003	0.013		0.025										0.003	0.013	0.025	0.0001	0.003326	0.00345	0.00983	0.0033	5
Pool Length (ft)					107.9	293.7		505.4										107.9	293.7	505.4	37.58	99.32	90.19	182.26	44.37	14
Pool Max depth (ft)					5.5	6.1		6.9										5.5	6.1	6.9	3.03	4.4	4.525	5.91	0.8265	10
Pool Spacing (ft)					313.7	473.1		749.5										313.7	473.1	749.5	48.85	147.39	92.07	347.97	115.45	9
<b>Pattern</b>																										
Channel Beltwidth (ft)					33	70		255										33	70	255	87.3	233		462		
Radius of Curvature (ft)					45	115		220										45	115	220	51.2	118.8		280.7		
Rc:Bankfull width (ft/ft)					1.2	3.2		6.1										1.2	3.2	6.1	2	4.5		10.7		
Meander Wavelength (ft)					227	361		559										227	361	559	436.2	454.6		475.2		
Meander Width Ratio					0.9	1.9		7										0.9	1.9	7	7.7	17.3		24.1		
<b>Transport parameters</b>																										
Reach Shear Stress (competency) lb/ft <sup>2</sup>								30										30						0.26		
Max part size (mm) mobilized at bankfull								80																	55.7	
Stream Power (transport capacity) W/m <sup>2</sup>																										
<b>Additional Reach Parameters</b>																										
Rosgen Classification								C/E/5/1										C/E4							E4	
Bankfull Velocity (fps)								2.5												2.5						
Bankfull Discharge (cfs)								237.5																		
Valley length (ft)																										
Channel Thalweg length (ft)																									2968.4	
Sinuosity (ft)								1.2												1.2					1.2	
Water Surface Slope (Channel) (ft/ft)								0.0024												0.0024					0.0024	
BF slope (ft/ft)																									0.00258	
<sup>3</sup> Bankfull Floodplain Area (acres)																										
<sup>4</sup> % of Reach with Eroding Banks																										
Channel Stability or Habitat Metric																										
Biological or Other																										

Shaded cells indicate that these will typically not be filled in.

1 = The distributions for these parameters can include information from both the cross-section surveys and the longitudinal profile. 2 = For projects with a proximal USGS gauge in-line with the project reach (added bankfull verification - rare).

3. Utilizing survey data produce an estimate of the bankfull floodplain area in acres, which should be the area from the top of bank to the toe of the terrace riser/slope.

4 = Proportion of reach exhibiting banks that are eroding based on the visual survey for comparison to monitoring data; 5. Of value/needed only if the n exceeds 3



Table 10a. Baseline Stream Data Summary  
 Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Unnamed Tributary (450 lf)

Parameter	Gauge <sup>2</sup>	Regional Curve			Pre-Existing Condition						Reference Reach(es) Data						Design			Monitoring Baseline					
		LL	UL	Eq.	Min	Mean	Med	Max	SD <sup>5</sup>	n	Min	Mean	Med	Max	SD <sup>5</sup>	n	Min	Med	Max	Min	Mean	Med	Max	SD <sup>5</sup>	n
<b>Dimension and Substrate - Riffle Only</b>																									
Bankfull Width (ft)					10.9	12		13					15.1				10.9	12	13	9.86	9.89		9.91		
Floodprone Width (ft)					27	33.5		40					30				27	33.5	40	8.5	12.5		16.5		
Bankfull Mean Depth (ft)					1.1	1.3		1.5					1.6				1.1	1.3	1.5	0.86	1.27		1.67		
<sup>1</sup> Bankfull Max Depth (ft)					2	2		2.1					2.6				2	2	2.1	1.43	2.17		2.91		
Bankfull Cross Sectional Area (ft <sup>2</sup> )					14.8	15.8		16.7					24.3				14.8	15.8	16.7	8.5	12.5		16.5		
Width/Depth Ratio					7.1	9.3		11.5					9.3				7.1	9.3	11.5	5.9	8.71		11.52		
Entrenchment Ratio					2.1	2.9		3.7					2				2.1	2.9	3.7	2.25	3.38		4.52		
<sup>1</sup> Bank Height Ratio					1	1.2		1.3					1					1		0.99	1.27		2.56		
<b>Profile</b>																									
Riffle Length (ft)																				26.98	41.87		59.91		
Riffle Slope (ft/ft)					0.015	0.025		0.05									0.015	0.025	0.05	0.006	0.01		0.018		
Pool Length (ft)					4	18.2		163									4	18.2	163	12.96	28.2		60.96		
Pool Max depth (ft)						2.4												2.4		0.74	2.06		3.26		
Pool Spacing (ft)					23.4	34.1		54.8									23.4	34.1	54.8	12.52	30.1		60.61		
<b>Pattern</b>																									
Channel Beltwidth (ft)					13.5	24.6		33.7									13.5	24.6	33.7	5.5	10.39		18.97		
Radius of Curvature (ft)					15	29		55									15	29	55	5.22	15.81		31.25		
Rc:Bankfull width (ft/ft)					1.2	2.4		4.6									1.2	2.4	4.6	1.547	1.784		2.02		
Meander Wavelength (ft)					55.8	83.9		111.9									55.8	83.9	111.9	135.7	172.4		209.2		
Meander Width Ratio					4.7	7		9.3									4.7	7	9.3	0.556	1.051		1.918		
<b>Transport parameters</b>																									
Reach Shear Stress (competency) lb/f <sup>2</sup>								0.71											0.71						
Max part size (mm) mobilized at bankfull								48																	
Stream Power (transport capacity) W/m <sup>2</sup>																									
<b>Additional Reach Parameters</b>																									
Rosgen Classification								E4/1					C/E4						C4/1				E4		
Bankfull Velocity (fps)								4.4											4.4						
Bankfull Discharge (cfs)								68.7																	
Valley length (ft)																									
Channel Thalweg length (ft)																									
Sinuosity (ft)								1.1											1.1						
Water Surface Slope (Channel) (ft/ft)								0.0095											0.0095						
BF slope (ft/ft)																									
<sup>3</sup> Bankfull Floodplain Area (acres)																									
<sup>4</sup> % of Reach with Eroding Banks																									
Channel Stability or Habitat Metric																									
Biological or Other																									

Shaded cells indicate that these will typically not be filled in.

1 = The distributions for these parameters can include information from both the cross-section surveys and the longitudinal profile. 2 = For projects with a proximal USGS gauge in-line with the project reach (added bankfull verification - rare).

3. Utilizing survey data produce an estimate of the bankfull floodplain area in acres, which should be the area from the top of bank to the toe of the terrace riser/slope.

4 = Proportion of reach exhibiting banks that are eroding based on the visual survey for comparison to monitoring data; 5. Of value/needed only if the n exceeds 3

**Table 10b. Baseline Stream Data Summary (Substrate, Bed, Bank, and Hydrologic Containment Parameter Distributions)  
Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Mainstem (2275 lf)**

Parameter	Pre-Existing Condition						Reference Reach(es) Data						Design						As-built/Baseline					
<sup>1</sup> Ri% / Ru% / P% / G% / S%																								
<sup>1</sup> SC% / Sa% / G% / C% / B% / Be%																								
<sup>1</sup> d16 / d35 / d50 / d84 / d95 / di <sup>p</sup> / di <sup>sp</sup> (mm)	0.2	0.7	2.4	138	216																			
<sup>2</sup> Entrenchment Class <1.5 / 1.5-1.99 / 2.0-4.9 / 5.0-9.9 / >10																								
<sup>3</sup> Incision Class <1.2 / 1.2-1.49 / 1.5-1.99 / >2.0																								

Shaded cells indicate that these will typically not be filled in.

1 = Riffle, Run, Pool, Glide, Step; Silt/Clay, Sand, Gravel, Cobble, Boulder, Bedrock; dip = max pave, disp = max subpave

2 = Entrenchment Class - Assign/bin the reach footage into the classes indicated and provide the percentage of the total reach footage in each class in the table. This will result from the measured cross-sections as well as visual estimates

3 = Assign/bin the reach footage into the classes indicated and provide the percentage of the total reach footage in each class in the table. This will result from the measured cross-sections as well as the longitudinal profile

**Footnotes 2,3** - These classes are loosely built around the Rosgen classification and hazard ranking breaks, but were adjusted slightly to make for easier assignment to somewhat coarser bins based on visual estimates in the field such that measurement of every segment for ER would not be necessary.

The intent here is to provide the reader/consumer of design and monitoring information with a good general sense of the extent of hydrologic containment in the pre-existing and the rehabilitated states as well as comparisons to the reference distributions.

ER and BHR have been addressed in prior submissions as a subsample (cross-sections as part of the design survey), however, these subsamples have often focused entirely on facilitating design without providing a thorough pre-construction distribution of these parameters, leaving the reader/consumer with a sample that is weighted heavily on the stable sections of the reach. This means that the distributions for these parameters should include data from both the cross-section surveys and the longitudinal profile and in the case of ER, visual estimates. For example, the typical longitudinal profile permits sampling of the BHR at riffles beyond those subject to cross-sections and therefore can be readily integrated and provide a more complete sample distribution for these parameters, thereby providing the distribution/coverage necessary to provide meaningful comparisons.

**Table 10b. Baseline Stream Data Summary (Substrate, Bed, Bank, and Hydrologic Containment Parameter Distributions)  
Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Unnamed Tributary (450 lf)**

Parameter	Pre-Existing Condition						Reference Reach(es) Data						Design						As-built/Baseline					
<sup>1</sup> Ri% / Ru% / P% / G% / S%																								
<sup>1</sup> SC% / Sa% / G% / C% / B% / Be%																								
<sup>1</sup> d16 / d35 / d50 / d84 / d95 / di <sup>p</sup> / di <sup>sp</sup> (mm)	0.2	0.5	3.4	19	53																			
<sup>2</sup> Entrenchment Class <1.5 / 1.5-1.99 / 2.0-4.9 / 5.0-9.9 / >10																								
<sup>3</sup> Incision Class <1.2 / 1.2-1.49 / 1.5-1.99 / >2.0																								

Shaded cells indicate that these will typically not be filled in.

1 = Riffle, Run, Pool, Glide, Step; Silt/Clay, Sand, Gravel, Cobble, Boulder, Bedrock; dip = max pave, disp = max subpave

2 = Entrenchment Class - Assign/bin the reach footage into the classes indicated and provide the percentage of the total reach footage in each class in the table. This will result from the measured cross-sections as well as visual estimates

3 = Assign/bin the reach footage into the classes indicated and provide the percentage of the total reach footage in each class in the table. This will result from the measured cross-sections as well as the longitudinal profile

**Footnotes 2,3** - These classes are loosely built around the Rosgen classification and hazard ranking breaks, but were adjusted slightly to make for easier assignment to somewhat coarser bins based on visual estimates in the field such that measurement of every segment for ER would not be necessary.

The intent here is to provide the reader/consumer of design and monitoring information with a good general sense of the extent of hydrologic containment in the pre-existing and the rehabilitated states as well as comparisons to the reference distributions.

ER and BHR have been addressed in prior submissions as a subsample (cross-sections as part of the design survey), however, these subsamples have often focused entirely on facilitating design without providing a thorough pre-construction distribution of these parameters, leaving the reader/consumer with a sample that is weighted heavily on the stable sections of the reach. This means that the distributions for these parameters should include data from both the cross-section surveys and the longitudinal profile and in the case of ER, visual estimates. For example, the typical longitudinal profile permits sampling of the BHR at riffles beyond those subject to cross-sections and therefore can be readily integrated and provide a more complete sample distribution for these parameters, thereby providing the distribution/coverage necessary to provide meaningful comparisons.

**Table 11a. Monitoring Data - Dimensional Morphology Summary (Dimensional Parameters – Cross Sections)  
Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Mainstem (2275 lf)**

	Cross Section 1 (Riffle)							Cross Section 2 (Pool)							Cross Section 3 (Pool)							Cross Section 4 (Riffle)							Cross Section 5 (Riffle)						
Based on fixed baseline bankfull elevation <sup>1</sup>	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+
Record elevation (datum) used	NAD 83 NC State Plane feet							NAD 83 NC State Plane feet							NAD 83 NC State Plane feet							NAD 83 NC State Plane feet							NAD 83 NC State Plane feet						
Bankfull Width (ft)	19.3	19.3	19.63					35.68	35.68	37.23					32.55	32.55	33.33					25.62	25.62	22.6					19.43	19.43	19.44				
Floodprone Width (ft)	48.01	48.01	45.1					73.15	73.2	73.27					65.21	65.21	65.18					47.46	47.46	43					47.21	47.21	44.04				
Bankfull Mean Depth (ft)	2.46	2.46	2.17					3.62	3.62	3.67					2.74	2.74	2.67					2.09	2.09	1.97					2.1	2.1	2.17				
Bankfull Max Depth (ft)	3.26	3.26	2.92					5.1	5.1	5.38					3.87	3.87	3.91					2.96	2.96	2.65					3.15	3.15	2.98				
Bankfull Cross Sectional Area (ft <sup>2</sup> )	47.41	47.41	42.63					129	129	136.8					89.22	89.22	88.97					53.43	53.43	44.54					40.83	40.83	42.26				
Bankfull Width/Depth Ratio	7.85	7.85	9.05					9.86	9.86	10.14					11.88	11.88	12.48					12.26	12.26	11.47					9.25	9.25	8.96				
Bankfull Entrenchment Ratio	2.49	2.49	2.3					2.05	2.05	1.97					2	2	1.96					1.85	1.85	1.9					2.43	2.43	2.27				
Bankfull Bank Height Ratio	1.06	1.06	1.01					1	1	0.99					1	1	0.98					1.75	1.75	1.01					0.95	0.95	0.97				
Cross Sectional Area between end pins (ft <sup>2</sup> )	176.8	176.8	172.2					257.2	257.2	267					159.1	159.1	158.4					219.1	219.1	207.7					141.3	141.3	138.7				
d50 (mm)	6.21	6.21	3.63					N/A	N/A	N/A					N/A	N/A	N/A					2.18	2.18	6.21					8.37	8.37	7.49				
	Cross Section 6 (Pool)							Cross Section 7 (Pool)							Cross Section 8 (Riffle)							Cross Section 9 (Riffle)							Cross Section 10 (Riffle)						
Based on fixed baseline bankfull elevation <sup>1</sup>	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+
Record elevation (datum) used	NAD 83 NC State Plane feet							NAD 83 NC State Plane feet							NAD 83 NC State Plane feet							NAD 83 NC State Plane feet							NAD 83 NC State Plane feet						
Bankfull Width (ft)	36.6	36.6	40.9					31.31	31.31	33.33					34.88	34.88	36.62					21.79	21.79	25.66					30.6	30.6	34.3				
Floodprone Width (ft)	60.21	60.21	60.42					56.8	56.8	58.36					65.72	65.72	65.79					47.34	47.34	52.87					48.37	48.37	48.37				
Bankfull Mean Depth (ft)	3.08	3.08	4.25					3.15	3.15	3.47					3.08	3.08	3.08					2.34	2.34	2.45					2.25	2.25	2.72				
Bankfull Max Depth (ft)	4.6	4.6	6.19					4.21	4.21	4.65					4.6	4.6	4.82					3.11	3.11	3.51					3.81	3.81	4.72				
Bankfull Cross Sectional Area (ft <sup>2</sup> )	112.8	112.8	174.1					98.77	98.77	115.8					107.3	107.3	112.6					50.91	50.91	62.79					68.86	68.86	93.13				
Bankfull Width/Depth Ratio	11.88	11.88	9.64					9.94	9.94	9.61					11.32	11.32	11.89					9.31	9.31	10.47					13.6	13.6	12.61				
Bankfull Entrenchment Ratio	1.65	1.65	1.48					1.81	1.81	1.75					1.88	1.88	1.8					2.17	2.17	2.06					1.58	1.58	1.41				
Bankfull Bank Height Ratio	1.38	1.38	1					1.06	1.06	0.99					1.02	1.02	1					1	1	1					1.28	1.28	1				
Cross Sectional Area between end pins (ft <sup>2</sup> )	295	295	292.9					210.6	210.6	197.4					271.4	271.4	248.8					245.3	245.3	229.9					162.4	162.4	166.5				
d50 (mm)	N/A	N/A	N/A					N/A	N/A	N/A					5.7	5.7	3.73					2.22	2.2	4.73					3.52	3.52	5.36				

1 = Widths and depths for monitoring resurvey will be based on the baseline bankfull datum regardless of dimensional/depositional development. Input the elevation used as the datum, which should be consistent and based on the baseline datum established. If the performer has inherited the project and cannot acquire the datum used for prior years this must be discussed with EEP. If this cannot be resolved in time for a given years report submission a footnote in this should be included that states: "It is uncertain if the monitoring datum has been consistent over the monitoring history, which may influence calculated values. Additional data from a prior performer is being acquired to provide confirmation. Values will be recalculated in a future submission based on a consistent datum if determined to be necessary."

**Table 11a. Monitoring Data - Dimensional Morphology Summary (Dimensional Parameters – Cross Sections)  
Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Unnamed Tributary (450 lf)**

	Cross Section 11 (Pool)							Cross Section 12 (Riffle)							Cross Section 13 (Pool)							Cross Section 14 (Riffle)						
Based on fixed baseline bankfull elevation <sup>1</sup>	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+	Base	MY1	MY2	MY3	MY4	MY5	MY+
Record elevation (datum) used	NAD 83 NC State Plane feet							NAD 83 State Plane feet							NAD 83 State Plane feet							NAD 83 State Plane feet						
Bankfull Width (ft)	15.57	15.57	19.85					9.91	9.91	10.26					9.86	9.86	10.49					10.08	10.08	9.16				
Floodprone Width (ft)	24.74	24.74	41.54					22.32	22.32	22.38					44.52	44.52	46.56					36.5	36.2	37.12				
Bankfull Mean Depth (ft)	0.69	0.69	1.38					0.86	0.86	0.83					1.67	1.67	1.61					1.52	1.52	1.64				
Bankfull Max Depth (ft)	1.7	1.7	2.78					1.43	1.43	1.54					2.91	2.91	3.03					2.46	2.46	2.71				
Bankfull Cross Sectional Area (ft <sup>2</sup> )	10.73	10.73	27.45					8.5	8.5	8.5					16.5	16.5	16.85					15.37	15.37	15				
Bankfull Width/Depth Ratio	22.57	22.57	14.38					11.52	11.52	12.36					5.9	5.9	6.52					6.63	6.63	5.59				
Bankfull Entrenchment Ratio	1.59	1.59	2.09					2.25	2.25	2.18					4.51	4.51	4.44					3.59	3.59	4.05				
Bankfull Bank Height Ratio	2.34	2.34	2.41					1	1	1					1	1	1					1.19	1.19	1.1				
Cross Sectional Area between end pins (ft <sup>2</sup> )	113.4	113.4	110.8					76.3	76.3	74.7					133.6	133.6	129.9					60.3	60.3	54.3				
d50 (mm)	N/A	N/A	N/A					5.21	5.21	7.42					N/A	N/A	N/A					3.3	3.3	4				

<sup>1</sup> = Widths and depths for monitoring resurvey will be based on the baseline bankfull datum regardless of dimensional/depositional development. Input the elevation used as the datum, which should be consistent and based on the baseline datum established. If the performer has inherited the project and cannot account for prior years this must be discussed with EEP. If this cannot be resolved in time for a given years report submission a footnote in this should be included that states: "It is uncertain if the monitoring datum has been consistent over the monitoring history, which may influence calculation. Additional data from a prior performer is being acquired to provide confirmation. Values will be recalculated in a future submission based on a consistent datum if determined to be necessary."



**Exhibit Table 11b. Monitoring Data - Stream Reach Data Summary**  
**Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Mainstem (2275 lf)**

Parameter	Baseline						MY-1						MY-2						MY-3						MY-4						MY-5					
	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n
<b>Dimension and Substrate - Riffle only</b>																																				
Bankfull Width (ft)	19.3	26.3	23.71	36.6	6.7	6	19.3	26.3	23.71	36.6	6.7	6	19.4	26.4	24.13	36.62	7.4	6																		
Floodprone Width (ft)	47.2	52.7	47.74	65.7	7.8	6	47.2	52.7	47.74	65.7	7.8	6	43	49.86	46.74	65.8	8.6	6																		
Bankfull Mean Depth (ft)	2.09	2.53	2.3	3.08	0.36	6	2.09	2.53	2.3	3.08	0.36	6	1.97	2.43	2.31	3.08	0.41	6																		
<sup>1</sup> Bankfull Max Depth (ft)	2.96	3.61	3.19	4.6	0.64	6	2.96	3.61	3.19	4.6	0.64	6	2.65	3.6	3.245	4.82	0.94	6																		
Bankfull Cross Sectional Area (ft <sup>2</sup> )	40.83	68.78	52.17	112.77	24.7	6	40.83	68.78	52.17	112.77	24.7	6	42.26	66.34	53.665	112.64	29.9	6																		
Width/Depth Ratio	7.85	10.31	10.32	12.26	2.4	6	7.85	10.31	10.32	12.26	2.4	6	8.96	10.74	10.97	12.61	1.5	6																		
Entrenchment Ratio	1.645	2.079	2.02	2.488	0.37	6	1.645	2.079	2.02	2.488	0.37	6	1.41	1.96	1.98	2.3	0.33	6																		
<sup>1</sup> Bank Height Ratio	0.9	1	1	1.01	0.006	6	0.99	1	1	1.01	0.006	6	0.98	0.995	0.992	1	0.006	6																		
<b>Profile</b>																																				
Riffle Length (ft)	62	159.33	137.16	353.24	119.9	5	62	159.33	137.16	353.24	119.9	5	26.55	52.64	42.12	101.02	29.9	5																		
Riffle Slope (ft/ft)	0.0001	0.003326	0.00345	0.00983	0.0033	5	0.0001	0.003326	0.00345	0.00983	0.0033	5	0.003890	0.0116	0.0133	0.0180	0.0070	5																		
Pool Length (ft)	37.58	99.32	90.19	182.26	44.37	14	37.58	99.32	90.19	182.26	44.37	14	24.23	124.2	132.17	217.92	55.56	14																		
Pool Max depth (ft)	3.03	4.4	4.525	5.91	0.8265	14	3.03	4.4	4.525	5.91	0.8265	14	1.3	2.45	2.63	3.21	0.963	14																		
Pool Spacing (ft)	48.85	147.39	92.07	347.97	115.45	9	48.85	147.39	92.07	347.97	115.45	9	31.69	86.5	69.97	214.55	58.43	9																		
<b>Pattern</b>																																				
Channel Beltwidth (ft)	87.3	233		462																																
Radius of Curvature (ft)	51.2	118.8		280.7																																
Rc:Bankfull width (ft/ft)	2	4.5		10.7																																
Meander Wavelength (ft)	436.2	454.6		475.2																																
Meander Width Ratio	7.7	17.3		24.1																																
<b>Additional Reach Parameters</b>																																				
Rosgen Classification		E4						E4						E4																						
Channel Thalweg length (ft)		2673						2673						2673																						
Sinuosity (ft)		1.6						1.6						1.6																						
Water Surface Slope (Channel) (ft/ft)		0.00242						0.00242						0.00248																						
BF slope (ft/ft)		0.00237						0.00237						0.00238																						
<sup>3</sup> Ri% / Ru% / P% / G% / S%																																				
<sup>3</sup> SC% / Sa% / G% / C% / B% / Be%																																				
<sup>3</sup> d16 / d35 / d50 / d84 / d95 /																																				
<sup>2</sup> % of Reach with Eroding Banks																																				
Channel Stability or Habitat Metric																																				
Biological or Other																																				

Pattern data will not typically be collected unless visual data, dimensional data or profile data indicate significant shifts from baseline

Shaded cells indicate that these will typically not be filled in.  
 1 = The distributions for these parameters can include information from both the cross-section surveys and the longitudinal profile.  
 2 = Proportion of reach exhibiting banks that are eroding based on the visual survey from visual assessment table  
 3 = Riffle, Run, Pool, Glide, Step; Silt/Clay, Sand, Gravel, Cobble, Boulder, Bedrock; dip = max pave, disp = max subpave  
 4. = Of value/needed only if the n exceeds 3

**Exhibit Table 11b. Monitoring Data - Stream Reach Data Summary**  
**Little Alamance Creek (Burlington Park) Stream Restoration/EEP Number (92372) Unnamed Tributary (450 lf)**

Parameter	Baseline						MY-1						MY-2						MY-3						MY-4						MY-5								
	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n	Min	Mean	Med	Max	SD <sup>4</sup>	n			
<b>Dimension and Substrate - Riffle only</b>																																							
Bankfull Width (ft)	9.86	9.89		9.91			9.86	9.89		9.91			9.16	9.71		10.26																							
Floodprone Width (ft)	8.5	12.5		16.5			8.5	12.5		16.5			22.38	29.75		37.12																							
Bankfull Mean Depth (ft)	0.86	1.27		1.67			0.86	1.27		1.67			0.83	1.24		1.64																							
<sup>1</sup> Bankfull Max Depth (ft)	1.43	2.17		2.91			1.43	2.17		2.91			1.54	2.13		2.17																							
Bankfull Cross Sectional Area (ft <sup>2</sup> )	8.5	12.5		16.5			8.5	12.5		16.5			5.3	9.18		12.36																							
Width/Depth Ratio	5.9	8.71		11.52			5.9	8.71		11.52			4.05	8.21		12.36																							
Entrenchment Ratio	2.25	3.38		4.52			2.25	3.38		4.52			1.1	1.64		2.18																							
<sup>1</sup> Bank Height Ratio	0.99	1.27		2.56			0.99	1.27		2.56			0.99	1.29		1.6																							
<b>Profile</b>																																							
Riffle Length (ft)	26.98	41.87		59.91			26.98	41.87		59.91			15.83	29.07		61.12																							
Riffle Slope (ft/ft)	0.006	0.0104		0.018			0.006	0.0104		0.018			0.003	0.022		0.046																							
Pool Length (ft)	12.96	28.2		60.96			12.96	28.2		60.96			8.2	16.84		23.12																							
Pool Max depth (ft)	0.74	2.06		3.26			0.74	2.06		3.26			0.63	1.33		2.22																							
Pool Spacing (ft)	12.52	30.1		60.61			12.52	30.1		60.61			12.03	14.78		14.88																							
<b>Pattern</b>																																							
Channel Beltwidth (ft)	5.5	10.39		18.97																																			
Radius of Curvature (ft)	5.22	15.81		31.25																																			
Rc:Bankfull width (ft/ft)	1.547	1.784		2.02																																			
Meander Wavelength (ft)	135.7	172.42		209.2																																			
Meander Width Ratio	0.556	1.051		1.918																																			
<b>Additional Reach Parameters</b>																																							
Rosgen Classification	E 4						E 4						E 4																										
Channel Thalweg length (ft)	426.02						426.02						426.02																										
Sinuosity (ft)	1.02						1.02						1.02																										
Water Surface Slope (Channel) (ft/ft)	0.00758						0.00758						0.00766																										
BF slope (ft/ft)	0.00728						0.00728						0.00754																										
<sup>3</sup> Ri% / Ru% / P% / G% / S%																																							
<sup>3</sup> SC% / Sa% / G% / C% / B% / Be%																																							
<sup>3</sup> d16 / d35 / d50 / d84 / d95 /																																							
<sup>2</sup> % of Reach with Eroding Banks																																							
Channel Stability or Habitat Metric																																							
Biological or Other																																							

Pattern data will not typically be collected unless visual data, dimensional data or profile data indicate significant shifts from baseline

Shaded cells indicate that these will typically not be filled in.  
 1 = The distributions for these parameters can include information from both the cross-section surveys and the longitudinal profile.  
 2 = Proportion of reach exhibiting banks that are eroding based on the visual survey from visual assessment table  
 3 = Riffle, Run, Pool, Glide, Step; Silt/Clay, Sand, Gravel, Cobble, Boulder, Bedrock; dip = max pave, disp = max subpave  
 4. = Of value/needed only if the n exceeds 3  
 Note: Calculations for the Unnamed Tributary are less than 3, which means that calculating media, SD, etc is not statistically correct

## Appendix E: Hydrologic Data

Table 12: Verification of Bankfull Events

Figure 9: Monthly Rainfall Data

Insert Table 12: Verification of Bankfull Events

Crest gauges were installed during Monitoring Year 1 field work. In July of monitoring year 2, there was a short period of several heavy rainfall events. As a result, Little Alamance Creek flooded and the crest gauge did not accurately record the flood event. Photographs of the event are shown below.

July 2013 Storm Event



View of Rail Road at PS1  
July 3, 2013



Bridge at XS 5  
July 3, 2013



View of water gauge on main tributary  
July 3, 2013



View of Bridge at XS 4  
July 3, 2013



View from XS 7  
July 3, 2013



View from PS 2, level spreader  
July 3, 2013



**LittleAlamance Creek 30-70 Percentile Graph**  
**Burlington, North Carolina**  
(Source: NOAA Station GHCND:USC00311239)

