

**Little Troublesome Site
Stream Restoration Monitoring Report
EEP Project # 749
Monitoring Year 02**



Submitted to:



NCDENR-EEP, 1652 Mail Service Center, Raleigh, NC 27699-1652

Construction Completed: December 2009

Data Collection: 2011

Submitted: December 2011

Design and Monitoring Firm



**Landmark Center II, Suite 220
4601 Six Forks Road
Raleigh, NC 27609
Phone: (919) 278-2514
Fax: (919) 783-9266**

**Project Manager: Adam Spiller
Email: adam.spiller@kci.com
Project No: 12071067C_LT11**

Table of Contents

| | | |
|------------|---|----------|
| 1.0 | EXECUIVE SUMMARY/PROJECT ABSTRACT..... | 1 |
| 2.0 | METHODOLOGY | 2 |
| 3.0 | REFERENCES..... | 2 |

Appendix A – Project Vicinity Map and Background Tables

| | | |
|-----------|--|---|
| Figure 1. | Vicinity Map..... | 4 |
| Figure 2. | Site Map..... | 5 |
| Table 1. | Project Components and Mitigation Credits..... | 6 |
| Table 2. | Project Activity and Reporting History | 7 |
| Table 3. | Project Contacts Table | 7 |
| Table 4. | Project Attribute Table..... | 8 |

Appendix B – Visual Assessment Data

| | |
|--|----|
| Current Condition Plan View..... | 10 |
| Table 5. Visual Stream Morphology Stability Assessment | 11 |
| Table 6. Vegetation Condition Assessment | 13 |
| Stream Station Photos | 14 |
| Vegetation Monitoring Plot Photos..... | 18 |

Appendix C – Vegetation Plot Data

| | |
|---|----|
| Table 7. Vegetation Plot Criteria Attainment | 21 |
| Table 8. CVS Vegetation Plot Metadata..... | 21 |
| Table 9. CVS Stem Count Total and Planted by Plot and Species | 22 |

Appendix D – Stream Survey Data

| | |
|--|----|
| Cross-Section Plots..... | 24 |
| Longitudinal Profile Plots | 31 |
| Pebble Count Plots..... | 33 |
| Table 10. Baseline Stream Data Summary Table | 40 |
| Table 11a. Cross-Section Morphology Data Table | 42 |
| Table 11b. Stream Reach Morphology Data Table..... | 44 |

Appendix E – Hydrologic Data

| | |
|---|----|
| Table 12. Verification of Bankfull Events | 45 |
|---|----|

1.0 EXECUTIVE SUMMARY / PROJECT ABSTRACT

The Little Troublesome Stream and Wetland Restoration Site, completed in December 2009, restored a total of 2,188 linear feet of stream in the Upper Cape Fear River Basin. In addition, there are approximately 4.5 acres of wetland preservation, 1.9 acres of wetland enhancement, and 2,754 linear feet of stream preservation within the site. The project is located in the USGS Hydrologic Unit 03030002-01-0030 of the Cape Fear River Basin. This HU is within the EEP's Upper Cape Fear Basin Local Watershed Plan and is also listed as a Targeted Local Watershed (TLW) in EEP's *Cape Fear River Basin Priorities Plan* (2009). The project goals and objectives are listed below.

Project Goals

- Restore a stable channel morphology to the project stream that is capable of moving the flows and sediment provided by its watershed.
- Improve water quality for an NCDWQ stream, classified as a Class C and Nutrient Sensitive Waters by reducing bank erosion and bed degradation.
- Enhance aquatic and terrestrial habitat.
- Enhance and preserve existing wetlands and forested buffers.

Project Objectives

- Restore 2,188 linear feet of stable stream channel with the appropriate pattern, profile, and dimension that can support a gravel transport system
- Restore a natural riparian buffer.
- Restore the hyporheic zone in the project streams and re-establish the natural stream features.
- Plug ditches to increase groundwater input to existing wetlands.
- Plant native trees and shrubs throughout the site.

The vegetation monitoring success criterion for the planted stream riparian zone is a density of 320 stems/acre after the third year of monitoring and an allowance for 10% mortality in the fourth and fifth years with a final density of 260 stems/acre. The second-year vegetation monitoring was based on the Level 2 CVS-EEP vegetation monitoring protocol. The site's average density for this monitoring period was 642 planted stems/acre, including live stakes, and 612 planted stems/acre, excluding live stakes. All of the eight plots had greater than 320 planted stems/acre. There are many volunteer woody stems throughout the site. Including volunteers, the monitoring plots averaged 3,065 total stems/acre. The 2011 monitoring found that the slope from the left bank of the tributary to the terrace (the north-facing slope) had sparse vegetation coverage with some bare areas. There has been high live stake survival along the tributary and variable survival along Little Troublesome Creek. Small sporadic areas of multiflora rose are present throughout the north side of Little Troublesome.

Second-year monitoring found Little Troublesome Creek to be stable, with only minor changes from the as-built and Year One conditions. The tributary has had areas of localized bed degradation and bank erosion since construction. These areas do not appear to be actively destabilizing and the plentiful streamside vegetation should continue to help stabilize these parts of the tributary. There are isolated areas of erosion on the south slope leading down to the tributary and on outer bends of Little Troublesome. These areas are not presently causing destabilization of the project, but should continue to be monitored. The longitudinal and cross-sectional data also reflect overall stability in the project streams. As a part of the stream success criterion, the stream must experience at least two bankfull events, each in separate monitoring years. The site has experienced multiple bankfull events since construction.

Summary information/data related to the occurrence of items such as beaver or encroachment and statistics related to performance of various project and monitoring elements can be found in the tables and

figures in the report appendices. Narrative background and supporting information formerly found in these reports can be found in the Baseline Monitoring Report (formerly Mitigation Plan) and in the Mitigation Plan (formerly the Restoration Plan) documents available on the EEPs website. All raw data supporting the tables and figures in the appendices are available from EEP upon request.

2.0 METHODOLOGY

The survey data were collected with a total station instrument the week of July 18, 2011.

The stationing for the longitudinal profile is based on the thalweg stationing and has been adjusted to match grade control structures from previous longitudinal profiles.

Some of the cross-section surveys on Little Troublesome Creek showed slightly lower top of bank measurements than the baseline measurements. In the cases where the top of bank measurement was only nominally lower than the bankfull elevation, the bankfull width was limited to just include the distance between the tops of left and right banks. This ensures that the bankfull width measurement is representative of the cross-section, and not abnormally large because of insignificant changes in the surveyed cross-section.

The CVS-EEP protocol, Level 2 (<http://cvs.bio.unc.edu/methods.htm>) was used to collect vegetation data from the site. The vegetation monitoring was completed during the week of August 22, 2011.

3.0 REFERENCES

Lee, M.T., R.K. Peet, S.D. Roberts, and T.R. Wentworth. 2006. CVS-EEP Protocol for Recording Vegetation, Version 4.0 (<http://cvs.bio.unc.edu/methods.htm>)

NCEEP. 2004. Troublesome and Little Troublesome Local Watershed Plan. (http://www.nceep.net/services/lwps/Troublesome_Creek/trouble-summ.pdf)

NCEEP. 2009. Cape Fear River Basin Restoration Priorities. (http://www.nceep.net/services/lwps/cape_fear/RBRP%20Cape%20Fear%202008.pdf)

USACE. 2003. Stream Mitigation Guidelines. USACE, NCDENR-DWQ, USEPA, NCWRC.

Appendix A

Project Vicinity Map and Background Tables












Figure 1. Vicinity Map


-  Project Site Location
-  Major Streams and Rivers
-  Major Roads
-  Other Roads
-  Local Watershed Plan Boundary

-  Cities and Towns
-  County Boundaries



1:63,360
1 inch = 1 miles






- Conservation Easement Boundary
- Stream Preservation
- Stream Restoration
- Other Streams
- - - Other Drainage Features
- - - Previous Stream Alignment
- - - FEMA 100 yr Floodplain Boundary
- Riparian Wetland Preservation
- Riparian Wetland Enhancement

Figure 2. Site Map
Little Troublesome Creek, Rockingham County, EEP Project 749



1:2,400
 1 inch = 200 feet
 200 100 0 200
 Feet



Source: NC Statewide Orthoimagery, 2010

12/19/2011

**Table 1. Project Components and Mitigation Credits
Little Troublesome / Project No. 749**

| Mitigation Credits | | | | | | | | | |
|---------------------------|----------------------|--------------------------|------------------|---------------------------------------|--------------------------------|------------------|--------|--------------------------|-----------------------------|
| | Stream | | Riparian Wetland | | Non-riparian Wetland | | Buffer | Nitrogen Nutrient Offset | Phosphorous Nutrient Offset |
| Type | R | RE | R | RE | R | RE | | | |
| Totals | 2188 | 551 | | 1.86 | | | | | |
| Project Components | | | | | | | | | |
| Project Component | Stationing/Location | Existing Footage/Acreage | Approach | Restoration or Restoration Equivalent | Restoration Footage or Acreage | Mitigation Ratio | | | |
| Little Troublesome Creek | 10+00 - 11+75 | 175 | P3 | R | 175 | 1:1 | | | |
| Little Troublesome Creek | 11+75 - 21+95 | 975 | P2 | R | 1020 | 1:1 | | | |
| Little Troublesome Creek | 21+95 - 23+75 | 179 | P3 | R | 180 | 1:1 | | | |
| UT1 | 50+00 - 58+13 | 813 | P3 | R | 813 | 1:1 | | | |
| UT2 | see Fig 2. | 2754 | - | RE | 2754 | 5:1 | | | |
| Enhancement Wetland #1 | see Fig 2. | 1.17 | - | RE | 1.17 | 2:1 | | | |
| Enhancement Wetland #2 | see Fig 2. | 0.74 | - | RE | 0.74 | 2:1 | | | |
| Preservation Wetland | see Fig 2. | 4.5 | - | RE | 4.5 | 5:1 | | | |
| Component Summation | | | | | | | | | |
| Restoration Level | Stream (linear feet) | Riparian Wetland (acres) | | Non-riparian Wetland (acres) | Buffer (square feet) | Upland (acres) | | | |
| | | Riverine | Non-Riverine | | | | | | |
| Restoration | 2188 | | | | | | | | |
| Enhancement | | 1.91 | | | | | | | |
| Enhancement I | | | | | | | | | |
| Enhancement II | | | | | | | | | |
| Creation | | | | | | | | | |
| Preservation | 2754 | 4.5 | | | | | | | |
| High Quality Preservation | | | | | | | | | |

| Table 2. Project Activity & Reporting History Little Troublesome / Project No. 749 | | |
|---|---------------------------------|--------------------------------------|
| Elapsed Time Since Grading and Planting Complete: 2 yr 0 months | | |
| Number of Reporting Years: 2 | | |
| Activity or Report | Data Collection Complete | Actual Completion or Delivery |
| Environmental Resource Technical Report | Sep 2006 | Sep 2006 |
| Restoration Plan | May 2007 | June 2007 |
| Final Design - Construction Plans | | Feb 2007 |
| Construction | | Dec 2009 |
| Temporary S&E mix applied | | Oct 2009 |
| Permanent seed mix applied | | Dec 2009 |
| Planting | | Dec 2009 |
| Baseline Monitoring | Feb 2010 | May 2010 |
| Year 1 Monitoring | Sep 2010 | Dec 2010 |
| Year 2 Monitoring | Jul 2011 | Dec 2011 |

| Table 3. Project Contacts Table Little Troublesome / Project No. 749 | |
|---|---|
| Designer | KCI Associates of North Carolina 4601 Six Forks Road, Suite 220 Raleigh, NC 27609 |
| Primary Project Design POC | April Helms (919) 783-9214 |
| Construction Contractor | Angler Environmental 12811 Randolph Ridge Lane Manassas, VA 20109 |
| Construction Contractor POC | Andrew Griffey (703) 393-4844 |
| Planting Contractor | HARP, Inc. 301 McCullough Drive, 4th Floor Charlotte, NC 28262 |
| Planting Contractor POC | Alan Peoples (704) 841-2841 |
| Seeding Contractor | Angler Environmental Manassas, VA 20109 |
| Seeding Contractor POC | Andrew Griffey (703) 393-4844 |
| Seed Mix Sources | MD Seed and Environmental Services Gaithersburg, MD 20879 |
| Monitoring Performers | KCI Associates of North Carolina 4601 Six Forks Road, Suite 220 Raleigh, NC 27609 |
| Monitoring POC | Adam Spiller (919) 278-2514 |










**Table 4. Project Attribute Table
Little Troublesome / Project No. 749**

| | | |
|--|--|------------|
| Project County | Rockingham County | |
| Physiographic Region | Piedmont | |
| Ecoregion | Northern Inner Piedmont | |
| River Basin | Cape Fear | |
| USGS HUC | 03030002010030 | |
| NCDWQ Sub-Basin | 03-06-01 | |
| Within Extent of EEP Watershed Plan | Yes - Upper Cape Fear Basin LWP | |
| WRC Class | Warm | |
| % of Project Easement Demarcated | 100% | |
| Beaver Activity Observed During Design Phase | No | |
| Restoration Component Attributes | | |
| | LTC | UT1 |
| Drainage Area (sq.mi.) | 12.09 | 0.1 |
| Stream Order | Third | First |
| Restored Length (feet) | 1,375 | 813 |
| Perennial or Intermittent | Perennial | Perennial |
| Watershed Type | Suburban | Suburban |
| Watershed LULC Distribution | | |
| Forest/Wetland | 49% | |
| Pasture/Managed Herbaceous | 21% | |
| Developed | 30% | |
| Watershed Impervious Cover | 21% | |
| NCDWQ AU/Index Number | 16-7 | |
| NCDWQ Classification | C; NSW | |
| 303d Listed | Yes | |
| Upstream of 303d Listed Segment | Yes | |
| Reasons for 303d Listing or Stressor | Aquatic life | |
| Total Acreage of Easement | 30.3 | |
| Total Vegetated Acreage within Easement | 30.0 | |
| Total Planted Acreage as Part of Restoration | 12.2 | |
| Rosgen Classification of Pre-Existing | E4 | G4c |
| Rosgen Classification of As-Built | E4/C4 | B4c |
| Valley Type | | |
| Valley Slope | 0.002 | 0.021 |
| Valley Side Slope Range | | |
| Valley Toe Slope Range | | |
| Cowardin Classification | | |
| Trout Waters Designation | No | |
| Species of Concern, Endangered, Etc. | Carolina ladle crayfish (<i>Cambarus davidi</i>) | |
| Dominant Soil Series and Characteristics | | |
| Series | Chewacla | |
| Depth | Deep | |
| Clay% | | |
| K | | |
| T | | |







Appendix B

Visual Assessment Data

LEGEND

- EASEMENT BOUNDARY..... 
- AS-BUILT STATIONED CENTERLINE AND TOP OF BANK..... 
- PHOTO POINT..... 
- CROSS-SECTION..... 
- OLD STREAM CHANNEL..... 
- RIFFLE GRADE CONTROL..... 
- LOG SILL..... 
- ROCK CROSS VANE..... 
- BED STABILIZATION..... 



PROJECT CONDITION

- STREAM BED DEGRADATION..... 
- BANK EROSION..... 
- UNDERCUT BANK..... 
- MASS WASTING OF BANK..... 
- VEG PLOT ACHIEVING DENSITY CRITERION..... 
- VEG PLOT BELOW DENSITY CRITERION..... 

PROJECT CONDITION DETAILS

VEG PLOT TOTAL / PLANTED STEM DENSITY..... 2306/607
 STRUCTURE NOT PROVIDING INTENDED POOL HABITAT..... H

IMAGE SOURCE: NC 2010 STATEWIDE ORTHOIMAGERY



| SYMBOL | DESCRIPTION | DATE | APPROVED |
|--------|-------------|------|----------|
| | | | |
| | | | |
| | | | |



KCI
 ASSOCIATES OF NC
 ENGINEERS • PLANNERS • SCIENTISTS
 4601 SIX FORKS ROAD
 RALEIGH, NORTH CAROLINA 27609

**LITTLE TROUBLESOME CREEK
 PROJECT #749 - MONITORING YEAR 02**
 ROCKINGHAM COUNTY, NORTH CAROLINA
 LITTLE TROUBLESOME CREEK AND UT1

DATE: NOV 2011
 SCALE: 1" = 100'
 CURRENT
 CONDITION
 PLAN VIEW
 SHEET 1 OF 1

Table 5. Visual Stream Morphology Stability Assessment

Project Number and Name: 749 - Little Troublesome

Assessed Length 1,375

Reach - Little Troublesome

| Major Channel Category | Channel Sub-Category | Metric | Number Stable, Performing as Intended | Total Number in As-built | Number of Unstable Segments | Amount of Unstable Footage | % Stable, Performing as Intended | Number with Stabilizing Woody Vegetation | Footage with Stabilizing Woody Vegetation | Adjusted % for Stabilizing Woody Vegetation | |
|---|--|---|--|--------------------------|-----------------------------|----------------------------|----------------------------------|--|---|---|------|
| 1. Bed | 1. Vertical Stability (Riffle and Run units) | 1. <u>Aggradation</u> - Bar formation/growth sufficient to significantly deflect flow laterally (not to include point bars) | | | 0 | 0 | 100% | | | | |
| | | 2. <u>Degradation</u> - Evidence of downcutting | | | 0 | 0 | 100% | | | | |
| | 2. Riffle Condition | 1. <u>Texture/Substrate</u> - Riffle maintains coarser substrate | 7 | 7 | | | | | | | 100% |
| | | 3. Meander Pool Condition | 1. <u>Depth</u> Sufficient (Max Pool Depth : Mean Bankfull Depth \geq 1.6) | 6 | | | | | | | 7 |
| | | | 2. <u>Length</u> appropriate (>30% of centerline distance between tail of upstream riffle and head of downstream riffle) | 7 | | | | | | | 7 |
| | 4. Thalweg Position | 1. Thalweg centering at upstream of meander bend (Run) | 7 | 7 | | | | | | | 100% |
| 2. Thalweg centering at downstream of meander (Glide) | | 7 | 7 | 100% | | | | | | | |
| Totals | | | | | | | | 2 | 40 | 99% | 0 |
| 2. Bank | 1. Scoured/Eroding | Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion | | | 0 | 0 | 100% | 0 | 0 | 100% | |
| | 2. Undercut | Banks undercut/overhanging to the extent that mass wasting appears likely. Does <u>NOT</u> include undercuts that are modest, appear sustainable and are providing habitat. | | | 0 | 0 | 100% | 0 | 0 | 100% | |
| | 3. Mass Wasting | Bank slumping, calving, or collapse | | | 2 | 40 | 99% | 0 | 0 | 99% | |
| 3. Engineered Structures | 1. Overall Integrity | Structures physically intact with no dislodged boulders or logs. | 3 | 3 | | | | 100% | | | |
| | 2. Grade Control | Grade control structures exhibiting maintenance of grade across the sill. | 3 | 3 | | | | 100% | | | |
| | 2a. Piping | Structures lacking any substantial flow underneath sills or arms. | 1 | 1 | | | | 100% | | | |
| | 3. Bank Protection | Bank erosion within the structures extent of influence does <u>not</u> exceed 15%. (See guidance for this table in EEP monitoring guidance document) | 1 | 1 | | | | 100% | | | |
| | 4. Habitat | Pool forming structures maintaining ~ Max Pool Depth : Mean Bankfull Depth ratio \geq 1.6 Rootwads/logs providing some cover at base-flow. | 0 | 1 | | | | 0% | | | |

| Table 5. Visual Stream Morphology Stability Assessment | | | | | | | | | | |
|--|--|---|---|--------------------------|-----------------------------|----------------------------|----------------------------------|--|---|---|
| Project Number and Name: 749 - Little Troublesome | | | | | | | | | | |
| Assessed Length 813 | | | | Reach - UTI | | | | | | |
| Major Channel Category | Channel Category | Sub-Metric | Number Stable, Performing as Intended | Total Number in As-built | Number of Unstable Segments | Amount of Unstable Footage | % Stable, Performing as Intended | Number with Stabilizing Woody Vegetation | Footage with Stabilizing Woody Vegetation | Adjusted % for Stabilizing Woody Vegetation |
| 1. Bed | 1. Vertical Stability (Riffle and Run units) | 1. <u>Aggradation</u> - Bar formation/growth sufficient to significantly deflect flow laterally (not to include point bars) | | | 0 | 0 | 100% | | | |
| | | 2. <u>Degradation</u> - Evidence of downcutting | | | 3 | 37 | 95% | | | |
| | 2. Riffle Condition | 1. <u>Texture/Substrate</u> - Riffle maintains coarser substrate | 11 | 13 | | | 85% | | | |
| | | 3. Meander Pool Condition | 1. <u>Depth</u> Sufficient (Max Pool Depth : Mean Bankfull Depth ≥ 1.6) | 14 | 16 | | 88% | | | |
| | | 2. <u>Length</u> appropriate (>30% of centerline distance between tail of upstream riffle and head of downstream riffle) | 7 | 14 | | | 50% | | | |
| | 4. Thalweg Position ⁺ | 1. Thalweg centering at upstream of meander bend (Run) | | | | | N/A | | | |
| 2. Thalweg centering at downstream of meander (Glide) | | | | | | N/A | | | | |
| Totals | | | | | | | | | | |
| 2. Bank | 1. Scoured/Eroding | Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion | | | 8 | 80 | 95% | 1 | 12 | 96% |
| | 2. Undercut | Banks undercut/overhanging to the extent that mass wasting appears likely. Does <u>NOT</u> include undercuts that are modest, appear sustainable and are providing habitat. | | | 1 | 10 | 99% | 0 | 0 | 99% |
| | 3. Mass Wasting | Bank slumping, calving, or collapse | | | 0 | 0 | 100% | 0 | 0 | 100% |
| Totals | | | | | | | | | | |
| 3. Engineered Structures | 1. Overall Integrity | Structures physically intact with no dislodged boulders or logs. | 2 | 2 | | | 100% | | | |
| | 2. Grade Control | Grade control structures exhibiting maintenance of grade across the sill. | 2 | 2 | | | 100% | | | |
| | 2a. Piping | Structures lacking any substantial flow underneath sills or arms. | 2 | 2 | | | 100% | | | |
| | 3. Bank Protection | Bank erosion within the structures extent of influence does <u>not</u> exceed 15%. (See guidance for this table in EEP monitoring guidance document) | 0 | 0 | | | N/A | | | |
| | 4. Habitat | Pool forming structures maintaining ~ Max Pool Depth : Mean Bankfull Depth ratio ≥ 1.6 Rootwads/logs providing some cover at base-flow. | 0 | 0 | | | N/A | | | |

⁺Due to this reach's small size and the scale of the pattern, the exact position of the thalweg in relation to the meanders and morphological features is inconsistent and not practical to evaluate .

| Table 6. Vegetation Condition Assessment | | | | | | |
|--|---|--------------------------|--------------------------------|---------------------------|-------------------------|-----------------------------|
| Project Number and Name: 749 - Little Troublesome | | | | | | |
| Planted Acreage 12.2 | | | Easement Acreage 30.3 | | | |
| Vegetation Category | Definitions | Mapping Threshold | CCPV Depiction | Number of Polygons | Combined Acreage | % of Planted Acreage |
| 1. Bare Areas | Very limited cover of both woody and herbaceous material. | 0.1 acre | Pattern and Color* | 0 | 0.00 | 0.0% |
| 2. Low Stem Density Areas | Woody stem densities clearly below target levels based on MY3, 4, or 5 stem count criteria. | 0.1 acre | Pattern and Color ⁺ | 2 | 0.30 | 2.5% |
| Total | | | | 2 | 0.30 | 2.5% |
| 3. Areas of Poor Growth Rates or Vigor | Areas with woody stems of a size class that are obviously small given the monitoring year. | 0.25 acre | Pattern and Color | 0 | 0.00 | 0.0% |
| Cumulative Total | | | | 2 | 0.30 | 2.5% |
| 4. Invasive Areas of Concern | Areas or points (if too small to render as polygons at map scale). | 1,000 SF | Pattern and Color | 0 | 0.00 | 0.0% |
| 5. Easement Encroachment Areas | Areas or points (if too small to render as polygons at map scale). | none | Pattern and Color | 0 | 0.00 | 0.0% |

*These areas were not depicted on the CCPV. Generally, the left slope of UT1 has many small scattered bare areas that are below the mapping threshold, but are significant when combined.

⁺These areas were not depicted on the CCPV. Generally, the left and right slopes of UT1 have many scattered areas of noticeable low stem densities that are below the mapping threshold, but are significant when combined.

Stream Station Photos



Photo Point 1u: View looking upstream near Station 11+10. 2/23/10 – Baseline



Photo Point 1u: View looking upstream near Station 11+10. 11/18/2011 – MY-02



Photo Point 1d: View looking downstream near Station 11+10. 2/23/10 – Baseline



Photo Point 1d: View looking downstream near Station 11+10. 11/18/2011 – MY-02



Photo Point 2u: View looking upstream taken near Station 17+40. 2/23/10 – Baseline



Photo Point 2u: View looking upstream taken near Station 17+40. 11/18/2011 – MY-02



Photo Point 2d: View looking downstream taken near Station 17+40. 2/23/10 – Baseline



Photo Point 2d: View looking downstream taken near Station 17+40. 11/18/2011 – MY-02



Photo Point 3u: View looking upstream near Station 22+25. 2/23/10 – Baseline



Photo Point 3u: View looking upstream near Station 22+25. 11/18/2011 – MY-02



Photo Point 3d: View looking downstream near Station 22+25. 2/23/10 – Baseline




Photo Point 3d: View looking downstream near Station 22+25. 11/18/2011 – MY-02



Photo Point 4: View looking upstream near Station 24+00. 2/23/10 – Baseline



Photo Point 4: View looking upstream near Station 24+00. 11/18/2011 – MY-02



Photo Point 5: View looking downstream near Station 50+00. 2/23/10 – Baseline



Photo Point 5: View looking downstream near Station 50+00. 11/18/2011 – MY-02



Photo Point 6u: View looking upstream near Station 54+90. 2/23/10 – Baseline



Photo Point 6u: View looking upstream near Station 54+90. 11/18/2011 – MY-02



Photo Point 6d: View looking downstream near Station 54+90. 2/23/10 – Baseline



Photo Point 6d: View looking downstream near Station 54+90. 11/18/2011 – MY-02



Photo Point 7: View looking upstream at the tributary confluence. 2/23/10 – Baseline



Photo Point 7: View looking upstream at the tributary confluence. 11/18/2011 – MY-02

Vegetation Monitoring Plot Photos



Plot 1 Photo: 8/22/11 – MY02



Plot 2 Photo: 8/22/11 – MY02



Plot 3 Photo: 8/22/11 – MY02



Plot 4 Photo: 8/22/11 – MY02



Plot 5 Photo: 8/22/11 – MY02



Plot 6 Photo: 8/22/11 – MY02



Plot 7 Photo: 8/22/11 – MY02



Plot 8 Photo: 8/22/11 – MY02

Appendix C

Vegetation Plot Data

| Table 7. Vegetation Plot Criteria Attainment | |
|---|---|
| Little Troublesome / Project No. 749 | |
| Vegetation Plot ID | Vegetation Survival Threshold Met? |
| 1 | Yes |
| 2 | Yes |
| 3 | Yes |
| 4 | Yes |
| 5 | Yes |
| 6 | Yes |
| 7 | Yes |
| 8 | Yes |

| Table 8. CVS Vegetation Plot Metadata | |
|--|---|
| Little Troublesome / Project No. 749 | |
| Report Prepared By | April Helms |
| Date Prepared | 12/5/2011 9:47 |
| database name | KCI-2011-LT.mdb |
| database location | M:\2007\12071067_2007 EEP OPEN END\Veg_database |
| computer name | 12-CV76KF1 |
| file size | 55836672 |
| DESCRIPTION OF WORKSHEETS IN THIS DOCUMENT----- | |
| Metadata | Description of database file, the report worksheets, and a summary of project(s) and project data. |
| Proj, planted | Each project is listed with its PLANTED stems per acre, for each year. This excludes live stakes. |
| Proj, total stems | Each project is listed with its TOTAL stems per acre, for each year. This includes live stakes, all planted stems, and all natural/volunteer stems. |
| Plots | List of plots surveyed with location and summary data (live stems, dead stems, missing, etc.). |
| Vigor | Frequency distribution of vigor classes for stems for all plots. |
| Vigor by Spp | Frequency distribution of vigor classes listed by species. |
| Damage | List of most frequent damage classes with number of occurrences and percent of total stems impacted by each. |
| Damage by Spp | Damage values tallied by type for each species. |
| Damage by Plot | Damage values tallied by type for each plot. |
| Planted Stems by Plot and Spp | A matrix of the count of PLANTED living stems of each species for each plot; dead and missing stems are excluded. |
| ALL Stems by Plot and spp | A matrix of the count of total living stems of each species (planted and natural volunteers combined) for each plot; dead and missing stems are excluded. |
| PROJECT SUMMARY----- | |
| Project Code | 749 |
| project Name | Little Troublesome Creek |
| Description | Stream and Wetland Restoration Site |
| River Basin | Cape Fear |
| length(ft) | 2200 |
| stream-to-edge width (ft) | 60 |
| area (sq m) | 24523.92 |
| Required Plots (calculated) | 8 |
| Sampled Plots | 8 |

Table 9. CVS Stem Count Total and Planted by Plot and Species

| Scientific Name | Common Name | Species Type | Annual Means | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------------------|--------------------|--------------|--------------|-------|------|-------------|-------|------|-------------|-------|------|-------------|-------|------|-------------|-------|------|-------------|-------|------|-------------|-------|-----|-------------|-------|------|------------|-------|------|------------|-------|------|------------|-------|-----|---|--|--|
| | | | E749-A-0001 | | | E749-A-0002 | | | E749-A-0003 | | | E749-A-0004 | | | E749-A-0005 | | | E749-A-0006 | | | E749-A-0007 | | | E749-A-0008 | | | MY2 (2011) | | | MY1 (2010) | | | MY0 (2010) | | | | | |
| | | | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | P-noLS | P-all | T | | | |
| <i>Acer negundo</i> | boxelder | Tree | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 13 | | | | | | |
| <i>Acer rubrum</i> | red maple | Tree | | | | | 7 | | | 1 | | | 1 | | | 3 | | | 1 | | | | | | | | | | | | 13 | | 33 | | | | | |
| <i>Aronia arbutifolia</i> | Red Chokeberry | Shrub | | | | | | | | | 1 | 1 | 1 | | | | | | | 1 | 1 | 1 | | | | 2 | 2 | 2 | | 2 | 2 | 2 | | | | | | |
| <i>Betula nigra</i> | river birch | Tree | 3 | 3 | 3 | 1 | 1 | 1 | | | | 1 | 1 | 20 | 8 | 8 | 13 | 3 | 3 | 3 | 4 | 4 | 4 | 7 | 7 | 11 | 27 | 27 | 55 | 31 | 31 | 60 | 35 | 35 | 35 | | | |
| <i>Celtis laevigata</i> | sugarberry | Shrub Tree | | | | | 1 | | 2 | 2 | 2 | | | 2 | 3 | 3 | 3 | | | | | 1 | | | | | 5 | 5 | 9 | | 5 | 5 | 17 | | | | | |
| <i>Cornus amomum</i> | silky dogwood | Shrub | | | | | | | | | | 1 | 1 | | | | | | | | | | | | | | 1 | 1 | | | 1 | 1 | | 1 | 3 | 3 | | |
| <i>Diospyros virginiana</i> | common persimmon | Tree | | | 11 | | | | | | | | | | | | 1 | 1 | 32 | 2 | 2 | 2 | | | 7 | 3 | 3 | 52 | | 2 | 2 | 36 | | | | | | |
| <i>Fraxinus pennsylvanica</i> | green ash | Tree | | | 7 | | | 15 | | | | | 110 | | | 80 | | | | | | | | | 1 | | | 247 | | | 190 | | | | | | | |
| <i>Ilex sp.</i> | holly | Shrub Tree | | | | | | | | | | | | | | | | | | | | 1 | 1 | 1 | 1 | 1 | 1 | | 1 | 1 | 1 | | | | | | | |
| <i>Juglans nigra</i> | black walnut | Tree | | | | | | | | | | | | 1 | | | | | | | | | | | | | | 1 | | | 1 | | | | | | | |
| <i>Liquidambar styraciflua</i> | sweetgum | Tree | | | 1 | | | 7 | | | | | | 2 | | | | | | | 12 | | | | 1 | | | 23 | | | 16 | | | | | | | |
| <i>Liriodendron tulipifera</i> | tuliptree | Tree | | | | | | 1 | | | | | | 1 | | | | | | | | | | | | | 2 | | | 1 | | | | | | | | |
| <i>Pinus taeda</i> | loblolly pine | Tree | | | | | | | | | | | | | | | | | 1 | | | | | | | | | 1 | | | 1 | | | | | | | |
| <i>Platanus occidentalis</i> | American sycamore | Tree | 1 | 1 | 1 | 1 | 1 | 6 | 6 | 6 | 8 | 3 | 3 | 11 | 2 | 2 | 2 | 4 | 4 | 4 | 10 | 10 | 10 | 1 | 1 | 2 | 28 | 28 | 44 | 28 | 28 | 51 | 29 | 29 | 29 | | | |
| <i>Quercus sp.</i> | oak | Shrub Tree | 1 | 1 | 1 | | | | | | | | | | | | | | | 1 | 1 | 1 | | | | 2 | 2 | 2 | 2 | 2 | 2 | 22 | 22 | 22 | | | | |
| <i>Quercus michauxii</i> | swamp chestnut oak | Tree | 3 | 3 | 3 | 3 | 3 | 3 | 4 | 4 | 4 | 8 | 8 | 9 | 2 | 2 | 2 | 4 | 4 | 4 | 4 | 4 | 4 | 2 | 2 | 2 | 30 | 30 | 31 | 32 | 32 | 32 | | | | | | |
| <i>Quercus palustris</i> | pin oak | Tree | | | | | | | 3 | 3 | 3 | 3 | 3 | 3 | | | | | | | | | 3 | 3 | 3 | 9 | 9 | 9 | 9 | 9 | 9 | | | | | | | |
| <i>Quercus phellos</i> | willow oak | Tree | | | | 3 | 3 | 5 | 2 | 2 | 3 | 1 | 1 | 1 | 1 | 1 | 1 | 2 | 2 | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 11 | 11 | 14 | 12 | 12 | 12 | 4 | 4 | 4 | | | |
| <i>Rhus sp.</i> | sumac | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | |
| <i>Salix sp.</i> | willow | Shrub Tree | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 6 | 6 | | | | |
| <i>Salix sericea</i> | silky willow | Shrub Tree | | | | | | | | | | 5 | 5 | | | | | | | | | | | | | | | 5 | 5 | | 5 | 5 | | | | | | |
| <i>Sambucus canadensis</i> | Common Elderberry | Shrub Tree | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 | 1 | | | |
| <i>Ulmus sp.</i> | elm | Tree | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 101 | | | | | | |
| <i>Ulmus americana</i> | American elm | Tree | | | 5 | | | 6 | | | 58 | | 4 | | | 16 | | | | | | | | 2 | | | 91 | | | | | | | | | | | |
| Unknown | | unknown | | | | | | | 1 | 1 | 1 | | | | | | | | | | | | 1 | 1 | 1 | 2 | 2 | 2 | 6 | 6 | 6 | 59 | 59 | 59 | | | | |
| <i>Viburnum nudum</i> | possumhaw | Shrub Tree | | | | | | | | | | | | | 1 | 1 | 1 | | | | | | | | | | 1 | 1 | 1 | 1 | 1 | 1 | | | | | | |
| Stem count | | | 8 | 8 | 32 | 8 | 8 | 52 | 18 | 18 | 190 | 17 | 23 | 142 | 17 | 17 | 75 | 14 | 14 | 59 | 22 | 22 | 23 | 17 | 17 | 33 | 121 | 127 | 606 | 131 | 137 | 592 | 150 | 159 | 159 | | | |
| size (ares) | | | 1 | | | 1 | | | 1 | | | 1 | | | 1 | | | 1 | | | 1 | | | 1 | | | 8 | | | 8 | | | 8 | | | | | |
| size (ACRES) | | | 0.02 | | | 0.02 | | | 0.02 | | | 0.02 | | | 0.02 | | | 0.02 | | | 0.02 | | | 0.02 | | | 0.20 | | | 0.20 | | | 0.20 | | | | | |
| Species count | | | 4 | 4 | 8 | 4 | 4 | 10 | 6 | 6 | 9 | 6 | 8 | 15 | 6 | 6 | 9 | 5 | 5 | 8 | 6 | 6 | 7 | 8 | 8 | 12 | 12 | 14 | 21 | 12 | 14 | 23 | 6 | 8 | 8 | | | |
| Stems per ACRE | | | 324 | 324 | 1295 | 324 | 324 | 2104 | 728 | 728 | 7689 | 688 | 931 | 5747 | 688 | 688 | 3035 | 567 | 567 | 2388 | 890 | 890 | 931 | 688 | 688 | 1335 | 612 | 642 | 3065 | 663 | 693 | 2995 | 759 | 804 | 804 | | | |

Appendix D

Stream Survey Data

| | |
|-------------------------------|------------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | LTC (XS - 1, Riffle) Station 13+08 |
| Drainage Area (sq mi): | 12.09 |
| Date: | 7/18/2011 |
| Field Crew: | A. French, J. Anders |




| Station | Elevation |
|---------|-----------|
| 0.0 | 655.84 |
| 0.7 | 655.36 |
| 2.2 | 655.21 |
| 5.2 | 655.04 |
| 8.7 | 654.53 |
| 12.7 | 654.59 |
| 16.6 | 654.56 |
| 20.4 | 654.73 |
| 23.8 | 654.61 |
| 24.9 | 653.80 |
| 25.9 | 652.97 |
| 26.9 | 652.28 |
| 27.9 | 651.66 |
| 28.5 | 651.37 |
| 29.6 | 651.04 |
| 30.6 | 650.42 |
| 30.9 | 650.36 |
| 32.9 | 650.24 |
| 34.2 | 650.01 |
| 36.4 | 650.01 |
| 38.4 | 649.83 |
| 40.0 | 649.70 |
| 41.9 | 649.68 |
| 43.8 | 649.88 |
| 45.6 | 649.95 |
| 47.0 | 650.08 |
| 48.2 | 650.13 |
| 49.7 | 650.46 |
| 50.6 | 651.07 |
| 51.8 | 651.74 |
| 53.5 | 652.37 |
| 54.6 | 653.27 |
| 55.4 | 653.88 |
| 56.3 | 654.53 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 654.6 |
| Bankfull Cross-Sectional Area: | 117.4 |
| Bankfull Width: | 33.2 |
| Flood Prone Area Elevation: | 659.4 |
| Flood Prone Width: | >200 |
| Max Depth at Bankfull: | 4.9 |
| Mean Depth at Bankfull: | 3.5 |
| W / D Ratio: | 9.4 |
| Entrenchment Ratio: | >6.0 |
| Bank Height Ratio: | 1.0 |

Stream Type E4/C4

Cape Fear River Basin, Little Troublesome Creek, MY-02, LTC (XS - 1, Riffle) Station 13+08



*Other shots not included due to space


| | |
|-------------------------------|----------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | LTC (XS - 2, Pool) Station 13+90 |
| Drainage Area (sq mi): | 12.09 |
| Date: | 7/18/2011 |
| Field Crew: | A. French, J. Anders |



Stream Type E4/C4

| Station | Elevation |
|---------|-----------|
| 0.0 | 654.88 |
| 0.9 | 654.50 |
| 4.6 | 654.36 |
| 10.0 | 654.55 |
| 14.2 | 654.51 |
| 17.8 | 654.53 |
| 21.1 | 654.33 |
| 23.6 | 654.01 |
| 24.6 | 653.69 |
| 26.0 | 653.25 |
| 27.5 | 652.72 |
| 29.8 | 652.15 |
| 31.5 | 651.95 |
| 33.2 | 651.61 |
| 34.3 | 651.18 |
| 36.2 | 650.71 |
| 37.7 | 649.80 |
| 39.7 | 649.54 |
| 41.0 | 649.41 |
| 43.7 | 648.88 |
| 45.9 | 648.53 |
| 48.4 | 648.27 |
| 49.7 | 647.66 |
| 51.2 | 646.66 |
| 53.7 | 648.94 |
| 54.1 | 649.72 |
| 54.8 | 651.26 |
| 55.9 | 651.89 |
| 57.1 | 653.15 |
| 58.3 | 654.13 |
| 59.0 | 654.49 |
| 62.0 | 654.71 |
| 67.1 | 654.63 |
| 71.9 | 654.63 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 654.3 |
| Bankfull Cross-Sectional Area: | 135.0 |
| Bankfull Width: | 37.5 |
| Flood Prone Area Elevation: | - |
| Flood Prone Width: | - |
| Max Depth at Bankfull: | 7.7 |
| Mean Depth at Bankfull: | 3.6 |
| W / D Ratio: | - |
| Entrenchment Ratio: | - |
| Bank Height Ratio: | - |



*Other shots not included due to space


| | |
|-------------------------------|------------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | LTC (XS - 3, Riffle) Station 16+30 |
| Drainage Area (sq mi): | 12.09 |
| Date: | 7/18/2011 |
| Field Crew: | A. French, J. Anders |



| Station | Elevation |
|---------|-----------|
| 0.0 | 655.87 |
| 1.3 | 655.38 |
| 5.6 | 655.22 |
| 8.7 | 654.96 |
| 9.5 | 654.87 |
| 11.6 | 653.95 |
| 13.3 | 653.90 |
| 17.6 | 653.99 |
| 20.9 | 654.00 |
| 24.0 | 653.78 |
| 28.5 | 653.81 |
| 32.1 | 653.99 |
| 32.8 | 653.65 |
| 34.2 | 652.62 |
| 35.6 | 651.80 |
| 37.0 | 650.91 |
| 38.5 | 650.36 |
| 39.3 | 649.59 |
| 41.1 | 649.48 |
| 42.2 | 649.44 |
| 43.3 | 649.28 |
| 45.4 | 649.31 |
| 46.6 | 649.11 |
| 47.9 | 648.98 |
| 49.3 | 649.03 |
| 50.6 | 648.99 |
| 52.1 | 649.07 |
| 54.0 | 649.16 |
| 55.3 | 649.37 |
| 56.1 | 649.58 |
| 56.9 | 649.90 |
| 58.0 | 650.05 |
| 59.1 | 650.81 |
| 60.5 | 651.45 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 653.9 |
| Bankfull Cross-Sectional Area: | 114.8 |
| Bankfull Width: | 32.2 |
| Flood Prone Area Elevation: | 658.9 |
| Flood Prone Width: | >200 |
| Max Depth at Bankfull: | 4.9 |
| Mean Depth at Bankfull: | 3.6 |
| W / D Ratio: | 9.0 |
| Entrenchment Ratio: | >6.0 |
| Bank Height Ratio: | 1.0 |

Stream Type E4/C4



*Other shots not included due to space


| | |
|-------------------------------|------------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | LTC (XS - 4, Riffle) Station 19+42 |
| Drainage Area (sq mi): | 12.09 |
| Date: | 7/19/2011 |
| Field Crew: | A. French, J. Anders |



| Station | Elevation |
|---------|-----------|
| 0.0 | 655.17 |
| 0.7 | 654.74 |
| 3.3 | 654.61 |
| 6.4 | 654.59 |
| 9.3 | 654.38 |
| 11.6 | 654.50 |
| 14.0 | 654.26 |
| 14.5 | 654.06 |
| 15.7 | 653.58 |
| 17.8 | 653.24 |
| 20.6 | 653.08 |
| 25.1 | 653.09 |
| 29.1 | 653.25 |
| 31.4 | 653.54 |
| 32.7 | 653.48 |
| 33.6 | 652.96 |
| 35.8 | 651.68 |
| 36.7 | 651.46 |
| 37.1 | 651.28 |
| 38.1 | 650.79 |
| 39.3 | 650.05 |
| 40.4 | 649.03 |
| 41.1 | 648.96 |
| 43.9 | 648.64 |
| 45.4 | 648.64 |
| 47.1 | 648.48 |
| 49.0 | 648.40 |
| 51.1 | 648.30 |
| 53.3 | 648.27 |
| 54.5 | 648.42 |
| 55.8 | 648.52 |
| 56.6 | 648.61 |
| 58.1 | 649.29 |
| 59.7 | 650.08 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 653.3 |
| Bankfull Cross-Sectional Area: | 115.9 |
| Bankfull Width: | 33.1 |
| Flood Prone Area Elevation: | 658.3 |
| Flood Prone Width: | >200 |
| Max Depth at Bankfull: | 5.0 |
| Mean Depth at Bankfull: | 3.5 |
| W / D Ratio: | 9.5 |
| Entrenchment Ratio: | >6.0 |
| Bank Height Ratio: | 1.0 |

Stream Type E4/C4



*Other shots not included due to space


| | |
|-------------------------------|------------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | UT1 (XS - 5, Riffle) Station 51+56 |
| Drainage Area (sq mi): | 0.10 |
| Date: | 7/19/2011 |
| Field Crew: | A. French, J. Anders |



| Station | Elevation |
|---------|-----------|
| 0.0 | 666.69 |
| 0.6 | 666.28 |
| 3.1 | 666.33 |
| 5.7 | 666.33 |
| 6.8 | 666.24 |
| 8.2 | 665.61 |
| 9.3 | 664.97 |
| 11.4 | 664.08 |
| 13.7 | 663.08 |
| 15.5 | 662.29 |
| 17.8 | 661.36 |
| 19.1 | 660.67 |
| 20.8 | 660.03 |
| 22.3 | 659.60 |
| 23.2 | 659.54 |
| 24.1 | 659.55 |
| 25.1 | 659.73 |
| 26.5 | 659.95 |
| 29.0 | 660.20 |
| 30.5 | 660.86 |
| 32.1 | 661.78 |
| 34.4 | 662.88 |
| 37.0 | 664.16 |
| 40.5 | 665.78 |
| 42.8 | 666.87 |
| 46.2 | 668.02 |
| 50.0 | 668.36 |
| 52.4 | 668.45 |
| 53.0 | 668.81 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 660.1 |
| Bankfull Cross-Sectional Area: | 2.0 |
| Bankfull Width: | 6.9 |
| Flood Prone Area Elevation: | 660.6 |
| Flood Prone Width: | 10.5 |
| Max Depth at Bankfull: | 0.5 |
| Mean Depth at Bankfull: | 0.3 |
| W / D Ratio: | 23.8 |
| Entrenchment Ratio: | 1.5 |
| Bank Height Ratio: | 1.0 |

| | |
|--------------------|-----|
| Stream Type | B4c |
|--------------------|-----|



| | |
|-------------------------------|----------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | UT1 (XS - 6, Pool) Station 55+08 |
| Drainage Area (sq mi): | 0.10 |
| Date: | 7/19/2011 |
| Field Crew: | A. French, J. Anders |




| Station | Elevation |
|---------|-----------|
| 0.0 | 660.64 |
| 0.7 | 660.28 |
| 2.6 | 660.46 |
| 4.2 | 660.29 |
| 6.1 | 659.71 |
| 8.2 | 658.98 |
| 10.7 | 658.07 |
| 13.7 | 657.16 |
| 16.0 | 656.20 |
| 18.5 | 655.21 |
| 20.6 | 654.45 |
| 21.8 | 654.04 |
| 23.0 | 653.73 |
| 23.6 | 653.44 |
| 24.0 | 652.65 |
| 24.5 | 652.11 |
| 24.8 | 652.06 |
| 25.4 | 652.00 |
| 25.7 | 652.21 |
| 26.6 | 652.20 |
| 27.0 | 653.15 |
| 27.5 | 653.50 |
| 28.6 | 653.84 |
| 29.3 | 654.06 |
| 30.6 | 654.59 |
| 32.5 | 655.28 |
| 34.1 | 656.08 |
| 37.4 | 657.63 |
| 39.7 | 658.40 |
| 41.5 | 659.20 |
| 42.8 | 659.55 |
| 46.1 | 659.91 |
| 49.6 | 659.88 |
| 50.1 | 660.14 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 653.6 |
| Bankfull Cross-Sectional Area: | 4.5 |
| Bankfull Width: | 4.5 |
| Flood Prone Area Elevation: | - |
| Flood Prone Width: | - |
| Max Depth at Bankfull: | 1.6 |
| Mean Depth at Bankfull: | 1.0 |
| W / D Ratio: | - |
| Entrenchment Ratio: | - |
| Bank Height Ratio: | - |

| | |
|--------------------|-----|
| Stream Type | B4c |
|--------------------|-----|

Cape Fear River Basin, Little Troublesome Creek, MY-02, UT1 (XS - 6, Pool) Station 55+08




| | |
|-------------------------------|------------------------------------|
| River Basin: | Cape Fear |
| Watershed: | Little Troublesome Creek, MY-02 |
| XS ID | UT1 (XS - 7, Riffle) Station 56+84 |
| Drainage Area (sq mi): | 0.10 |
| Date: | 7/19/2011 |
| Field Crew: | A. French, J. Anders |




| Station | Elevation |
|---------|-----------|
| 0.0 | 657.65 |
| 0.3 | 657.22 |
| 3.3 | 657.13 |
| 5.9 | 657.00 |
| 7.7 | 656.58 |
| 10.3 | 656.12 |
| 12.9 | 654.91 |
| 15.7 | 653.83 |
| 17.8 | 652.73 |
| 19.9 | 651.88 |
| 21.2 | 651.37 |
| 21.9 | 651.24 |
| 23.6 | 650.73 |
| 25.0 | 650.56 |
| 25.3 | 650.24 |
| 25.9 | 650.20 |
| 26.3 | 650.16 |
| 27.3 | 650.16 |
| 28.1 | 650.26 |
| 28.9 | 650.40 |
| 29.5 | 650.73 |
| 31.1 | 651.25 |
| 32.7 | 651.67 |
| 33.9 | 652.28 |
| 36.0 | 653.01 |
| 38.9 | 654.11 |
| 40.8 | 655.08 |
| 42.6 | 655.70 |
| 46.4 | 655.80 |
| 49.2 | 655.94 |
| 51.4 | 655.88 |
| 51.7 | 656.29 |

| SUMMARY DATA | |
|---------------------------------------|-------|
| Bankfull Elevation: | 650.9 |
| Bankfull Cross-Sectional Area: | 3.2 |
| Bankfull Width: | 6.9 |
| Flood Prone Area Elevation: | 651.6 |
| Flood Prone Width: | 12.0 |
| Max Depth at Bankfull: | 0.7 |
| Mean Depth at Bankfull: | 0.5 |
| W / D Ratio: | 14.9 |
| Entrenchment Ratio: | 1.7 |
| Bank Height Ratio: | 1.0 |

| | |
|--------------------|-----|
| Stream Type | B4c |
|--------------------|-----|




**Longitudinal Profile
Little Troublesome Creek
EEP Project Number - 749
Station 10+00 - 24+50**





- | | | | | | | | | |
|---------------------|------------------|------------------|---------------------|------------|-------------|-----------------|------------------|-------------|
| — Baseline, 2/12/10 | — MY-01, 9/16/10 | — MY-02, 7/19/11 | - - - Water Surface | ■ Bankfull | ◇ Structure | ◇ Cross-Section | - - - - WS Slope | — BKF Slope |
|---------------------|------------------|------------------|---------------------|------------|-------------|-----------------|------------------|-------------|

Longitudinal Profile
UT1 to Little Troublesome Creek
EEP Project Number - 749
Station 50+00 - 58+50





- | | | | | | | | | |
|---------------------|------------------|--------------------|---------------------|------------|-------------|-----------------|------------------|-------------|
| — Baseline, 2/12/10 | — MY-01, 9/17/10 | —■— MY-02, 7/20/11 | - - - Water Surface | ■ Bankfull | ◇ Structure | ◇ Cross-Section | - - - - WS Slope | — BKF Slope |
|---------------------|------------------|--------------------|---------------------|------------|-------------|-----------------|------------------|-------------|



| Cross-Section 1 Riffle - LTC MY-02 | | | | | | |
|------------------------------------|-------------|--------------|-------|--------|-------|-----|
| Particle | Millimeter | Material | Count | Item % | Cum % | |
| Silt/Clay | < 0.062 | S/C | | 0% | 0% | |
| Very Fine | .062 - .125 | S | | 0% | 0% | |
| Fine | .125 - .25 | A | | 0% | 0% | |
| Medium | .25 - .50 | N | | 0% | 0% | |
| Coarse | .50 - 1 | D | 5 | 5% | 5% | |
| Very Coarse | 1 - 2 | S | 3 | 3% | 8% | |
| Very Fine | 2 - 4 | G | 6 | 6% | 14% | |
| Fine | 4 - 5.7 | | | 0% | 14% | |
| Fine | 5.7 - 8 | | R | 1 | 1% | 15% |
| Medium | 8 - 11.3 | | A | 6 | 6% | 21% |
| Medium | 11.3 - 16 | | V | 9 | 9% | 30% |
| Coarse | 16 - 22.6 | | E | 12 | 12% | 42% |
| Coarse | 22.6 - 32 | | L | 17 | 17% | 59% |
| Very Coarse | 32 - 45 | | S | 7 | 7% | 66% |
| Very Coarse | 45 - 64 | | | 7 | 7% | 73% |
| Small | 64 - 90 | | C | 9 | 9% | 82% |
| Small | 90 - 128 | O | 12 | 12% | 94% | |
| Large | 128 - 180 | B | 5 | 5% | 99% | |
| Large | 180 - 256 | L | 1 | 1% | 100% | |
| Small | 256 - 362 | B | | 0% | 100% | |
| Small | 362 - 512 | L | | 0% | 100% | |
| Medium | 512 - 1024 | D | | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | | 0% | 100% | |
| Bedrock | >2048 | BDRK | | 0% | 100% | |
| | | Total | 100 | 100% | 100% | |
| Summary Data | | | | | | |
| D50 | 26 | | | | | |
| D84 | 95 | | | | | |
| D95 | 140 | | | | | |





| Cross-Section 2 Pool - LTC MY-02 | | | | | | |
|----------------------------------|-------------|--------------|-------|--------|-------|------|
| Particle | Millimeter | Material | Count | Item % | Cum % | |
| Silt/Clay | < 0.062 | S/C | | 0% | 0% | |
| Very Fine | .062 - .125 | S | | 0% | 0% | |
| Fine | .125 - .25 | A | | 0% | 0% | |
| Medium | .25 - .50 | N | 11 | 11% | 11% | |
| Coarse | .50 - 1 | D | 43 | 43% | 54% | |
| Very Coarse | 1 - 2 | S | 27 | 27% | 81% | |
| Very Fine | 2 - 4 | G | 12 | 12% | 93% | |
| Fine | 4 - 5.7 | | | 0% | 93% | |
| Fine | 5.7 - 8 | | | 0% | 93% | |
| Medium | 8 - 11.3 | | A | 1 | 1% | 94% |
| Medium | 11.3 - 16 | | V | 3 | 3% | 97% |
| Coarse | 16 - 22.6 | | E | 3 | 3% | 100% |
| Coarse | 22.6 - 32 | | L | | 0% | 100% |
| Very Coarse | 32 - 45 | | S | | 0% | 100% |
| Very Coarse | 45 - 64 | | | | 0% | 100% |
| Small | 64 - 90 | | C | | 0% | 100% |
| Small | 90 - 128 | O | | 0% | 100% | |
| Large | 128 - 180 | B | | 0% | 100% | |
| Large | 180 - 256 | L | | 0% | 100% | |
| Small | 256 - 362 | B | | 0% | 100% | |
| Small | 362 - 512 | L | | 0% | 100% | |
| Medium | 512 - 1024 | D | | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | | 0% | 100% | |
| Bedrock | >2048 | BDRK | | 0% | 100% | |
| | | Total | 100 | 100% | 100% | |
| Summary Data | | | | | | |
| D50 | 0.94 | | | | | |
| D84 | 2.4 | | | | | |
| D95 | 12 | | | | | |





| Cross-Section 3 Riffle - LTC MY-02 | | | | | | |
|------------------------------------|-------------|--------------|-------|--------|-------|-----|
| Particle | Millimeter | Material | Count | Item % | Cum % | |
| Silt/Clay | < 0.062 | S/C | | 0% | 0% | |
| Very Fine | .062 - .125 | S | | 0% | 0% | |
| Fine | .125 - .25 | A | | 0% | 0% | |
| Medium | .25 - .50 | N | 1 | 1% | 1% | |
| Coarse | .50 - 1 | D | 2 | 2% | 3% | |
| Very Coarse | 1 - 2 | S | 2 | 2% | 5% | |
| Very Fine | 2 - 4 | G | 5 | 5% | 10% | |
| Fine | 4 - 5.7 | | | 0% | 10% | |
| Fine | 5.7 - 8 | | R | 3 | 3% | 13% |
| Medium | 8 - 11.3 | | A | 7 | 7% | 20% |
| Medium | 11.3 - 16 | | V | 13 | 13% | 33% |
| Coarse | 16 - 22.6 | | E | 11 | 11% | 44% |
| Coarse | 22.6 - 32 | | L | 16 | 16% | 60% |
| Very Coarse | 32 - 45 | | S | 9 | 9% | 69% |
| Very Coarse | 45 - 64 | | | 17 | 17% | 86% |
| Small | 64 - 90 | | C | 12 | 12% | 98% |
| Small | 90 - 128 | O | 2 | 2% | 100% | |
| Large | 128 - 180 | B | | 0% | 100% | |
| Large | 180 - 256 | L | | 0% | 100% | |
| Small | 256 - 362 | B | | 0% | 100% | |
| Small | 362 - 512 | L | | 0% | 100% | |
| Medium | 512 - 1024 | D | | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | | 0% | 100% | |
| Bedrock | >2048 | BDRK | | 0% | 100% | |
| | | Total | 100 | 100% | 100% | |
| Summary Data | | | | | | |
| D50 | 25 | | | | | |
| D84 | 61 | | | | | |
| D95 | 83 | | | | | |





| Cross-Section 4 Riffle - LTC MY-02 | | | | | | |
|------------------------------------|-------------|--------------|-------|--------|-------|-----|
| Particle | Millimeter | Material | Count | Item % | Cum % | |
| Silt/Clay | < 0.062 | S/C | | 0% | 0% | |
| Very Fine | .062 - .125 | S | | 0% | 0% | |
| Fine | .125 - .25 | A | 1 | 1% | 1% | |
| Medium | .25 - .50 | N | 4 | 4% | 5% | |
| Coarse | .50 - 1 | D | 3 | 3% | 8% | |
| Very Coarse | 1 - 2 | S | 3 | 3% | 11% | |
| Very Fine | 2 - 4 | G | 8 | 8% | 19% | |
| Fine | 4 - 5.7 | | | 0% | 19% | |
| Fine | 5.7 - 8 | | R | 1 | 1% | 20% |
| Medium | 8 - 11.3 | | A | 10 | 10% | 30% |
| Medium | 11.3 - 16 | | V | 10 | 10% | 40% |
| Coarse | 16 - 22.6 | | E | 14 | 14% | 53% |
| Coarse | 22.6 - 32 | | L | 11 | 11% | 64% |
| Very Coarse | 32 - 45 | | S | 18 | 18% | 82% |
| Very Coarse | 45 - 64 | | | 11 | 11% | 93% |
| Small | 64 - 90 | | C | 4 | 4% | 97% |
| Small | 90 - 128 | O | 2 | 2% | 99% | |
| Large | 128 - 180 | B | | 0% | 99% | |
| Large | 180 - 256 | L | 1 | 1% | 100% | |
| Small | 256 - 362 | B | | 0% | 100% | |
| Small | 362 - 512 | L | | 0% | 100% | |
| Medium | 512 - 1024 | D | | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | | 0% | 100% | |
| Bedrock | >2048 | BDRK | | 0% | 100% | |
| | | Total | 101 | 100% | 100% | |
| Summary Data | | | | | | |
| D50 | 20 | | | | | |
| D84 | 48 | | | | | |
| D95 | 76 | | | | | |



| Cross-Section 5 Riffle - UT1 MY-02 | | | | | | |
|------------------------------------|-------------|--------------|-------|--------|-------|------|
| Particle | Millimeter | Material | Count | Item % | Cum % | |
| Silt/Clay | < 0.062 | S/C | | 0% | 0% | |
| Very Fine | .062 - .125 | S | 13 | 13% | 13% | |
| Fine | .125 - .25 | A | 12 | 12% | 25% | |
| Medium | .25 - .50 | N | 27 | 27% | 52% | |
| Coarse | .50 - 1 | D | 26 | 26% | 78% | |
| Very Coarse | 1 - 2 | S | 15 | 15% | 93% | |
| Very Fine | 2 - 4 | G | 6 | 6% | 99% | |
| Fine | 4 - 5.7 | | | 0% | 99% | |
| Fine | 5.7 - 8 | | R | 1 | 1% | 100% |
| Medium | 8 - 11.3 | | A | | 0% | 100% |
| Medium | 11.3 - 16 | | V | | 0% | 100% |
| Coarse | 16 - 22.6 | | E | | 0% | 100% |
| Coarse | 22.6 - 32 | | L | | 0% | 100% |
| Very Coarse | 32 - 45 | | S | | 0% | 100% |
| Very Coarse | 45 - 64 | | | | 0% | 100% |
| Small | 64 - 90 | | C | | 0% | 100% |
| Small | 90 - 128 | O | | 0% | 100% | |
| Large | 128 - 180 | B | | 0% | 100% | |
| Large | 180 - 256 | L | | 0% | 100% | |
| Small | 256 - 362 | B | | 0% | 100% | |
| Small | 362 - 512 | L | | 0% | 100% | |
| Medium | 512 - 1024 | D | | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | | 0% | 100% | |
| Bedrock | >2048 | BDRK | | 0% | 100% | |
| | | Total | 100 | 100% | 100% | |
| Summary Data | | | | | | |
| D50 | 0.47 | | | | | |
| D84 | 1.3 | | | | | |
| D95 | 2.5 | | | | | |



| Cross-Section 6 Pool - UT1 MY-02 | | | | | | |
|----------------------------------|-------------|--------------|-------|--------|-------|------|
| Particle | Millimeter | Material | Count | Item % | Cum % | |
| Silt/Clay | < 0.062 | S/C | 2 | 2% | 2% | |
| Very Fine | .062 - .125 | S | 2 | 2% | 4% | |
| Fine | .125 - .25 | A | 2 | 2% | 6% | |
| Medium | .25 - .50 | N | 6 | 6% | 11% | |
| Coarse | .50 - 1 | D | 14 | 13% | 25% | |
| Very Coarse | 1 - 2 | S | 16 | 15% | 40% | |
| Very Fine | 2 - 4 | G | 19 | 18% | 58% | |
| Fine | 4 - 5.7 | | 0% | 58% | | |
| Fine | 5.7 - 8 | | 5 | 5% | 63% | |
| Medium | 8 - 11.3 | | 5 | 5% | 68% | |
| Medium | 11.3 - 16 | | V | 13 | 12% | 80% |
| Coarse | 16 - 22.6 | | E | 8 | 8% | 88% |
| Coarse | 22.6 - 32 | | L | 3 | 3% | 90% |
| Very Coarse | 32 - 45 | | S | 5 | 5% | 95% |
| Very Coarse | 45 - 64 | | | 5 | 5% | 100% |
| Small | 64 - 90 | | C | | 0% | 100% |
| Small | 90 - 128 | O | | 0% | 100% | |
| Large | 128 - 180 | B | | 0% | 100% | |
| Large | 180 - 256 | L | | 0% | 100% | |
| Small | 256 - 362 | B | | 0% | 100% | |
| Small | 362 - 512 | L | | 0% | 100% | |
| Medium | 512 - 1024 | D | | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | | 0% | 100% | |
| Bedrock | >2048 | BDRK | | 0% | 100% | |
| | | Total | 105 | 100% | 100% | |
| Summary Data | | | | | | |
| D50 | 2.9 | | | | | |
| D84 | 19 | | | | | |
| D95 | 44 | | | | | |



| Cross-Section 7 Riffle - UT1 MY-02 | | | | | |
|------------------------------------|-------------|--------------|-------|--------|-------|
| Particle | Millimeter | Material | Count | Item % | Cum % |
| Silt/Clay | < 0.062 | S/C | 1 | 1% | 1% |
| Very Fine | .062 - .125 | S | 1 | 1% | 2% |
| Fine | .125 - .25 | A | 9 | 8% | 10% |
| Medium | .25 - .50 | N | 19 | 17% | 27% |
| Coarse | .50 - 1 | D | 47 | 42% | 69% |
| Very Coarse | 1 - 2 | S | 24 | 21% | 90% |
| Very Fine | 2 - 4 | G | 11 | 10% | 100% |
| Fine | 4 - 5.7 | | 0% | 100% | |
| Fine | 5.7 - 8 | | 0% | 100% | |
| Medium | 8 - 11.3 | | 0% | 100% | |
| Medium | 11.3 - 16 | | 0% | 100% | |
| Coarse | 16 - 22.6 | | 0% | 100% | |
| Coarse | 22.6 - 32 | | 0% | 100% | |
| Very Coarse | 32 - 45 | | 0% | 100% | |
| Very Coarse | 45 - 64 | | 0% | 100% | |
| Small | 64 - 90 | | C | 0% | 100% |
| Small | 90 - 128 | O | 0% | 100% | |
| Large | 128 - 180 | B | 0% | 100% | |
| Large | 180 - 256 | L | 0% | 100% | |
| Small | 256 - 362 | B | 0% | 100% | |
| Small | 362 - 512 | L | 0% | 100% | |
| Medium | 512 - 1024 | D | 0% | 100% | |
| Lrg- Very Lrg | 1024 - 2048 | R | 0% | 100% | |
| Bedrock | >2048 | BDRK | 0% | 100% | |
| | | Total | 112 | 100% | 100% |
| Summary Data | | | | | |
| D50 | 0.73 | | | | |
| D84 | 1.6 | | | | |
| D95 | 2.8 | | | | |





Table 10 Baseline Stream Data Summary Table: Little Troublesome Creek - 1,375 lf
Little Troublesome / Project No. 749

| Parameter | Regional Curve | | | Pre-Existing Condition | | | | | | Reference Reach(es) Data | | | | | | Design | | | As-built | | | | | | | | | |
|---|----------------|----|-----|------------------------|-------|-----------|-------|------|----|--------------------------|------|-----------|--------|-----|-----|--------|-----------|-------|----------|--------|--------|--------|--------|----|----|----|---|---|
| | LL | UL | Eq. | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Med | Max | Min | Mean | Med | Max | SD | n | | | | |
| Dimension and Substrate - Riffle | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width (ft) | | | | 21.3 | 24.2 | 23.3 | 29.0 | 3.4 | 4 | 11.9 | | | 20.1 | | 2 | | 31.6 | | 32.1 | 32.7 | 32.6 | 33.3 | 0.6 | 3 | | | | |
| Floodprone Width (ft) | | | | | >65 | | | | 3 | | >60 | | | | 2 | | >60 | | | >200 | | | | | 3 | | | |
| Bankfull Mean Depth (ft) | | | | 4.4 | 4.7 | 4.8 | 5.0 | 0.2 | 4 | 1.7 | | | 2.7 | | 2 | | 3.7 | | 3.6 | 3.7 | 3.7 | 3.7 | 0.1 | 3 | | | | |
| Bankfull Max Depth (ft) | | | | 6.2 | 6.6 | 6.7 | 6.9 | 0.3 | 4 | 3.3 | | | 4.2 | | 2 | | 4.9 | | 4.7 | 4.8 | 4.8 | 4.9 | 0.1 | 3 | | | | |
| Bankfull Cross-Sectional Area (ft ²) | | | | 106.1 | 114.3 | 107.6 | 135.8 | 14.4 | 4 | 32.4 | | | 33.4 | | 2 | | 118.0 | | 118.6 | 118.8 | 118.6 | 119.2 | 0.3 | 3 | | | | |
| Width/Depth Ratio | | | | 4.2 | 5.0 | 4.7 | 6.2 | 1.0 | 3 | 4.4 | | | 12.1 | | 2 | | 8.5 | | 8.7 | 9.0 | 8.9 | 9.3 | 0.3 | 3 | | | | |
| Entrenchment Ratio | | | | 2.0 | 2.6 | 2.7 | 3.0 | 0.5 | 3 | 2.0 | | | 3.0 | | 2 | | >3.0 | | | >6.0 | | | | | 3 | | | |
| Bank Height Ratio | | | | 1.0 | 1.1 | 1.1 | 1.2 | 0.1 | 3 | 1.0 | | | 1.1 | | 2 | | 1.0 | | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 3 | | | | |
| d50 (mm) | | | | 4.5 | 6.8 | 6.8 | 9.1 | 3.3 | 2 | 1.9 | | | 3.4 | | 2 | | | | 4.1 | 12.7 | 14.0 | 20.0 | 8.0 | 3 | | | | |
| Profile | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Riffle Length (ft) | | | | | | | | | | | | | | | | | 58 | | 60 | 90 | 89 | 121 | 21 | 6 | | | | |
| Riffle Slope (ft/ft) | | | | | | | | | | 0.0010 | | | 0.0070 | | | 0.002 | | 0.004 | 0.0008 | 0.0022 | 0.0018 | 0.0039 | 0.0013 | 6 | | | | |
| Pool Length (ft) | | | | | | | | | | 13 | | | 21 | | | 20 | | 56 | 11 | 60 | 42 | 144 | 42 | 7 | | | | |
| Pool Max Depth | | | | | | | | | | 1.5 | | | 2.5 | | | | 7.5 | | 4.9 | 5.7 | 5.8 | 6.2 | 0.5 | 7 | | | | |
| Pool Spacing (ft) | | | | | | | | | | 32 | | | 80 | | | 50 | | 212 | 169 | 199 | 180 | 285 | 44 | 6 | | | | |
| Pool Volume (ft ³) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Pattern | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Channel Beltwidth (ft) | | | | | | | | | | 50 | | | 60 | | | | 125 | | 51 | 63 | 55 | 85 | 15 | 6 | | | | |
| Radius of Curvature (ft) | | | | | | | | | | 24 | | | 31 | | | 72 | | 126 | 59 | 87 | 90 | 120 | 24 | 7 | | | | |
| Rc:Bankfull width (ft/ft) | | | | | | | | | | 1.2 | | | 2.6 | | | 2.3 | | 4.0 | 1.8 | 2.7 | 2.8 | 3.7 | | | | | | |
| Meander Wavelength (ft) | | | | | | | | | | 77 | | | 138 | | | 158 | | 358 | 293 | 328 | 318 | 385 | 35 | 5 | | | | |
| Meander Width Ratio | | | | | | | | | | 2.5 | | | 5.0 | | | | 3.9 | | 1.6 | 1.9 | 1.7 | 2.6 | | | | | | |
| Substrate, bed and transport parameters | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Ri%/Ru%/P%/G%/S% | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SC% / Sa% / G% / C% / B% / Be% | | | | | 3% | 54% | 40% | 3% | 0% | 0% | | 0% | 52% | 48% | 0% | 0% | 0% | | 1% | 19% | 75% | 6% | 0% | 0% | | | | |
| d16 / d35 / d50 / d84 / d95 / di ^p / di ^{sp} (mm) | | | | | 0.26 | 0.56 | 1.4 | 8.1 | 15 | - | - | | 0.7 | 1.2 | 1.9 | 16 | 26 | - | - | | 0.79 | 6.1 | 10 | 18 | 42 | 71 | - | - |
| Reach Shear Stress (competency) lb/ft ² | | | | | | | | | | | | | | | | | 0.38 | | | | 0.28 | | | | | | | |
| Max part size (mm) mobilized at bankfull | | | | | | | | | | | | | | | | | 28 | | | | 20 | | | | | | | |
| Stream Power (transport capacity) W/m ² | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Additional Reach Parameters | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Drainage Area (SM) | | | | | | 12.09 | | | | | | 1.68 | | | | | 12.09 | | | | 12.09 | | | | | | | |
| Impervious cover estimate | | | | | | 21% | | | | | | | | | | | 21% | | | | 21% | | | | | | | |
| Rosgen Classification | | | | | | E4 | | | | | | E4 | | | | | E4/C4 | | | | E4/C4 | | | | | | | |
| Bankfull Velocity (fps) | | | | | | 4.1 - 5.3 | | | | | | 3.4 - 4.4 | | | | | 4.3 | | | | | | | | | | | |
| Bankfull Discharge (cfs) | | | | | | 553 - 564 | | | | | | 115 - 150 | | | | | 510 - 550 | | | | | | | | | | | |
| Valley length (ft) | | | | | | 1,273 | | | | | | | | | | | 1,273 | | | | 1,273 | | | | | | | |
| Channel thalweg length (ft) | | | | | | 1,329 | | | | | | | | | | | 1,379 | | | | 1,401 | | | | | | | |
| Sinuosity | | | | | | 1.06 | | | | | | | | | | | 1.10 | | | | 1.10 | | | | | | | |
| Water Surface Slope (Channel) (ft/ft) | | | | | | 0.0020 | | | | | | 0.0030 | | | | | 0.0020 | | | | 0.0015 | | | | | | | |
| BF slope (ft/ft) | | | | | | 0.0020 | | | | | | | | | | | 0.0020 | | | | 0.0018 | | | | | | | |
| Bankfull Floodplain Area (acres) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Proportion over wide (%) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Entrenchment Class (ER Range) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Incision Class (BHR Range) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| BEHI VL% / L% / M% / H% / VH% / E% | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Channel Stability or Habitat Metric | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Biological or Other | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Table 10 Baseline Stream Data Summary Table: UT1 - 813 lf

Little Troublesome / Project No. 749

| Parameter | Regional Curve | | | Pre-Existing Condition | | | | | | Reference Reach(es) Data | | | | | | Design | | | As-built | | | | | |
|---|----------------|----|-----|---------------------------|------|------|------|-----|---|------------------------------|------|-----|--------|----|---|-------------------------------------|------|--------|----------|--------|--------|--------|--------|----|
| | LL | UL | Eq. | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Med | Max | Min | Mean | Med | Max | SD | n |
| Dimension and Substrate - Riffle | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width (ft) | | | | 4.0 | 5.4 | 5.1 | 7.7 | 1.4 | 5 | 7.7 | | | 10.8 | | | | 6.3 | | 7.2 | 7.6 | | 7.9 | 0.5 | 2 |
| Floodprone Width (ft) | | | | 5 | 6 | 6 | 7 | 0.9 | 3 | 13 | | | 16 | | | | 12 | | 13 | 13 | | 14 | 0.6 | 2 |
| Bankfull Mean Depth (ft) | | | | 0.7 | 0.9 | 0.9 | 1.1 | 0.2 | 5 | 0.7 | | | 0.9 | | | | 0.6 | | 0.6 | 0.6 | | 0.6 | 0 | 2 |
| Bankfull Max Depth (ft) | | | | 1.0 | 1.3 | 1.1 | 1.9 | 0.4 | 5 | 1.1 | | | 1.4 | | | | 1.0 | | 1.1 | 1.1 | | 1.1 | 0 | 2 |
| Bankfull Cross-Sectional Area (ft ²) | | | | 3.6 | 4.6 | 4.3 | 5.8 | 1.0 | 5 | 6.1 | | | 8.8 | | | | 3.5 | | 4.5 | 4.7 | | 4.8 | 0.2 | 2 |
| Width/Depth Ratio | | | | 4.4 | 5.7 | 5.6 | 7.0 | 1.3 | 3 | 8.5 | | | 11.4 | | | | 11.4 | | 11.5 | 12.3 | | 13.0 | 1.1 | 2 |
| Entrenchment Ratio | | | | 1.0 | 1.3 | 1.4 | 1.5 | 0.3 | 3 | 1.6 | | | 2.1 | | | | 1.9 | | 1.6 | 1.8 | | 1.9 | 0.2 | 2 |
| Bank Height Ratio | | | | 5.3 | 6.1 | 6.4 | 6.5 | 0.7 | 3 | | | | | | | | 1.0 | | 1.0 | 1.0 | | 1.0 | 0 | 2 |
| d50 (mm) | | | | 2.2 | 11.2 | 12.3 | 19.2 | 8.6 | 3 | | | | | | | | | | 0.8 | 1.0 | | 1.1 | 0.2 | 2 |
| Profile | | | | | | | | | | | | | | | | | | | | | | | | |
| Riffle Length (ft) | | | | | | | | | | | | | | | | | | | 3 | 11 | 8 | 32 | 9 | 11 |
| Riffle Slope (ft/ft) | | | | | | | | | | 0.0120 | | | 0.0280 | | | 0.0180 | | 0.0400 | 0.0077 | 0.0378 | 0.0318 | 0.1022 | 0.0283 | 11 |
| Pool Length (ft) | | | | | | | | | | 5 | | | 9 | | | 3 | | 11 | 5 | 13 | 12 | 36 | 8 | 14 |
| Pool Max Depth | | | | | | | | | | 0.8 | | | 0.9 | | | | 1.4 | | 1.7 | 2.3 | 2.2 | 3.0 | 0.5 | 12 |
| Pool Spacing (ft) | | | | | | | | | | | | | | | | | | | 21 | 44 | 41 | 81 | 22 | 13 |
| Pool Volume (ft ³) | | | | | | | | | | | | | | | | | | | | | | | | |
| Pattern | | | | | | | | | | | | | | | | | | | | | | | | |
| Channel Beltwidth (ft) | | | | | | | | | | | 22 | | | | | | 13 | | 6 | 9 | 9 | 14 | 2.1 | 19 |
| Radius of Curvature (ft) | | | | | | | | | | 11 | | | 23 | | | 13 | | 32 | 14 | 18 | 18 | 27 | 4.5 | 27 |
| Rc:Bankfull width (ft/ft) | | | | | | | | | | 1.0 | | | 3.0 | | | 2.0 | | 5.0 | 1.8 | 2.4 | 2.4 | 3.6 | | |
| Meander Wavelength (ft) | | | | | | | | | | 45 | | | 59 | | | 32 | | 63 | 40 | 51 | 49 | 69 | 7.6 | 25 |
| Meander Width Ratio | | | | | | | | | | 2.0 | | | 2.9 | | | 2.0 | | 2.9 | 0.8 | 1.2 | 1.2 | 1.9 | | |
| Substrate, bed and transport parameters | | | | | | | | | | | | | | | | | | | | | | | | |
| Ri%/Ru%/P%/G%/S% | | | | | | | | | | | | | | | | | | | | | | | | |
| SC% / Sa% / G% / C% / B% / Be% | | | | 0% / 27% / 73% / 0% / 0% | | | | | | 6% / 45% / 42% / 7% / 0% | | | | | | 1% / 63% / 36% / 0% / 0% / 0% | | | | | | | | |
| d16 / d35 / d50 / d84 / d95 / di ^p / di ^{sp} (mm) | | | | 1.4 / 3.2 / 7.3 / 15 / 20 | | | | | | 0.14 / 0.38 / 1.8 / 18 / 139 | | | | | | 0.22 / 0.47 / 0.87 / 2.1 / 7.3 / 23 | | | | | | | | |
| Reach Shear Stress (competency) lb/ft ² | | | | | | | | | | | | | | | | | 0.42 | | | | | 0.60 | | |
| Max part size (mm) mobilized at bankfull | | | | | | | | | | | | | | | | | 32 | | | | | 35 | | |
| Stream Power (transport capacity) W/m ² | | | | | | | | | | | | | | | | | | | | | | | | |
| Additional Reach Parameters | | | | | | | | | | | | | | | | | | | | | | | | |
| Drainage Area (SM) | | | | 0.10 | | | | | | 0.15 | | | | | | 0.10 | | | 0.10 | | | | | |
| Impervious cover estimate | | | | | | | | | | | | | | | | | | | | | | | | |
| Rosgen Classification | | | | G4c | | | | | | B4c | | | | | | B4c | | | B4c | | | | | |
| Bankfull Velocity (fps) | | | | 4.3 - 4.7 | | | | | | 5.1 - 5.8 | | | | | | 3.7 | | | 3.7 | | | | | |
| Bankfull Discharge (cfs) | | | | 16 - 20 | | | | | | 31 - 49 | | | | | | 13 - 20 | | | 17 | | | | | |
| Valley length (ft) | | | | 769 | | | | | | 769 | | | | | | 769 | | | 769 | | | | | |
| Channel thalweg length (ft) | | | | 873 | | | | | | 813 | | | | | | 813 | | | 824 | | | | | |
| Sinuosity | | | | 1.02 | | | | | | 1.20 | | | | | | 1.10 | | | 1.10 | | | | | |
| Water Surface Slope (Channel) (ft/ft) | | | | 0.019 | | | | | | 0.012 | | | | | | 0.018 | | | 0.017 | | | | | |
| BF slope (ft/ft) | | | | 0.021 | | | | | | 0.017 | | | | | | 0.021 | | | 0.016 | | | | | |
| Bankfull Floodplain Area (acres) | | | | | | | | | | | | | | | | | | | | | | | | |
| Proportion over wide (%) | | | | | | | | | | | | | | | | | | | | | | | | |
| Entrenchment Class (ER Range) | | | | | | | | | | | | | | | | | | | | | | | | |
| Incision Class (BHR Range) | | | | | | | | | | | | | | | | | | | | | | | | |
| BEHI VL% / L% / M% / H% / VH% / E% | | | | | | | | | | | | | | | | | | | | | | | | |
| Channel Stability or Habitat Metric | | | | | | | | | | | | | | | | | | | | | | | | |
| Biological or Other | | | | | | | | | | | | | | | | | | | | | | | | |

**Table 11a. Cross-Section Morphology Data Tables
Little Troublesome / Project No. 749**

| Dimension and Substrate | Cross-Section 1 (LTC, Riffle) Station 13+08 | | | | | | | | Cross-Section 2 (LTC, Pool) Station 13+90 | | | | | | | | Cross-Section 3 (LTC, Riffle) Station 16+30 | | | | | | | | Cross-Section 4 (LTC, Riffle) Station 19+42 | | | | | | | | Cross-Section 5 (UT1, Riffle) Station 51+56 | | | | | | | |
|--|--|-------|-------|-----|-----|-----|-----|-------|--|-------|-----|-----|-----|-----|-------|-------|--|-----|-----|-----|-----|-------|-------|-------|--|-----|-----|-----|-------|-------|-------|--|--|-----|-----|-----|-----|-----|-----|--|
| | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | |
| Based on fixed baseline elevation | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width (ft) | 32.6 | 33.0 | 33.2 | | | | | 36.0 | 39.1 | 37.5 | | | | | 32.1 | 32.3 | 32.2 | | | | | 33.3 | 33.5 | 33.1 | | | | | 7.9 | 7.7 | 6.9 | | | | | | | | | |
| Floodprone Width (ft) | >200 | >200 | >200 | | | | | - | - | - | | | | | >200 | >200 | >200 | | | | | >200 | >200 | >200 | | | | | 13 | 13 | 11 | | | | | | | | | |
| Bankfull Mean Depth (ft) | 3.7 | 3.6 | 3.5 | | | | | 3.4 | 3.4 | 3.6 | | | | | 3.7 | 3.6 | 3.6 | | | | | 3.6 | 3.6 | 3.5 | | | | | 0.6 | 0.5 | 0.3 | | | | | | | | | |
| Bankfull Max Depth (ft) | 4.8 | 4.8 | 4.9 | | | | | 6.0 | 7.3 | 7.7 | | | | | 4.9 | 4.9 | 4.9 | | | | | 4.7 | 4.9 | 5.0 | | | | | 1.1 | 0.9 | 0.5 | | | | | | | | | |
| Bankfull Cross-Sectional Area (ft ²) | 119.2 | 118.4 | 117.4 | | | | | 123.1 | 134.3 | 135.0 | | | | | 118.6 | 117.5 | 114.8 | | | | | 118.6 | 120.0 | 115.9 | | | | | 4.8 | 4.1 | 2.0 | | | | | | | | | |
| Bankfull Width/Depth Ratio | 8.9 | 9.2 | 9.4 | | | | | - | - | - | | | | | 8.7 | 8.9 | 9 | | | | | 9.3 | 9.4 | 9.5 | | | | | 13.0 | 14.5 | 23.3 | | | | | | | | | |
| Bankfull Entrenchment Ratio | >6.0 | >6.0 | >6.0 | | | | | - | - | - | | | | | >6.0 | >6.0 | >6.0 | | | | | >6.0 | >6.0 | >6.0 | | | | | 1.6 | 1.6 | 1.5 | | | | | | | | | |
| Bankfull Bank Height Ratio | 1.0 | 1.0 | 1.0 | | | | | - | - | - | | | | | 1.0 | 1.0 | 1.0 | | | | | 1.0 | 1.0 | 1.0 | | | | | 1.0 | 1.0 | 1.0 | | | | | | | | | |
| Cross-Sectional Area Between End Pins (ft ²) | 142.4 | 147.9 | 144.2 | | | | | 170.0 | 171.1 | 170.2 | | | | | 156.0 | 160.1 | 156.7 | | | | | 162.2 | 165.8 | 161.2 | | | | | 150.8 | 156.3 | 152.5 | | | | | | | | | |
| d50 (mm) | 20.0 | 29.0 | 26.0 | | | | | 1.8 | 0.36 | 0.94 | | | | | 14.0 | 22.0 | 25.0 | | | | | 4.1 | 8.4 | 20.0 | | | | | 1.1 | 8.9 | 0.47 | | | | | | | | | |
| | Cross-Section 6 (UT1, Pool) Station 55+08 | | | | | | | | Cross-Section 7 (UT1, Riffle) Station 56+84 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Based on fixed baseline elevation | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | Base | MY1 | MY2 | MY3 | MY4 | MY5 | MY+ | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width (ft) | 4.6 | 4.8 | 4.5 | | | | | 7.2 | 6.9 | 6.9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Floodprone Width (ft) | - | - | - | | | | | 13.6 | 13.6 | 12.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Mean Depth (ft) | 0.9 | 1.0 | 1.0 | | | | | 0.6 | 0.6 | 0.5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Max Depth (ft) | 1.4 | 1.6 | 1.6 | | | | | 1.1 | 1.0 | 0.7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Cross-Sectional Area (ft ²) | 4.2 | 4.8 | 4.5 | | | | | 4.5 | 4.3 | 3.2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width/Depth Ratio | - | - | - | | | | | 11.5 | 11.1 | 15.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Entrenchment Ratio | - | - | - | | | | | 1.9 | 2.0 | 1.7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Bank Height Ratio | - | - | - | | | | | 1.0 | 1.0 | 1.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Cross-Sectional Area Between End Pins (ft ²) | 146.9 | 149.8 | 149.9 | | | | | 120.6 | 123.6 | 121.4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| d50 (mm) | 1.0 | 8.6 | 2.9 | | | | | 0.82 | 0.4 | 0.73 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Table 11b. Stream Reach Morphology Data Tables

Little Troublesome / Project No. 749

Segment Reach: Little Troublesome Creek (1,375 ft.)

| Parameter | MY01 (2010) | | | | | | MY02 (2011) | | | | | | MY03 (2012) | | | | | | MY04 (2013) | | | | | | MY05 (2014) | | | | | |
|--|-------------|-------|-----------------------|-------|-------|---|-------------|-------|-----------------------|-------|-------|---|-------------|------|-----|-----|----|---|-------------|------|-----|-----|----|---|-------------|------|-----|-----|----|---|
| | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n |
| Dimension | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width (ft) | 32.3 | 33.0 | | 33.5 | | 3 | 32.2 | 32.8 | | 33.2 | | 3 | | | | | | | | | | | | | | | | | | |
| Floodprone Width (ft) | 200 | 200 | | 200 | | 3 | 200 | 200 | | 200 | | 3 | | | | | | | | | | | | | | | | | | |
| Bankfull Mean Depth (ft) | 3.6 | 3.6 | | 3.6 | | 3 | 3.5 | 3.5 | | 3.6 | | 3 | | | | | | | | | | | | | | | | | | |
| Bankfull Max Depth (ft) | 4.8 | 4.9 | | 4.9 | | 3 | 4.9 | 4.9 | | 5.0 | | 3 | | | | | | | | | | | | | | | | | | |
| Bankfull Cross-Sectional Area (ft ²) | 117.5 | 118.4 | | 120.0 | | 3 | 114.8 | 116.0 | | 117.4 | | 3 | | | | | | | | | | | | | | | | | | |
| Width/Depth Ratio | 8.9 | 9.2 | | 9.4 | | 3 | 9.0 | 9.3 | | 9.5 | | 3 | | | | | | | | | | | | | | | | | | |
| Entrenchment Ratio | 6.0 | 6.0 | | 6.0 | | 3 | 6.0 | 6.0 | | 6.0 | | 3 | | | | | | | | | | | | | | | | | | |
| Bank Height Ratio | 1.0 | 1.0 | | 1.0 | | 3 | 1.0 | 1.0 | | 1.0 | | 3 | | | | | | | | | | | | | | | | | | |
| Pattern | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Channel Beltwidth (ft) | 66 | 89 | 90 | 110 | 18.2 | 6 | 66 | 89 | 90 | 110 | 18.2 | 6 | | | | | | | | | | | | | | | | | | |
| Radius of Curvature (ft) | 80 | 96 | 80 | 120 | 21.9 | 5 | 80 | 96 | 80 | 120 | 21.9 | 5 | | | | | | | | | | | | | | | | | | |
| Rad. of Curv. : Bankfull Width (ft/ft) | 2.4 | 2.9 | 2.4 | 3.6 | | | 2.5 | 2.9 | 2.4 | 3.6 | | | | | | | | | | | | | | | | | | | | |
| Meander Wavelength (ft) | 280 | 318 | 314 | 375 | 33.2 | 6 | 280 | 318 | 314 | 375 | 33.2 | 6 | | | | | | | | | | | | | | | | | | |
| Meander Width Ratio | 2.0 | 2.7 | 2.7 | 3.3 | | | 2 | 2.7 | 2.7 | 3.3 | | | | | | | | | | | | | | | | | | | | |
| Profile | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Riffle Length (ft) | 21 | 65 | 60 | 104 | 26 | 7 | 75 | 86 | 83 | 112 | 14 | 7 | | | | | | | | | | | | | | | | | | |
| Riffle Slope (ft/ft) | 0.002 | 0.005 | 0.004 | 0.014 | 0.004 | 7 | 0.001 | 0.003 | 0.003 | 0.005 | 0.001 | 7 | | | | | | | | | | | | | | | | | | |
| Pool Length (ft) | 32 | 65 | 48 | 127 | 35 | 7 | 53 | 79 | 68 | 161 | 39 | 7 | | | | | | | | | | | | | | | | | | |
| Pool Max Depth (ft) | 7.3 | 7.3 | | 7.3 | | 1 | 3.3 | 3.3 | | 3.3 | | 1 | | | | | | | | | | | | | | | | | | |
| Pool Spacing (ft) | 93 | 198 | 179 | 291 | 73 | 6 | 166 | 202 | 179 | 308 | 54 | 6 | | | | | | | | | | | | | | | | | | |
| Additional Reach Parameters | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Valley Length (ft) | | | 1,285 | | | | | | 1,285 | | | | | | | | | | | | | | | | | | | | | |
| Channel Thalweg Length (ft) | | | 1,402 | | | | | | 1,402 | | | | | | | | | | | | | | | | | | | | | |
| Sinuosity | | | 1.08 | | | | | | 1.08 | | | | | | | | | | | | | | | | | | | | | |
| Water Surface Slope (ft/ft) | | | 0.0015 | | | | | | 0.0015 | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Slope (ft/ft) | | | 0.0018 | | | | | | 0.0018 | | | | | | | | | | | | | | | | | | | | | |
| Rosgen Classification | | | C5 | | | | | | C5 | | | | | | | | | | | | | | | | | | | | | |
| Ri% / Ru% / P% / G% / S% | | | 25 / 20 / 30 / 25 / 0 | | | | | | 25 / 20 / 30 / 25 / 0 | | | | | | | | | | | | | | | | | | | | | |
| SC% / Sa% / G% / C% / B% / Be% | | | 0%/12%/81%/7%/0%/0% | | | | | | 0%/26%/62%/12%/0%/0% | | | | | | | | | | | | | | | | | | | | | |
| d16 / d35 / d50 / d84 / d95 | | | 7.3/17/22/50/76 | | | | | | 5.3/12/18/52/78 | | | | | | | | | | | | | | | | | | | | | |
| % of Reach with Eroding Banks | | | 1% | | | | | | 1% | | | | | | | | | | | | | | | | | | | | | |

Table 11b. Stream Reach Morphology Data Tables

Little Troublesome / Project No. 749

Segment Reach: UT1 (813 ft.)

| Parameter | MY01 (2010) | | | | | | MY02 (2011) | | | | | | MY03 (2012) | | | | | | MY04 (2013) | | | | | | MY05 (2014) | | | | | |
|--|-------------|-------|---------------------|-------|-------|----|-------------|-------|-----------------------|-------|-------|---|-------------|------|-----|-----|----|---|-------------|------|-----|-----|----|---|-------------|------|-----|-----|----|---|
| | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n | Min | Mean | Med | Max | SD | n |
| Dimension | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Width (ft) | 6.9 | 7.3 | | 7.7 | 0.566 | 2 | 6.9 | 6.9 | | 6.9 | 0.000 | 2 | | | | | | | | | | | | | | | | | | |
| Floodprone Width (ft) | 12.7 | 13.15 | | 13.6 | 0.636 | 2 | 10.5 | 11.3 | | 12.0 | 1.061 | 2 | | | | | | | | | | | | | | | | | | |
| Bankfull Mean Depth (ft) | 0.5 | 0.6 | | 0.6 | 0.064 | 2 | 0.3 | 0.4 | | 0.5 | 0.141 | 2 | | | | | | | | | | | | | | | | | | |
| Bankfull Max Depth (ft) | 0.9 | 1.0 | | 1.0 | 0.064 | 2 | 0.5 | 0.6 | | 0.7 | 0.141 | 2 | | | | | | | | | | | | | | | | | | |
| Bankfull Cross-Sectional Area (ft ²) | 4.1 | 4.2 | | 4.3 | 0.141 | 2 | 2.0 | 2.6 | | 3.2 | 0.849 | 2 | | | | | | | | | | | | | | | | | | |
| Width/Depth Ratio | 11.1 | 12.8 | | 14.5 | 2.396 | 2 | 15.0 | 19.2 | | 23.3 | 5.869 | 2 | | | | | | | | | | | | | | | | | | |
| Entrenchment Ratio | 1.6 | 1.8 | | 2.0 | 0.283 | 2 | 1.5 | 1.6 | | 1.7 | 0.141 | 2 | | | | | | | | | | | | | | | | | | |
| Bank Height Ratio | 1.0 | 1.0 | | 1.0 | 0.000 | 2 | 1.0 | 1.0 | | 1.0 | 0.000 | 2 | | | | | | | | | | | | | | | | | | |
| Pattern | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Channel Beltwidth (ft) | 7 | 12 | 12 | 17 | 2.91 | 21 | | | | | | | | | | | | | | | | | | | | | | | | |
| Radius of Curvature (ft) | 12 | 18.1 | 20 | 25 | 3.19 | 26 | | | | | | | | | | | | | | | | | | | | | | | | |
| Rad. of Curv. : Bankfull Width (ft/ft) | 1.7 | 2.5 | 2.7 | 2.5 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Meander Wavelength (ft) | 45 | 50.1 | 50 | 56 | 2.79 | 22 | | | | | | | | | | | | | | | | | | | | | | | | |
| Meander Width Ratio | 1.0 | 1.64 | 1.64 | 2.33 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Profile | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Riffle Length (ft) | 2 | 10 | 6 | 42 | 12 | 13 | 8 | 12 | 9 | 22 | 6 | 6 | | | | | | | | | | | | | | | | | | |
| Riffle Slope (ft/ft) | 0.000 | 0.061 | 0.049 | 0.162 | 0.053 | 13 | 0.026 | 0.045 | 0.041 | 0.076 | 0.020 | 6 | | | | | | | | | | | | | | | | | | |
| Pool Length (ft) | 3 | 9 | 6 | 30 | 7 | 16 | 6 | 14 | 11 | 38 | 10 | 9 | | | | | | | | | | | | | | | | | | |
| Pool Max Depth (ft) | 1.6 | | 1.6 | 1.6 | | 1 | 1.6 | | 1.6 | 1.6 | | 1 | | | | | | | | | | | | | | | | | | |
| Pool Spacing (ft) | 18 | 39 | 33 | 69 | 18 | 15 | 24 | 55 | 47 | 98 | 27 | 8 | | | | | | | | | | | | | | | | | | |
| Additional Reach Parameters | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Valley Length (ft) | | | 780 | | | | | | 780 | | | | | | | | | | | | | | | | | | | | | |
| Channel Thalweg Length (ft) | | | 811 | | | | | | 811 | | | | | | | | | | | | | | | | | | | | | |
| Sinuosity | | | 1.04 | | | | | | 1.04 | | | | | | | | | | | | | | | | | | | | | |
| Water Surface Slope (ft/ft) | | | 0.0171 | | | | | | 0.0181 | | | | | | | | | | | | | | | | | | | | | |
| Bankfull Slope (ft/ft) | | | 0.0164 | | | | | | 0.0164 | | | | | | | | | | | | | | | | | | | | | |
| Rosgen Classification | | | B5 | | | | | | B5 | | | | | | | | | | | | | | | | | | | | | |
| Ri% / Ru% / P% / G% / S%* | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SC% / Sa% / G% / C% / B% / Be% | | | 3%/83%/15%/0%/0%/0% | | | | | | 1%/73%/26%/0%/0%/0% | | | | | | | | | | | | | | | | | | | | | |
| d16 / d35 / d50 / d84 / d95 | | | 0.16/0.3/0.4/1.7/9 | | | | | | 0.37/0.8/1.4/7.3/16.4 | | | | | | | | | | | | | | | | | | | | | |
| % of Reach with Eroding Banks | | | 5% | | | | | | 5% | | | | | | | | | | | | | | | | | | | | | |

*The small size of UT 1 combined with vegetation growing in the channel creates poorly defined features.

**Table 12. Verification of Bankfull Events
Little Troublesome / Project No. 749**

| Date of Data Collection | Date of Occurrence | Method | Photo Number |
|--------------------------------|---------------------------|--|-----------------------|
| 6/14/2009 | 6/11/2009 | Site visit to evaluate indicators of stage after storm event | N/A |
| 11/11/2009 | 11/11/2009 | Site visit to evaluate indicators of stage after storm event | N/A |
| 12/25/2009 | 12/25/2009 | Land owner, eye-witness account | N/A |
| 1/25/2010 | 1/25/2010 | Site visit to evaluate indicators of stage after storm event | N/A |
| 10/7/2010 | 9/26/2010 | Site visit to evaluate indicators of stage after storm event | see MY01 report photo |
| 11/18/2011 | unknown | Crest gauge and indicators of storm event | N/A |