

# Lyle Creek Restoration

## 2003 Annual Monitoring Report



Delivered to: NCDENR/Ecosystem Enhancement Program  
1619 Mail Service Center  
Raleigh, NC 27699-1619

Prepared by: Biological & Agricultural Engineering  
Water Resources Research Institute  
North Carolina State University  
Campus Box 7625  
Raleigh, NC 27695

March, 2004



**NC STATE UNIVERSITY**

## 2003 Lyle Creek Monitoring Abstract

An Unnamed Tributary to Lyle Creek was enhanced/restored through the North Carolina Wetlands Restoration Program (NCWRP). The objectives of the project are to:

- 1.) Establish an stable dimension, pattern and profile on 2260 feet of Lyle Creek
- 2.) Improve habitat within Little Lyle Creek
- 3.) Establish an riparian buffer along Lyle Creek

This is the 2<sup>nd</sup> year of the 5-year monitoring plan for Lyle Creek.

**Table 1A. Background Information**

<b>Project Name</b>	Lyle Creek
<b>Designer's Name</b>	Eco-Science Corporation 1101 Haynes Street, Suite 101 Raleigh, NC 27604
<b>Contractor's Name</b>	North State Environmental, Inc.
<b>Project County</b>	Catawba County, North Carolina
<b>Directions to Project Site</b>	From Interstate I-40 take Exit 138. Head south on Oxford School Rd for 0.1 mile. Turn right on Wyke Rd follow Wyke Rd for 1 mile. Turn Right on US-70, follow US-70 for 0.2 mile. The project approximately located 1000ft upstream of the US-70 Bridge over Lyle Creek.
<b>Drainage Area</b>	0.5 sq. mi.
<b>USGS Hydro Unit</b>	3050101
<b>NCDWQ Subbasin</b>	11-01-76
<b>Project Length</b>	2,400 Linear feet
<b>Restoration Approach</b>	1,345-feet of dimension, pattern, and profile 1,055-feet of bank and riparian enhancement
<b>Date of Completion</b>	July, 2002
<b>Monitoring Dates</b>	February, 2003; November, 2003

### Results and Discussion

Overall, while the majority of the stream is functioning and is holding grade, the stream has two major areas of concern that total 425 linear feet and should be maintained as soon as possible. Table 2 shows a summary of monitoring measurement results. Overall the project is performing well. Channel dimension, pattern, and profile are similar to as-built conditions with the exceptions of some limited areas of bank slumping and the 425 linear feet of concern. Vegetation is not succeeding to levels required for mitigation credit. Placed structures are holding grade and functioning well. Concerns include two headcuts, areas with bank slumping and erosion, piping and large drops off a few structures

**Table 2A. Summary of Channel Conditions**

DIMENSION	Lyle Creek In-Place Reach Cross-section #1 Pool		Lyle Creek In-Place Reach Cross-section #2 Riffle		Lyle Creek In-Place Reach Cross-section #3 Riffle		Lyle Creek Relocation Reach Cross-section #4 Riffle		Lyle Creek Relocation Reach Cross-section #5 Riffle		Lyle Creek Relocation Reach Cross-section #6 Pool		Lyle Creek Relocation Reach Cross-section #7 Riffle		
	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	
	Bankfull Cross-sectional Area	20.8	14.1	16.5	28.1	15.6	26.1	17.5	17.8	16.9	20.7	19.6	27.3	15.2	16.2
	Bankfull Width	16.3	16.5	11.8	18.6	13.2	16.2	10.8	10.8	10.7	13.9	12.8	13.5	11.2	11.2
Bankfull Mean Depth	1.3	0.9	1.4	1.5	1.2	1.6	1.6	1.6	1.6	1.5	1.5	2.0	1.4	1.4	
Bankfull Max Depth	3.1	1.7	2.2	2.4	2.2	2.0	2.7	2.6	2.5	2.6	2.8	2.7	2.2	2.1	

PATTERN	Lyle Creek As-built			Lyle Creek 2003			Lyle Creek (in place) As-built			Lyle Creek (in place) 2003		
	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median
Meander Wave Length	33	114	63	49	150	71	Not Reported			59	177	149
Radius of Curvature	14.9	37.5	22.4	16.7	38.5	20.9	Not Reported			13.3	48.6	30.9
Beltwidth	33	141	88	22	56	33	Not Reported			42	109	55

PROFILE	Lyle Creek As-built			Lyle Creek 2003			Lyle Creek (in place) As-built			Lyle Creek (in place) 2003		
	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median
Riffle Length	Not Reported			7	39	17	Not Reported			9	68	21
Riffle Slope	0.00%	3.64%	1.41%	0.56%	4.94%	1.71%	Not Reported			0.17%	4.74%	2.12%
Pool Length	14	64	27	9	41	23	Not Reported			11	49	27
Pool to Pool Spacing	22	161	54	27	176	46	Not Reported			28	140	66

SUBSTRATE	Lyle Creek Cross-section #1 Pool		Lyle Creek Cross-section #2 Riffle		Lyle Creek Cross-section #3 Riffle		Lyle Creek Cross-section #4 Riffle		Lyle Creek Cross-section #5 Riffle		Lyle Creek Cross-section #6 Pool		Lyle Creek Cross-section #7 Riffle	
	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003
	D50	0.09	0.29	0.19	0.29	0.19	0.45	0.19	0.11	0.19	0.33	0.09	0.71	0.19
D85	0.52	0.76	15.91	13.33	15.91	1.01	15.91	3.11	15.91	17.52	0.52	31.78	15.91	3.00

VEGETATION	Quad 1 Lyle Creek		Quad 2 Lyle Creek		Quad 3 Lyle Creek		Quad 4 Lyle Creek	
	Observed	Planted	Observed	Planted	Observed	Planted	Observed	Planted
Tree Stratum (trees/acre)	720	0	520	40	600	240	12560	0
Shrub Stratum (% cover)	1.0	-	1.0	-	8.5	-	15.5	-
Herb Stratum (% cover)	62.5	-	184	-	171.5	-	152.2	-

The following areas of concern should be monitored closely and considered for repair as suggested:

- **Easement Limits**
  - NCWRP should work with landowners to ensure easement limits are maintained and that cattle stay out of the riparian area.
- **Areas of major head cuts**
  - There are two areas of major head cut approximately 425 ft
  - The first area has a maximum head cut of one foot and is approximately 190 ft in length this head cut is located from station 13+20 to 15+10. There is still two hundred foot upstream until the next structure controlling grade
  - The second area has a maximum head cut of six inches and is approximately 235 ft in length this head cut is located from station 17+90 to 20+25. There is still three hundred foot upstream until the next structure controlling grade
- **Areas with bank slumping**
  - These areas should be planted heavily with live stakes to help establish root mass along the channel bank.
  - These areas should be monitored closely during upcoming site visits to determine if the problem is localized to more regional in scale.
  - Overland flow may need to be routed away from areas that show signs of severe bank erosion
- **Areas lacking stream features**
  - There are seven riffles that were constructed that do not exist in the longitudinal profile measured during the 2003 monitoring
  - Some of the riffles that have been removed as a result of the major head cuts in the two sections listed above
  - The remainder of the failed riffles have been transformed into runs or glides
- **Areas showing stream pattern adjustments**
  - There are two areas that have shown a significant change in stream pattern
  - The first section is from station 14+00 to 15+00 there is half of a meander wavelength that has been straightened into a long run this is the result of the head cut mentioned above
  - The second section is from station 20+50 to 22+20 there an entire meander wavelength that has been straightened into a run followed by a long step pool feature at the end of the project.
- **Vegetation Concerns**
  - Natural regeneration appears to be dominant and should continue to be monitored for growth habits.
  - Planting more trees if required for mitigation at this time the tree stems per acre is 70 but it appears that natural regeneration will be able to raise the tree stems per acre to the level for mitigation credit
  - It is recommended to stake in areas where erosion is problematic in a few areas, particularly on outside meander bends
  - The invasive vegetation requires no treatment at this time.
  - Adjacent side slope should be stabilized to reduced sediment from washing into the creek.

**Photos**

The following are photographs of typical sections and areas of concern throughout the project.



**Typical Riffle on Lyle Creek.**



**Typical Pool on Lyle Creek.**



**Issue Photo 1  
Cattle within the Lyle Creek Easement.**



**Issue Photo 2 – Station 11+00  
Bank undercutting due to lack of vegetation.**



**Issue Photo 3 and 4 – Station 16+90  
Bank failure due to overland flow.**



**Issue Photo 5 – Station 10+40  
Bank failure under matting.**



**Issue Photo 6 – Station 15+80  
Bank erosion due to lack of vegetation.**



**Issue Photo 7 – Station 15+00  
Bank Failure under matting.**



**Issue Photo 8 – Station 13+70  
Severe bank erosion.**



**Issue Photo 9 – Station 13+40  
Scour around upstream side of cross vane wing.**



**Issue Photo 9A – Station 18+50  
Scour around upstream side of cross vane wing.**



**Issue Photo 9B – Station 19+70  
Scour below cross vane.**

**Figure 1. Project Plan view.**

# Table of Contents

<b>2003 Lyle Creek Monitoring Abstract</b> .....	i
<b>Table of Contents</b> .....	vii
<b>Tables and Figures</b> .....	vii
1.0 BACKGROUND INFORMATION .....	1
1.1 Goals and Objective .....	2
1.2 Project Location.....	2
1.3 Project Description .....	2
2.0 YEAR 2003 RESULTS AND DISCUSSION .....	7
2.1 Vegetation.....	7
2.2 Morphology .....	8
2.2.1 Results and Discussion.....	8
2.3 Areas of Concern.....	13

## Tables and Figures

Figure 1. Project Location Map .....	3
Figure 2. Watershed Ortho-Photo .....	4
Figure 3. Plan view of As-built conditions .....	5
Figure 4. Plan view of 2003 overlain on As-built.....	6
Table 1. Summary of Results.....	10
Figure 5. Lyle Creek In-Place Profile .....	11
Figure 6. Lyle Creek Relocation Profile .....	12



## **1.0 BACKGROUND INFORMATION**

The background information for this report is referenced from previous monitoring reports conducted by Eco-Science, Inc. The following was excerpted from 2003 Eco-Science monitoring report:

The N.C. Wetlands Restoration Program (WRP) has developed a stream mitigations site within the northeastern Piedmont region of the Catawba River basin. As part of this effort, WRP has implemented detailed mitigation plans for the Lyle Creek Mitigation Site (hereafter referred to as the "Site"), an approximately 12.4-acre tract located along an unnamed tributary to Lyle Creek, approximately 3 miles west of the Catawba River. This region of the state is located within U.S. Geological Survey subbasin 03050101 (USGS 1974) (Figure 1). The Site is situated between U.S. Interstate Route 40 (I-40) and U.S. Route 70, approximately three miles west of the Catawba and Iredell County line.

The Site historically was utilized for agricultural hay production and livestock grazing. On-site streams are characterized as first- to second-order streams which have been degraded by past land uses, including vegetation clearing, dredging, straightening activities, and livestock trampling. Dredging and straightening appears to have been conducted to facilitate agricultural production and to expedite drainage from the Site. Straightening of the channel and channel instability from livestock trampling appears to have resulted in an entrenched stream channel with headcut migration occurring through the Site.

Stream mitigation activities have been designed to restore the stream features and functions similar to those exhibited by reference streams in the region. Site alterations designed to restore characteristic stream channel dimension, pattern, and profile include 1) installation of grade control/bank stabilization structures (cross vane weirs, J-hook vanes, and log vanes), excavation of bankfull benches, channel backfilling to design depth, bank stabilization through installation rootwad structures and erosion control matting, and excavation of channel on new location. Tree and shrub planting is expected to be conducted in the fall 2002 to facilitate the establishment of diagnostic natural communities. Vegetation planting has not been documented as part of this as-built report.

After implementation, the Site is expected to support 12.4 acres of riverine and adjacent slope forest encompassing 2,400 linear feet of restored stream channel (1,345 linear feet restored on new alignment and 1,055 linear feet restored in place). Stream enhancement/preservation activities will also be undertaken along approximately 800 linear feet of a secondary, unnamed tributary through bare root plantings and livestock exclusion.

### **1.1 Goals and Objective**

The goals and objectives of this project are as follows.


- 1.) Restore 2,400 linear feet of an unnamed tributary to Lyle Creek.
- 2.) Enhance the riparian area through planting native species
- 3.) Exclude cattle access to the unnamed tributary to Lyle Creek and 800 linear feet of a secondary unnamed tributary.

### **1.2 Project Location**

The Lyle Creek restoration project is located in Catawba County. From Interstate I-40 take Exit 138. Head south on Oxford School Rd for 0.1 mile. Turn right on Wyke Rd follow Wyke Rd for 1 mile. Turn Right on US-70, follow US-70 for 0.2 mile. The project approximately located 1000ft upstream of the US-70 Bridge over Lyle Creek.

### **1.3 Project Description**

The restoration of 2,400 linear feet of an unnamed tributary to Lyle Creek consists of relocating 1,345 linear feet of the existing channel away from a previously straightened ditch, stabilizing and enhancing 1,055 linear feet of channel in place and preserving through the use of fencing and re-vegetating 800 linear feet of a secondary unnamed tributary. Restoration included the incorporation of rock cross vane structures to establish grade and enhance habitat. The area was planted with native bare root seedlings and herbaceous cover to enhance the riparian areas and stabilize the streambanks. The relocated section included reconnecting a previously incised channel to its adjacent floodplain. The un-relocated section was not incised.



**NC STATE UNIVERSITY**

Department of Biological & Agricultural Engineering

Campus Box 7625  
Raleigh, NC 27606


**Project Location: Lyle Creek**  
Catawba County, North Carolina

EEP Monitoring Report



Dwn. By: MVH  
Ckd By: DAB  
Date: March 2004

**FIGURE 1**




**NC STATE UNIVERSITY**

Department of Biological & Agricultural Engineering

Campus Box 7625  
Raleigh, NC 27606

**Aerial Watershed Photo: Lyle Creek**  
Catawba County, North Carolina

EEP Monitoring Report



Dwn. By:

MVH

Ckd By:

DAB

Date:

March 2004

FIGURE

**2**

**Figure 3. Plan view of As-built conditions**

(To be attached)

showing all structures with station numbers

showing vegetation permanent plots

showing permanent cross-sections and benchmarks

showing vegetation plots

showing monitoring gauges

**Figure 4. Plan view of 2003 overlain on As-built**  
(To be attached)

## 2.0 YEAR 2003 RESULTS AND DISCUSSION

Year 2003 monitoring results are shown for Lyle Creek Monitoring.

### 2.1 Vegetation

The following describes the results of 2003 vegetation monitoring conducted at the Lyle Creek Restoration Site. Sampling and analysis methods used can be found in the appendix. Modifications to those methods are described below. Using the Draft Vegetation Monitoring Plan for NCWRP Riparian Buffer and Wetland Restoration Projects, 4 vegetation monitoring plots were randomly located within the riparian buffer of the Lyle Creek project. No reference area was studied; therefore no comparisons could be made to reference conditions.

#### 2.1.1 Results and Discussion

Vegetation within the riparian buffer of Lyle Creek is overall considered successful. The herbaceous layer was well established and diverse. *Panicum* spp. (deertongue and switchgrass) *Juncus* spp. (rushes) and *Carex* spp. (sedges) were most notably dominant throughout. Streambanks and floodplain areas were well covered with herbaceous plants. Shrub species, particularly those sprouting from livestakes are performing well. In the majority of areas where livestakes were planted, they are alive and growing. There is also a large number of naturally regeneration shrub species throughout the project area.

Overall number of planted trees was low. Extrapolation from the four plots resulted in an overall average of approximately 70 planted trees per acre for this restoration site. If natural regeneration is included with planted trees, the number is increased to an average of approximately 3600 trees per acre. This is not surprising given that there is a healthy mature overstory covering most of the project site which contributes greatly to the native seedbank. Both of these estimates are based on a diverse mix of species as well. Natural regeneration obviously plays an important role in the restoration of this site.

Wetland pockets throughout the riparian area also provide a diverse habitat for both plants and animals. These areas contained many different species of wetland plants and also serve as breeding grounds for numerous amphibians.

*Microstegium vimineum* was the only major invasive exotic plant located within these areas. In several plots it was the dominant herbaceous plant.

A slope are outside of the project easement has not re-vegetated since construction. It is believed that soil was borrowed from this area and re-vegetation efforts have failed. Although this area is outside of the project easement, rills have formed on the steeper sections of the slope. Sediment is washing into the channel from this area potentially degrading the habitat within the channel. This area should be stabilized with top soil, fertilizer and native herbaceous cover.

Recommendations include planting more trees if required for mitigation. Natural regeneration appears to be dominant, however, and should continue to be monitored for

growth habits. It is recommended to stake in areas where erosion is problematic in a few areas, particularly on outside meander bends. The invasive vegetation should also be monitored over time to determine if it will be a limiting factor in native plant growth in the future. No treatment is recommended at this time.

## **2.2 Morphology**

Restored channel dimension, pattern, profile and substrate were examined during the 2003 monitoring.

### **2.2.1 Results and Discussion**

#### ***New location Reach of Lyle Creek***

Channel profile along the relocation section of Lyle Creek has shown two areas of significant down-cutting. The first area is held by a structure at station 15+09 and works upstream 190 feet but has the potential to migrate another 200 foot until it reaches the next structure. The maximum head cut in this section is one foot. This head cut is possibly caused by a designed decrease in riffle slope from the structure at station 15+09. Another compounding factor may have been that the riffle features in this section were built with the highest bankfull area and the channel cross-sectional area is increasing due to significant bank erosion. The second area of down cutting is held by a structure at station 20+30 and works upstream 235 feet but has the potential to migrate another 300 foot until it reaches the next structure. The maximum head cut in this section is six inches. During the monitoring, the cause of this head cut was not identified. The number of defined riffles in the bedform has decreased from 20 in 2002, to 13 in 2003. The average riffle length has also decreased to 17 feet. This is also consistent with pebble count results which show a significant increase in fine particles since construction in the cross sections located within the head cut regions, and no significant change in the pebble count results from the other cross sections. Hardened riffle areas are not maintaining elevation throughout the relocated entire reach. The structures are maintaining the grade and in general look good. Eco-Science results were recalculated using NCSU techniques for consistency purposes. Data was examined but field identified features were retained.

Cross-sections 4 through 7 are located within the relocated reach. Cross-sections 4 and 7 show little change from as-built conditions. Cross sections 5 and 6 have increased in area due to the effects of incision from the above-mentioned headcut and channel widening due to bank erosion. See table 1 for summary results and the appendix for detailed data results.

Structures within this reach remain as constructed for the most part. A few of the cross vanes are showing signs of piping and have drops on the downstream side up to one foot. Several meander bends are eroding due to the combination of channel incision and lack of rootmass. These areas should be monitored closely in future monitoring.

Previous channel substrate measurements were conducted for regions instead of specific cross sections. Typical sections were selected and used as a standard for comparison purposes. Future monitoring will allow direct comparisons. Channel substrate in the riffle sections continue have very little change. The d50 decreased from 0.19mm to 0.11mm in



riffle 4, the d50 increased from 0.19mm to 0.33mm in riffle 5, and the d50 increased from 0.19mm to 0.34mm in riffle 7. There are areas of coarse sediments consisting of cobbles and the channel bed in the riffles are maintaining a mostly gravel substrate. The pool cross-section d50 has increases as well, from 0.09mm to 0.71mm, but not a significantly.

Channel pattern appears to have been maintained since construction. A few of the outside meander bends are experiencing slight migration through bank slumping but no excessive migration is evident and no shoot cut-offs are apparent.

### ***In Place Reach of Lyle Creek***

Channel profile along the in place section of has remained similar to as-built conditions. Two cross vane structures near the tie-in with the relocated reach have one-foot drops. These areas should be watched closely in future monitoring periods to ensure the structures do not fail. The remaining area appears to be functioning well. The previous survey of this area did not match up very well with the 2003 survey due to file conversion difficulties. Pools and riffles identified in the field matched up with 2003 survey data and profile or planform appeared to be located correctly so 2003 data will be used as base data for future monitoring periods.

Cross-sections 1 through 3 are located within the in-place reach. Cross-section 1 (pool) showed a decrease in cross sectional area, from 20.8 to 14.1 square feet. This is likely due to the building of the point bar and decrease in stream maximum depth. Stream depth likely decreased because of the lower floodplain constructed adjacent to the creek which lowered shear stress around the meander bend. Future monitoring will confirm these theories. Cross-sections 2 and 3 showed an increase in cross-sectional area, 9 square foot increase for both. This was due to the increase in channel width. The channel widened after construction. These areas have vegetated with a dense herbaceous cover. This vegetation has stabilized the stream banks and is likely going to narrow the channel as sediment becomes entrained. Future monitoring will validate this. See table 1 for summary results and the appendix for detailed data results.

Previous channel substrate measurements were conducted for regions instead of specific cross sections. Typical sections were selected and used as a standard for comparison purposes. Future monitoring will allow direct comparisons. Channel substrate cross-section 1, pool, increased in coarseness slightly since construction. Cross-section 2, riffle remained consistent to as-built conditions. Cross-section 3, riffle decreased in particle size on the upper end of the scale with d85 of 15.91 to 1.01mm. This are will be monitored in future monitoring periods to examine trends. Because the base data is not specifically from this location, no trends can be generated.

Channel pattern appears to have been maintained since construction. Channel banks are well vegetated and no areas of active erosion were evident.

**Table 1. Summary of Channel Conditions**

DIMENSION	Lyle Creek In-Place Reach Cross-section #1 Pool		Lyle Creek In-Place Reach Cross-section #2 Riffle		Lyle Creek In-Place Reach Cross-section #3 Riffle		Lyle Creek Relocation Reach Cross-section #4 Riffle		Lyle Creek Relocation Reach Cross-section #5 Riffle		Lyle Creek Relocation Reach Cross-section #6 Pool		Lyle Creek Relocation Reach Cross-section #7 Riffle	
	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003
	Bankfull Cross-sectional Area	20.8	14.1	16.5	28.1	15.6	26.1	17.5	17.8	16.9	20.7	19.6	27.3	15.2
Bankfull Width	16.3	16.5	11.8	18.6	13.2	16.2	10.8	10.8	10.7	13.9	12.8	13.5	11.2	11.2
Bankfull Mean Depth	1.3	0.9	1.4	1.5	1.2	1.6	1.6	1.6	1.6	1.5	1.5	2.0	1.4	1.4
Bankfull Max Depth	3.1	1.7	2.2	2.4	2.2	2.0	2.7	2.6	2.5	2.6	2.8	2.7	2.2	2.1

PATTERN	Lyle Creek As-built			Lyle Creek 2003			Lyle Creek (in place) As-built			Lyle Creek (in place) 2003		
	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median
Meander Wave Length	33	114	63	49	150	71	Not Reported			59	177	149
Radius of Curvature	14.9	37.5	22.4	16.7	38.5	20.9	Not Reported			13.3	48.6	30.9
Beltwidth	33	141	88	22	56	33	Not Reported			42	109	55

PROFILE	Lyle Creek As-built			Lyle Creek 2003			Lyle Creek (in place) As-built			Lyle Creek (in place) 2003		
	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median
Riffle Length	Not Reported			7	39	17	Not Reported			9	68	21
Riffle Slope	0.00%	3.64%	1.41%	0.56%	4.94%	1.71%	Not Reported			0.17%	4.74%	2.12%
Pool Length	14	64	27	9	41	23	Not Reported			11	49	27
Pool to Pool Spacing	22	161	54	27	176	46	Not Reported			28	140	66

SUBSTRATE	Lyle Creek Cross-section #1 Pool		Lyle Creek Cross-section #2 Riffle		Lyle Creek Cross-section #3 Riffle		Lyle Creek Cross-section #4 Riffle		Lyle Creek Cross-section #5 Riffle		Lyle Creek Cross-section #6 Pool		Lyle Creek Cross-section #7 Riffle	
	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003	As-built	2003
	D50	0.09	0.29	0.19	0.29	0.19	0.45	0.19	0.11	0.19	0.33	0.09	0.71	0.19
D85	0.52	0.76	15.91	13.33	15.91	1.01	15.91	3.11	15.91	17.52	0.52	31.78	15.91	3.00

VEGETATION	Quad 1 Lyle Creek		Quad 2 Lyle Creek		Quad 3 Lyle Creek		Quad 4 Lyle Creek	
	Observed	Planted	Observed	Planted	Observed	Planted	Observed	Planted
Tree Stratum (trees/acre)	720	0	520	40	600	240	12560	0
Shrub Stratum (% cover)	1.0	-	1.0	-	8.5	-	15.5	-
Herb Stratum (% cover)	62.5	-	184	-	171.5	-	152.2	-

# LYLE CREEK IN PLACE LONG PROFILE

Figure 5  
Lyle Creek Inplace Channel  
Catawba County, NC  
2003 Annual Monitoring Report  
Longitudinal Profile







Figure 5  
Lyle Creek New Channel  
Catawba County, NC  
2003 Annual Monitoring Report  
Longitudinal Profile



### 2.3 Areas of Concern

The following areas of concern should be monitored closely and considered for repair as suggested:

- **Easement Limits**
  - NCWRP should work with landowners to ensure easement limits are maintained and that cattle stay out of the riparian area.
- **Areas of major head cuts**
  - There are two areas of major head cut approximately 425 ft
  - The first area has a maximum head cut of one foot and is approximately 190 ft in length this head cut is located from station 13+20 to 15+10. There is still two hundred foot upstream until the next structure controlling grade
  - The second area has a maximum head cut of six inches and is approximately 235 ft in length this head cut is located from station 17+90 to 20+25. There is still three hundred foot upstream until the next structure controlling grade
- **Areas with bank slumping**
  - These areas should be planted heavily with live stakes to help establish root mass along the channel bank.
  - These areas should be monitored closely during upcoming site visits to determine if the problem is localized to more regional in scale.
  - Overland flow may need to be routed away from areas that show signs of severe bank erosion
- **Areas lacking stream features**
  - There are seven riffles that were constructed that do not exist in the longitudinal profile measured during the 2003 monitoring
  - Some of the riffles that have been removed as a result of the major head cuts in the two sections listed above
  - The remainder of the failed riffles have been transformed into runs or glides
- **Areas showing stream pattern adjustments**
  - There are two areas that have shown a significant change in stream pattern
  - The first section is from station 14+00 to 15+00 there is half of a meander wavelength that has been straightened into a long run this is the result of the head cut mentioned above
  - The second section is from station 20+50 to 22+20 there an entire meander wavelength that has been straightened into a run followed by a long step pool feature at the end of the project.
- **Vegetation Concerns**
  - Natural regeneration appears to be dominant and should continue to be monitored for growth habits.
  - Planting more trees if required for mitigation at this time the tree stems per acre is 70 but it appears that natural regeneration will be able to raise the tree stems per acre to the level for mitigation credit

- It is recommended to stake in areas where erosion is problematic in a few areas, particularly on outside meander bends
- The invasive vegetation requires no treatment at this time.
- Adjacent side slope should be stabilized to reduced sediment from washing into the creek.

## 2.4 Photo Log

2.4 Photo Log

**PHOTO PLOT 1**



**J-Hook**



**Looking Downstream**



**PHOTO PLOT 2**



**Looking Upstream**



**Looking Downstream**

**PHOTO PLOT 3**



**Looking Upstream**



**Looking Downstream**

**PHOTO PLOT 4**



**Looking Upstream**



**Looking Downstream**

**PHOTO PLOT 5**



**Cross-Vane Weir**



**Looking Downstream**

**PHOTO PLOT 6**



**Looking Upstream**



**Looking Downstream**

**PHOTO PLOT 7**



**Looking Upstream**



**Looking Down-valley**

**PHOTO PLOT 8**



**Looking Upstream**



**Looking Downstream**

**PHOTO PLOT 9**



**Looking Upstream**



**Looking Downstream**



**PHOTO PLOT 10**



**Looking Downstream**

**PHOTO PLOT 11**



**Looking Upstream**



**Looking Downstream**

**PHOTO PLOT 12**



**Looking Upstream**



**Looking Downstream**

## **Appendices**

### **A. Methods**

1. Vegetation
2. Morphology

### **B. Vegetation data**

1. Listed by plot
2. Species, number and age
3. Analysis of planted vs. natural recruitment

### **C. Morphology Data**

1. Cross-section data and plotted
2. Longitudinal data and plotted
3. Pebble count data and plotted
4. Pattern


<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#1
<b>Feature</b>	Pool
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
1.0	816.76		0.0	816.81	
5.9	815.11		4.3	815.44	
9.8	814.73		13.8	814.8	
18.0	814.53		17.0	814.86	
20.5	813.86		30.1	813.45	
26.8	813.32		34.7	813.1	
32.0	813.08		40.8	812.28	
35.8	812.99		43.2	811.8	
37.4	812.65		45.0	811.47	
38.8	812.65		46.5	811.17	
41.0	812.21		47.5	811.06	
42.6	811.78		48.3	811.22	
43.5	811.73		49.8	811.25	
44.0	811.29		50.2	811.82	
45.9	810.42		52.4	812.14	
48.4	809.70		54.2	814.46	
52.0	812.07		57.4	814.3	
53.9	813.08		66.4	813.48	
54.2	814.44		72.0	812.96	
58.0	814.24		80.8	812.94	
60.7	813.95		91.1	812.96	
75.8	813.81				
85.9	814.20				
98.8	814.63				
102.9	813.66				
109.8	811.29				
118.0	811.82				
125.9	814.82				
133.6	815.84				



Photo of Cross-Section #1 - Looking Downstream

	2002	2003
Area	20.79	14.07
Width	16.3	16.5
Mean Depth	1.3	0.9
Max Depth	3.1	1.7




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#1
<b>Feature</b>	Pool
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

Description	Material	Size (mm)	2002*			2003			
			Pool	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %
<b>Silt/Clay</b>	silt/clay	0.061	9	23.7%	23.7%	0	14	14.1%	14.1%
<b>Sand</b>	very fine sand	0.062	10	26.3%	50.0%	0	14	14.1%	28.3%
	fine sand	0.125	6	15.8%	65.8%	0	9	9.1%	37.4%
	medium sand	0.25	5	13.2%	78.9%	8	14	22.2%	59.6%
	course sand	0.50	5	13.2%	92.1%	15	9	24.2%	83.8%
	very course sand	1.0	0	0.0%	92.1%	9	1	10.1%	93.9%
<b>G r a v e l</b>	very fine gravel	2.0	2	5.3%	97.4%	1	1	2.0%	96.0%
	fine gravel	4.0	0	0.0%	97.4%	1	0	1.0%	97.0%
	fine gravel	5.7	0	0.0%	97.4%	0	0	0.0%	97.0%
	medium gravel	8.0	0	0.0%	97.4%	0	1	1.0%	98.0%
	medium gravel	11.3	0	0.0%	97.4%	0	0	0.0%	98.0%
	course gravel	16.0	0	0.0%	97.4%	0	0	0.0%	98.0%
	course gravel	22.6	0	0.0%	97.4%	0	1	1.0%	99.0%
	very course gravel	32	0	0.0%	97.4%	0	0	0.0%	99.0%
	very course gravel	45	1	2.6%	100.0%	0	0	0.0%	99.0%
	<b>Cobble</b>	small cobble	64	0	0.0%	100.0%	0	1	1.0%
medium cobble		90	0	0.0%	100.0%	0	0	0.0%	100.0%
large cobble		128	0	0.0%	100.0%	0	0	0.0%	100.0%
very large cobble		180	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>Boulder</b>	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>Bedrock</b>	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>TOTAL / %of whole count</b>						38	100.0%		
			38	100.0%		34	65	100.0%	

	d16	d35	d50	d85	d95
<b>2002*</b>	0.00	0.08	0.09	0.52	2.33
<b>2003</b>	0.07	0.16	0.29	0.76	2.29




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#2
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
-28.0	812.58		0.2	813.59	
-13.1	813.46		5.5	813.87	
5.0	814.63		17.9	812.88	
8.1	813.46		20.0	811.75	
12.3	813.14		21.8	810.53	
16.9	812.96		23.5	810.33	
18.0	812.87		25.6	810.34	
20.0	812.20		26.8	810.43	
21.2	810.97		28.5	810.52	
22.4	810.44		29.2	810.51	
25.5	810.94		30.1	810.67	
27.6	810.77		31.1	811.12	
28.7	811.18		31.6	811.43	
29.4	812.40		34.8	811.95	
31.0	812.81		37.0	813.25	
32.9	813.84		48.3	813.24	
34.0	814.04		55.1	813.37	
37.9	813.57		59.5	813.34	
40.9	813.34				
44.5	813.31				
59.0	813.31				



Photo of Cross-Section #2 - Looking Upstream

	2002	2003
Area	16.50	28.07
Width	11.8	18.6
Mean Depth	1.4	1.5
Max Depth	2.2	2.4




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#2
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

Description	Material	Size (mm)	2002*			2003				
			Riffle	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %	
Silt/Clay	silt/clay	0.061	9	15.0%	15.0%	0	14	13.7%	13.7%	
Sand	very fine sand	0.062	9	15.0%	30.0%	0	17	16.7%	30.4%	
	fine sand	0.125	12	20.0%	50.0%	4	7	10.8%	41.2%	
	medium sand	0.25	2	3.3%	53.3%	11	6	16.7%	57.8%	
	course sand	0.50	4	6.7%	60.0%	6	1	6.9%	64.7%	
	very course sand	1.0	0	0.0%	60.0%	8	0	7.8%	72.5%	
Gravel	very fine gravel	2.0	3	5.0%	65.0%	3	0	2.9%	75.5%	
	fine gravel	4.0	1	1.7%	66.7%	3	0	2.9%	78.4%	
	fine gravel	5.7	3	5.0%	71.7%	2	0	2.0%	80.4%	
	medium gravel	8.0	2	3.3%	75.0%	0	0	0.0%	80.4%	
	medium gravel	11.3	3	5.0%	80.0%	4	0	3.9%	84.3%	
	course gravel	16.0	6	10.0%	90.0%	3	0	2.9%	87.3%	
	course gravel	22.6	1	1.7%	91.7%	5	0	4.9%	92.2%	
	very course gravel	32	4	6.7%	98.3%	5	0	4.9%	97.1%	
	very course gravel	45	1	1.7%	100.0%	1	0	1.0%	98.0%	
Cobble	small cobble	64	0	0.0%	100.0%	2	0	2.0%	100.0%	
	medium cobble	90	0	0.0%	100.0%	0	0	0.0%	100.0%	
	large cobble	128	0	0.0%	100.0%	0	0	0.0%	100.0%	
	very large cobble	180	0	0.0%	100.0%	0	0	0.0%	100.0%	
Boulder	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%	
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%	
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%	
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%	
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%	
Bedrock	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%	
<b>TOTAL / %of whole count</b>						60	100.0%	57	45	100.0%

	d16	d35	d50	d85	d95
2002*	0.06	0.12	0.19	15.91	32.90
2003	0.07	0.13	0.29	13.33	33.80






<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#3
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
-48.4	812.54		0.0	812.35	
-34.4	812.15		9.1	812.21	
0.4	812.07		9.8	812.2	
6.1	812.20		11.3	810.44	
9.5	812.20		13.0	810.31	
11.5	811.94		15.4	810.04	
12.5	811.68		18.9	810.07	
13.5	811.29		21.6	810.25	
14.5	810.73		22.8	810.48	
15.8	810.09		24.4	810.79	
17.2	809.87		26.0	812.17	
19.2	810.22		28.5	812.78	
20.2	810.17		33.6	813.24	
21.2	811.03		36.8	813.17	
23.5	812.07		41.9	814.14	
25.5	812.84		53.2	815.21	
31.2	813.23				
34.5	813.36				
38.6	814.43				



Photo of Cross-Section #3 - Looking Downstream

	2002	2003
Area	15.60	26.08
Width	13.2	16.2
Mean Depth	1.2	1.6
Max Depth	2.2	2.0




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#3
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

Description	Material	Size (mm)	2002*			2003				
			Riffle	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %	
Silt/Clay	silt/clay	0.061	9	15.0%	15.0%	0	18	17.8%	17.8%	
Sand	very fine sand	0.062	9	15.0%	30.0%	2	12	13.9%	31.7%	
	fine sand	0.125	12	20.0%	50.0%	0	1	1.0%	32.7%	
	medium sand	0.25	2	3.3%	53.3%	7	3	9.9%	42.6%	
	course sand	0.50	4	6.7%	60.0%	25	12	36.6%	79.2%	
	very course sand	1.0	0	0.0%	60.0%	10	4	13.9%	93.1%	
Gravel	very fine gravel	2.0	3	5.0%	65.0%	3	0	3.0%	96.0%	
	fine gravel	4.0	1	1.7%	66.7%	1	0	1.0%	97.0%	
	fine gravel	5.7	3	5.0%	71.7%	0	0	0.0%	97.0%	
	medium gravel	8.0	2	3.3%	75.0%	0	0	0.0%	97.0%	
	medium gravel	11.3	3	5.0%	80.0%	3	0	3.0%	100.0%	
	course gravel	16.0	6	10.0%	90.0%	0	0	0.0%	100.0%	
	course gravel	22.6	1	1.7%	91.7%	0	0	0.0%	100.0%	
	very course gravel	32	4	6.7%	98.3%	0	0	0.0%	100.0%	
	very course gravel	45	1	1.7%	100.0%	0	0	0.0%	100.0%	
Cobble	small cobble	64	0	0.0%	100.0%	0	0	0.0%	100.0%	
	medium cobble	90	0	0.0%	100.0%	0	0	0.0%	100.0%	
	large cobble	128	0	0.0%	100.0%	0	0	0.0%	100.0%	
	very large cobble	180	0	0.0%	100.0%	0	0	0.0%	100.0%	
Boulder	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%	
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%	
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%	
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%	
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%	
Bedrock	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%	
<b>TOTAL / %of whole count</b>						60	100.0%	51	50	100.0%

	d16	d35	d50	d85	d95
2002*	0.06	0.12	0.19	15.91	32.90
2003	0.00	0.23	0.45	1.01	2.47




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#4
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
-90.4	808.12		0.0	805.16	
-85.6	806.93		9.6	805	
-80.5	806.16		11.0	804.98	
-58.4	805.61		11.5	804.87	
-34.6	805.65		12.4	804.43	
-26.5	804.84		12.9	804.06	
-9.6	804.84		14.4	802.97	
-2.4	805.48		15.3	803.07	
4.9	805.23		16.0	802.62	
8.5	805.40		17.7	802.29	
11.5	805.01		18.8	802.23	
12.4	804.59		19.6	802.51	
13.6	804.12		19.8	802.75	
14.5	803.57		20.5	803.13	
15.7	802.63		21.6	803.92	
17.8	802.50		22.4	804.35	
19.3	802.08		22.9	804.92	
20.6	802.29		24.9	804.89	
20.9	803.23		28.2	804.93	
22.1	804.03		37.0	804.69	
23.0	804.89				
28.7	805.14				
42.6	805.82				
67.6	808.21				



Photo of Cross-Section #4 - Looking Downstream

	2002	2003
Area	17.49	17.76
Width	10.8	10.8
Mean Depth	1.6	1.6
Max Depth	2.7	2.6




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#4
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

Description	Material	Size (mm)	2002*			2003			
			Riffle	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %
<b>Silt/Clay</b>	silt/clay	0.061	9	15.0%	15.0%	30	4	36.6%	36.6%
<b>Sand</b>	very fine sand	0.062	9	15.0%	30.0%	10	2	12.9%	49.5%
	fine sand	0.125	12	20.0%	50.0%	2	2	4.3%	53.8%
	medium sand	0.25	2	3.3%	53.3%	2	6	8.6%	62.4%
	course sand	0.50	4	6.7%	60.0%	9	8	18.3%	80.6%
	very course sand	1.0	0	0.0%	60.0%	0	1	1.1%	81.7%
<b>G r a v e l</b>	very fine gravel	2.0	3	5.0%	65.0%	0	2	2.2%	83.9%
	fine gravel	4.0	1	1.7%	66.7%	0	2	2.2%	86.0%
	fine gravel	5.7	3	5.0%	71.7%	0	3	3.2%	89.2%
	medium gravel	8.0	2	3.3%	75.0%	0	1	1.1%	90.3%
	medium gravel	11.3	3	5.0%	80.0%	0	0	0.0%	90.3%
	course gravel	16.0	6	10.0%	90.0%	0	0	0.0%	90.3%
	course gravel	22.6	1	1.7%	91.7%	0	4	4.3%	94.6%
	very course gravel	32	4	6.7%	98.3%	0	1	1.1%	95.7%
	very course gravel	45	1	1.7%	100.0%	0	2	2.2%	97.8%
	<b>Cobble</b>	small cobble	64	0	0.0%	100.0%	0	0	0.0%
medium cobble		90	0	0.0%	100.0%	0	1	1.1%	98.9%
large cobble		128	0	0.0%	100.0%	0	1	1.1%	100.0%
very large cobble		180	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>Boulder</b>	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>Bedrock</b>	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>TOTAL / %of whole count</b>						60	100.0%		
						53	40	100.0%	

	d16	d35	d50	d85	d95
<b>2002*</b>	0.06	0.12	0.19	15.91	32.90
<b>2003</b>	0.00	0.00	0.11	3.11	31.22




**Project Name** Lyle Creek  
**Cross Section** #5  
**Feature** Riffle  
**Date** 11/4/03  
**Crew** Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
-82.0	807.34		0.0	804.51	
-77.9	806.24		9.4	804.54	
-70.0	805.47		14.9	804.48	
-52.0	804.85		18.9	804.35	
-38.9	805.09		19.8	804.37	
-29.9	804.70		21.3	803.59	
-16.0	804.66		23.1	802.61	
1.1	804.46		23.8	802.09	
14.2	804.32		24.6	801.68	
22.1	804.27		26.3	801.95	
24.0	803.08		27.9	802.01	
25.7	802.07		28.6	802.14	
28.1	801.98		29.7	802.45	
28.4	801.78		30.9	803.27	
29.5	801.98		31.7	803.45	
30.0	802.31		33.7	804.45	
31.7	803.32		39.1	804.72	
33.0	804.56		45.9	805.1	
37.1	804.70				
39.0	804.85				
49.1	805.33				
59.2	809.16				



Photo of Cross-Section #5 - Looking Downstream

	2002	2003
Area	16.92	20.73
Width	10.7	13.9
Mean Depth	1.6	1.5
Max Depth	2.5	2.6




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#5
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

Description	Material	Size (mm)	2002*			2003			
			Riffle	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %
Silt/Clay	silt/clay	0.061	9	15.0%	15.0%	12	1	13.1%	13.1%
Sand	very fine sand	0.062	9	15.0%	30.0%	16	0	16.2%	29.3%
	fine sand	0.125	12	20.0%	50.0%	12	4	16.2%	45.5%
	medium sand	0.25	2	3.3%	53.3%	0	6	6.1%	51.5%
	course sand	0.50	4	6.7%	60.0%	0	6	6.1%	57.6%
	very course sand	1.0	0	0.0%	60.0%	0	3	3.0%	60.6%
Gravel	very fine gravel	2.0	3	5.0%	65.0%	0	1	1.0%	61.6%
	fine gravel	4.0	1	1.7%	66.7%	0	2	2.0%	63.6%
	fine gravel	5.7	3	5.0%	71.7%	0	6	6.1%	69.7%
	medium gravel	8.0	2	3.3%	75.0%	0	4	4.0%	73.7%
	medium gravel	11.3	3	5.0%	80.0%	0	4	4.0%	77.8%
	course gravel	16.0	6	10.0%	90.0%	0	9	9.1%	86.9%
	course gravel	22.6	1	1.7%	91.7%	0	7	7.1%	93.9%
	very course gravel	32	4	6.7%	98.3%	0	4	4.0%	98.0%
	very course gravel	45	1	1.7%	100.0%	0	2	2.0%	100.0%
Cobble	small cobble	64	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium cobble	90	0	0.0%	100.0%	0	0	0.0%	100.0%
	large cobble	128	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large cobble	180	0	0.0%	100.0%	0	0	0.0%	100.0%
Boulder	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%
Bedrock	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>TOTAL / % of whole count</b>			60	100.0%		40	59	100.0%	

	d16	d35	d50	d85	d95
2002*	0.06	0.12	0.19	15.91	32.90
2003	0.07	0.13	0.33	17.52	30.24




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#6
<b>Feature</b>	Pool
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
-81.3	807.30		0.2	804.51	
-77.3	806.22		12.9	804.29	
-69.3	805.48		17.5	804.17	
-51.1	804.83		20.5	804.18	
-38.2	805.09		22.6	804.06	
-29.2	804.70		23.4	803.35	
-15.1	804.61		24.5	803.17	
1.9	804.43		25.3	802.31	
13.9	804.13		27.0	802.03	
17.0	804.22		28.2	801.81	
23.8	804.35		29.2	801.86	
25.9	803.61		31.1	801.84	
26.9	803.22		33.5	801.48	
27.8	802.83		33.8	801.5	
29.9	802.26		34.7	801.92	
31.2	801.70		34.9	802.03	
33.3	801.39		36.1	803.14	
34.2	801.70		37.9	804.42	
35.8	803.13		40.6	804.78	
37.9	804.57		45.3	805.09	
42.9	805.13		49.5	805.51	
47.8	805.43				
58.9	806.57				



Photo of Cross-Section #6 - Looking Downstream

	2002	2003
<b>Area</b>	19.64	27.31
<b>Width</b>	12.8	13.5
<b>Mean Depth</b>	1.5	2.0
<b>Max Depth</b>	2.8	2.7




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#6
<b>Feature</b>	Pool
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

		2002*			2003				
Description	Material	Size (mm)	Pool	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %
Silt/Clay	silt/clay	0.061	9	22.5%	22.5%	13	0	13.0%	13.0%
Sand	very fine sand	0.062	10	25.0%	47.5%	24	1	25.0%	38.0%
	fine sand	0.125	6	15.0%	62.5%	2	0	2.0%	40.0%
	medium sand	0.25	5	12.5%	75.0%	1	1	2.0%	42.0%
	course sand	0.50	5	12.5%	87.5%	0	9	9.0%	51.0%
	very course sand	1.0	0	0.0%	87.5%	0	4	4.0%	55.0%
Gravel	very fine gravel	2.0	2	5.0%	92.5%	0	3	3.0%	58.0%
	fine gravel	4.0	0	0.0%	92.5%	0	1	1.0%	59.0%
	fine gravel	5.7	0	0.0%	92.5%	0	1	1.0%	60.0%
	medium gravel	8.0	0	0.0%	92.5%	0	0	0.0%	60.0%
	medium gravel	11.3	2	5.0%	97.5%	0	6	6.0%	66.0%
	course gravel	16.0	0	0.0%	97.5%	0	4	4.0%	70.0%
	course gravel	22.6	0	0.0%	97.5%	0	8	8.0%	78.0%
	very course gravel	32	0	0.0%	97.5%	0	15	15.0%	93.0%
	very course gravel	45	1	2.5%	100.0%	0	7	7.0%	100.0%
Cobble	small cobble	64	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium cobble	90	0	0.0%	100.0%	0	0	0.0%	100.0%
	large cobble	128	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large cobble	180	0	0.0%	100.0%	0	0	0.0%	100.0%
Boulder	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%
Bedrock	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>TOTAL / % of whole count</b>						40	60	100.0%	

	d16	d35	d50	d85	d95
2002*	0.00	0.08	0.11	0.65	11.65
2003	0.07	0.09	0.71	31.78	43.07






<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#7
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2002 As Build Survey			2003 2003 Survey		
Station	Elevation	Notes	Station	Elevation	Notes
5.4	803.18		0.0	803.143	
13.5	803.35		8.6	803.223	
15.6	803.24		15.1	803.393	
16.5	802.97		16.5	802.913	
18.6	801.89		17.5	801.99	
19.1	801.03		18.1	801.383	
19.5	800.82		18.2	801.123	
21.6	801.20		19.0	801.033	
23.4	801.09		20.4	800.953	
24.2	801.14		22.3	801.073	
25.1	801.68		24.2	801.283	
26.8	802.49		25.1	801.443	
27.6	803.02		25.6	801.773	
36.2	802.97		26.7	802.653	
41.8	803.51		27.9	803.053	
53.7	804.31		29.8	803.123	
68.7	804.42		36.2	803.003	
76.9	804.47		42.8	803.643	
86.7	805.39				



Photo of Cross-Section #7 - Looking Downstream

	2002	2003
<b>Area</b>	15.24	16.20
<b>Width</b>	11.2	11.2
<b>Mean Depth</b>	1.4	1.4
<b>Max Depth</b>	2.2	2.1




<b>Project Name</b>	Lyle Creek
<b>Cross Section</b>	#7
<b>Feature</b>	Riffle
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

\* 2002 pebble count is a typical riffle sections used as baseline information.

Description	Material	Size (mm)	2002*			2003			
			Riffle	%	Cum %	Riffle - Bed	Riffle - Bank	%	Cum %
Silt/Clay	silt/clay	0.061	9	15.0%	15.0%	0	11	11.0%	11.0%
Sand	very fine sand	0.062	9	15.0%	30.0%	3	16	19.0%	30.0%
	fine sand	0.125	12	20.0%	50.0%	6	6	12.0%	42.0%
	medium sand	0.25	2	3.3%	53.3%	10	0	10.0%	52.0%
	course sand	0.50	4	6.7%	60.0%	25	0	25.0%	77.0%
	very course sand	1.0	0	0.0%	60.0%	5	0	5.0%	82.0%
Gravel	very fine gravel	2.0	3	5.0%	65.0%	2	0	2.0%	84.0%
	fine gravel	4.0	1	1.7%	66.7%	1	0	1.0%	85.0%
	fine gravel	5.7	3	5.0%	71.7%	1	0	1.0%	86.0%
	medium gravel	8.0	2	3.3%	75.0%	1	0	1.0%	87.0%
	medium gravel	11.3	3	5.0%	80.0%	0	0	0.0%	87.0%
	course gravel	16.0	6	10.0%	90.0%	5	0	5.0%	92.0%
	course gravel	22.6	1	1.7%	91.7%	4	0	4.0%	96.0%
	very course gravel	32	4	6.7%	98.3%	4	0	4.0%	100.0%
very course gravel	45	1	1.7%	100.0%	0	0	0.0%	100.0%	
Cobble	small cobble	64	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium cobble	90	0	0.0%	100.0%	0	0	0.0%	100.0%
	large cobble	128	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large cobble	180	0	0.0%	100.0%	0	0	0.0%	100.0%
Boulder	small boulder	256	0	0.0%	100.0%	0	0	0.0%	100.0%
	small boulder	362	0	0.0%	100.0%	0	0	0.0%	100.0%
	medium boulder	512	0	0.0%	100.0%	0	0	0.0%	100.0%
	large boulder	1024	0	0.0%	100.0%	0	0	0.0%	100.0%
	very large boulder	2049	0	0.0%	100.0%	0	0	0.0%	100.0%
Bedrock	bedrock	40096	0	0.0%	100.0%	0	0	0.0%	100.0%
<b>TOTAL / %of whole count</b>						60	100.0%		
			60	100.0%		67	33	100.0%	

	d16	d35	d50	d85	d95
2002*	0.06	0.12	0.19	15.91	32.90
2003	0.07	0.13	0.34	3.00	25.30



<b>Project Name</b>	Little Pine and Brush Creeks
<b>Task</b>	Feature Slope and Length Calculations
<b>Date</b>	9/30/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

2003 Data

**Little Pine**

Riffle	Station	Change	Bed elevation	Water elevation	change	slope
	85		95.48	96.1		
	132	47	94.73	95.8	0.3	0.64%
	204		95.07	95.55		
	222	18	93.91	95.07	0.48	2.67%
	266		94.12	95.01		
	308	42	93.86	94.74	0.27	0.64%
	390		93.37	94.33		
	486	96	92.02	93.06	1.27	1.32%
	574		92.23	93.14		
	601	27	91.68	92.55	0.59	2.19%
	728		91.8	92.48		
	759	31	90.83	91.7	0.78	2.52%

Pool	length	p-p spacing	min	max	median
18.75					
85.85	67.1		18.0	96.0	36.5
222			0.64%	2.67%	1.75%
266	44	191.7	44.0	121.0	77.6
330			116	192	162
390	60	116			
486					
574	88	170			
601					
722	121	131.5			
773					
873	100	161.5			

**Brush Creek**

Riffle	Station	Change	Water elevation	change	slope
	0		92.68		
	114	114	91.81	0.87	0.76%
	408		91.78		
	559	151	91.59	0.19	0.13%
	736		91.47		
	796	60	90.88	0.59	0.98%
	935		90.77		
	1281	346	89.71	1.06	0.31%
	1591		89.76		
	1682	91	89.52	0.24	0.26%
	1898		89.3		
	1951	53	88.84	0.46	0.87%

Pool	length	p-p spacing	min	max	median
114					
408	294		53.0	346.0	102.5
557			0.13%	0.98%	0.53%
736	179	385.5	179.0	311.0	226.0
1280			274	789	370
1591	311	789			
1682					
1898	216	354.5			
1951					
2177	226	274			

PROFILE	Little Pine As-built - 2001			Brush Creek As-built - 2001			Little Pine 2003			Brush Creek 2003		
	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median	Minimum	Maximum	Median
Riffle Length	6.1	46.8	18.4	20	417	32.9	18	96	36.5	53	346	102.5
Riffle Slope	1.17%	2.79%	1.61%	0.24%	1.65%	1.35%	0.64%	2.67%	1.75%	0.13%	0.98%	0.53%
Pool Length	34.1	111.6	44.5	51	348	187	44	121	77.55	179	311	226
Pool to Pool Spacing	51	150.3	63.7	53	966	359	116	191.7	161.5	274	789	370

<b>Project Name</b>	Lyle Creek
<b>Task</b>	Channel Pattern Measurements
<b>Date</b>	11/4/03
<b>Crew</b>	Shaffer, Bidelspach, Clinton

Lyle Creek In Place		
Radius of Curvature	Meander Wavelength	Channel Beltwidth
13.3	58.9	109.2
30.8	105.5	42.0
24.3	107.1	45.7
21.4	123.2	45.9
42.8	124.2	46.4
31.0	148.8	51.3
24.9	152.4	57.9
32.9	152.5	60.1
31.8	155.8	61.8
38.5	160.8	80.3
21.2	177.1	50.0
22.5		
48.6		
37.2		
29.1		
40.4		
13.3	58.9	42.0
48.6	177.1	109.2
30.9	148.8	51.3

*min*  
*max*  
*median*

Lyle Creek		
Radius of Curvature	Meander Wavelength	Channel Beltwidth
16.7	48.8	21.7
16.9	53.8	22.0
17.2	58.9	22.3
17.7	60.2	24.4
18.1	61.7	25.4
18.3	62.0	27.1
18.9	62.3	30.3
19.2	62.9	31.0
20.4	63.6	31.3
20.4	64.7	32.9
20.7	70.0	33.0
21.1	71.4	33.1
21.1	72.2	34.4
22.6	72.3	35.7
22.6	76.0	37.7
23.4	76.7	38.0
23.6	89.1	40.5
24.2	90.0	40.6
25.0	90.2	42.1
27.5	101.0	42.4
32.4	118.2	49.2
38.5	150.4	55.7
16.7	48.8	21.7
38.5	150.4	55.7
20.9	70.7	33.0

Lyle Creek Stream Restoration  
 Catawba County, NC

### Quad 1

#### Tree Stratum

<u>Species</u>	<u>Height (cm)</u>	<u>Diameter (mm)</u>	<u>Radius (mm)</u>	<u>Σ X-sec. (mm<sup>2</sup>)</u>	<u>Rel. x-sec (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>	<u>Average</u>
<i>Liriodendron tulipifera</i>	9	1	0.5	0.8	95.8	17	94.4	1	95.13889
	9	1	0.5	0.8					
	4	0.5	0.25	0.2					
	4	0.5	0.25	0.2					
	4	0.5	0.25	0.2					
	4	0.5	0.25	0.2					
	4	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
	3	0.5	0.25	0.2					
<b>Total</b>				<b>4.5</b>					
<i>Betula nigra</i>	2	0.5	0.25	0.2	4.2	1	5.6	2	4.861111
<b>Total</b>				<b>0.2</b>					
<b>Overall Total</b>				<b>4.7</b>	<b>100.0</b>	<b>18.0</b>	<b>100.0</b>		<b>100</b>
Total Trees per acre						720			
Planted trees per acre						0			

#### Shrub Stratum

<u>Species</u>	<u>Cover (%)</u>	<u>Rel. cover (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>
<i>Alnus serrulata</i>	0.5	50	1	50	1
Unknown	0.5	50	1	50	1

#### Herb Stratum

<u>Species</u>	<u>Cover (%)</u>	<u>Rel. cover (%)</u>	<u>Rank (Importance)</u>
<i>Panicum sp.</i>	40	64.0	1
<i>Paspalum sp.</i>	0.5	0.8	5
<i>Eupatorium capillifolium</i>	0.5	0.8	5
<i>Hystrix patula</i>	0.5	0.8	5
<i>Trifolium sp.</i>	5	8.0	3
<i>Festuca sp.</i>	1	1.6	4
<i>Microstegium vimineum</i>	15	24.0	2
<b>Total</b>	<b>62.5</b>	<b>100.0</b>	

Lyle Creek Stream Restoration  
Catawba County, NC

## Quad 2

### Tree Stratum

<u>Species</u>	<u>Height (cm)</u>	<u>Diameter (mm)</u>	<u>Radius (mm)</u>	<u>Σ X-sec. (mm<sup>2</sup>)</u>	<u>Rel. x-sec (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>	<u>Average</u>
<i>Liriodendron tulipifera</i>	5	1	0.5	0.8	0.0	9	69.2	1	34.62038
	5	1	0.5	0.8					
	5	1	0.5	0.8					
	5	1	0.5	0.8					
	5	1	0.5	0.8					
	5	1	0.5	0.8					
	5	1	0.5	0.8					
	5	1	0.5	0.8					
	5	1	0.5	0.8					
<b>Total</b>				<b>7.1</b>					
<i>Betula nigra</i>	73	3			100.0	4	30.8	2	65.37962
	3000	430							
	3000	280							
	3000	300	150	70685.8					
<b>Total</b>				<b>70685.8</b>					
<b>Overall Total</b>				<b>70692.9</b>	<b>100.0</b>	<b>13.0</b>	<b>100.0</b>		<b>100</b>
Total Trees per acre						520			
Planted trees per acre						40			

### Shrub Stratum

<u>Species</u>	<u>Cover (%)</u>	<u>Rel. cover (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>
<i>Salix nigra</i>	0.5	50	4	0.7	2
<i>Cornus amomum</i>	0.5	50	6	1.0	1

### Herb Stratum

<u>Species</u>	<u>Cover (%)</u>	<u>Rel. cover (%)</u>	<u>Rank (Importance)</u>
<i>Festuca sp.</i>	75	40.8	2
<i>Juncus sp.</i>	5	2.7	4
<i>Echinochloa crusgalli</i>	15	8.2	3
<i>Eupatorium sp.</i>	5	2.7	4
<i>Panicum virgatum</i>	2	1.1	5
<i>Aster sp.</i>	2	1.1	5
<i>Microstegium</i>	80	43.5	1
<b>Total</b>	<b>184</b>	<b>100.0</b>	

### Quad 3

#### Tree Stratum

<u>Species</u>	<u>Height (cm)</u>	<u>Diameter (mm)</u>	<u>Radius (mm)</u>	<u>Σ X-sec. (mm<sup>2</sup>)</u>	<u>Rel. x-sec (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>	<u>Average</u>
<i>Liriodendron tulipifera</i>	3000	1500	750	1767145.9	100.0	7	46.7	1	73.33174
	3000	550	275	237582.9					
	3000	550	275	237582.9					
	3000	42	21	1385.4					
	9	0.5	0.25	0.2					
	14	2	1	3.1					
	10	1	0.5	0.8					
<b>Total</b>			<b>1322.75</b>	<b>2243701.3</b>					
<i>Platanus occidentalis</i>	38	4	2	12.6	0.0				
	21	2	1	3.1		2	13.3	2	13.33333
<b>Total</b>			<b>3</b>	<b>15.7</b>					
<i>Quercus shumardii</i>	55	7	3.5	38.5	0.0	1	6.7	3	3.334191
<b>Total</b>		7	<b>3.5</b>	<b>38.5</b>					
<i>Morus rubra</i>	37	2	1	3.1	0.0	1	6.7	3	3.333403
<b>Total</b>			<b>1</b>	<b>3.1</b>					
<i>Celtis occidentalis</i>	42	3	1.5	7.1	0.0	2	13.3	2	6.666894
	29	2	1	3.1					
<b>Total</b>		<b>5</b>	<b>2.5</b>	<b>10.2</b>					
<i>Cornus florida</i>	18	1	0.5	0.8	0.0	1	6.7	3	3.333351
<b>Total</b>			<b>0.5</b>	<b>0.8</b>					
<i>Carpinus caroliniana</i>	21	2	1	3.1	0.0	1	6.7	3	3.333403
<b>Total</b>			<b>1</b>	<b>3.1</b>					
<b>Overall Total</b>				<b>2243772.8</b>	<b>100.0</b>	<b>15.0</b>	<b>86.7</b>		

Total Trees per acre  
Planted trees per acre

600  
240

#### Shrub Stratum

<u>Species</u>	<u>Cover (%)</u>	<u>Rel. cover (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>
<i>Salix nigra</i>	4	47.1	36	60	1
<i>Sambucus canadensis</i>	0.5	5.9	3	5	3
<i>Cornus amomum</i>	4	47.1	21	35	2

#### Herb Stratum

<u>Species</u>	<u>Cover (%)</u>	<u>Rel. cover (%)</u>	<u>Rank (Importance)</u>
<i>Aster sp.</i>	15	8.7	3
<i>Microstegium</i>	90	52.5	1
<i>Carex sp.</i>	15	8.7	3
<i>Juncus sp.</i>	15	8.7	3
<i>Polygonum sp.</i>	25	14.6	2
<i>Viola sp.</i>	1	0.6	5
<i>Trifolium sp.</i>	0.5	0.3	6
<i>Verbesina occidentalis</i>	10	5.8	4
<b>Total</b>	<b>171.5</b>	<b>100.0</b>	

Quad 4

Tree Stratum

<u>Species</u>	<u>Height (cm)</u>	<u>Diameter (mm)</u>	<u>Radius (mm)</u>	<u>Σ X-sec. (mm<sup>2</sup>)</u>	<u>Rel. x-sec (%)</u>	<u>Density</u>	<u>Rel. Density (%)</u>	<u>Rank (Importance)</u>	<u>Average</u>
<b>Total</b>									
<i>Liquidambar styraciflua</i>	10	1	0.5	0.8	25.7	59	18.8	3	22.22099
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	10	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	15	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	22	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
	7	1	0.5	0.8					
<b>Total</b>			<b>29.5</b>	<b>46.3</b>	<b>25.7</b>				









