



**REEDY BRANCH
FINAL MONITORING REPORT
YEAR 2 OF 5
2006**

EEP Project # 301
Alamance County, North Carolina

Original Design Firm:
ECOLOGIC ASSOCIATES PC
218-4 Swing Road
Greensboro, NC 27409

Submitted to:



NCDENR-EEP
1652 Mail Service Center
Raleigh, NC 27699

Monitoring Firm:



1025 Wade Avenue
Raleigh, North Carolina 27605
Phone: (919)789-9977
Project Manager:
Phillip Todd
ptodd@sepiengineering.com

Executive Summary

The North Carolina Ecosystem Enhancement Program (EEP) restored approximately 3,150 linear feet of stream along Reedy Branch. This project is located in Alamance County, NC. This segment of Reedy Branch flows through a moderately dense wooded section surrounded by pasture areas. Prior to restoration, cattle and horses had unlimited access to the stream channels which created areas of severe bank erosion and loss of vegetation. Since the restoration has been complete, the livestock have been fenced out of the stream with the exception of a few crossings that are used throughout the year to move the cattle between pastures.

There were several goals for this stream and buffer restoration project. Goals of the stream project included: reducing the bank erosion; reducing nutrient runoff on the site; stabilizing stream channel banks by planting vegetation; and, helping the stream reach its equilibrium through the proper design ratios for dimension, pattern, and profile.

This report documents the data collected for Year 2 monitoring. The data includes geomorphic and vegetative components. The geomorphic data collected includes: longitudinal profiles, cross-sections, pebble counts, and photo points along the segment of restored stream. The vegetation data collected includes: stem count species and numbers for all of the vegetative plots throughout the project. The geomorphic data collected for Year 2 was compared to previous data collected in Year 1 by overlays of graphs for the longitudinal and cross-section surveys.

Three new cross section locations were established in Year 2 monitoring adding to the three existing cross sections from Year 1. The three cross-sections overlaid between the two years showed no major changes in dimensions. The longitudinal profiles between the two years were inconclusive. No conclusions were made due to discrepancies in stationing between years. This uncertainty in the location of some monitoring features and benchmarks has now been eliminated and therefore subsequent annual comparisons will be fully consistent with the data collection in this report. Some of the structures, as noted in the report, need to be monitored closely over the next year and may need to be repaired.

TABLE OF CONTENTS

1.-1	PROJECT BACKGROUND.....	1
	1.1 Project Location	1
	1.2 Project Setting	1
	1.3 Project Objectives.....	1
	1.4 History and Background.....	3
2.-1	PROJECT MONITORING METHODOLOGY	5
	2.1 Vegetation Methodology	5
	2.2 Stream Methodology.....	5
	2.2.1 Longitudinal Profile.....	5
	2.2.2 Permanent Cross-Sections	5
	2.2.3 Pebble Counts.....	6
	2.3 Photo Documentation.....	6
3.-1	PROJECT CONDITIONS AND RESULTS.....	6
	3.1 Vegetation.....	6
	3.1.1 Soils Data.....	6
	3.1.2 Vegetative Problem Area Plan View	6
	3.1.3 Stem Counts.....	7
	3.2 Stream.....	7
	3.2.1 Longitudinal Profile.....	7
	3.2.2 Permanent Cross-Sections	7
	3.2.3 Pebble Counts.....	7
	3.3 Photo Documentation.....	7
	3.4 Problem Areas.....	8
4.-1	OVERALL CONCLUSION FOR YEAR 2 MONITORING	8
	REFERENCES	9
	TABLES	
	Table I Project Mitigation Structure and Objectives Table	1
	Table II Project Activity and Reporting History	3
	Table III Project Contract Table.....	4
	Table IV Project Background Table.....	4
	Table V Preliminary Soil Data	6
	Table VI Vegetative Problem Areas.....	6
	Table VII Stem counts for each species arranged by plot	8
	Table VIII Verification of Bankfull Events.....	Appendix B3
	Table IX BEHI and Sediment Export Estimates (not included in this year's data)	
	Table X Stream Problem Area	Appendix B3
	Table XI Categorical Stream Feature Visual Stability Assessment.....	Appendix B3
	Table XII Baseline Morphology and Hydraulic Summary	Appendix B3
	Table XIII. Morphology and Hydraulic Monitoring Summary	Appendix B3
	FIGURES	
	Figure 1: Vicinity Map	2

APPENDICES

Appendix A

Appendix A1: Photolog – Vegetation Problem Areas	A1
Appendix A2: Photolog – Vegetation Plots	A2
Appendix A3: Vegetation Data Tables	A3

Appendix B

Appendix B1: Photolog – Stream Problem Areas	B1
Appendix B2: Photolog – Cross Sections and Photo Points ..B2	B2
Appendix B3: Stream Data Tables	B3
Appendix B4: Stream Cross Sections	B4
Appendix B5: Stream Longitudinal Profile	B5
Appendix B6: Stream Pebble Counts	B6

Appendix C: Plan View Sheets for Vegetation and Geomorphic Monitoring Year 2

1.0 PROJECT BACKGROUND

1.1 Project Location

This project is near Snow Camp, North Carolina in south-central Alamance County. To reach the site from Raleigh, go west on US 64 to Siler City. In Siler City, go north on Martin Luther King Boulevard; the North Carolina Atlas and Gazetteer (DeLorme 1997) labels the road as Snow Camp Road. Continue north toward the community of Snow Camp (approximately 12 miles). Before entering Snow Camp, take a right on SR 2358 (Workman Rd). Continue on Workman Road approximately 1 mile then take a right on Quakenbush Road. Continue on Quakenbush Road for approximately 1½ miles to a small road crossing over Reedy Branch. The road crossing is at the downstream end of the project. Reedy Branch extends upstream (south) of Quakenbush Road. Figure 1 shows the location of Reedy Branch.

1.2 Project Setting

The project is located entirely on property owned by Sam and Deborah Kiser. Cattle pasture makes up most of the Kiser Farm surrounding the restoration site. The restored stream is enclosed in a moderately dense wooded area and contains large bedrock outcrops as well other sporadic occurrences of bedrock throughout the reach.



Overall, Reedy Branch covers approximately 3155 linear feet of stream. It also contains significant bends as it flows through its valley length. These bends combine for a total valley length of approximately 2,550 feet.

1.3 Project Objectives

The goal of this stream restoration project is to improve the water quality in the Cape Fear River Basin. Reedy Branch is a typical stream within this and surrounding watersheds, exhibiting instability and degradation in response to current and historical practices with land use. Nutrient input should decrease with the establishment of a riparian buffer and fencing the cattle out of the streams. The buffer will also provide shade to the stream which will encourage wildlife diversity in the area (both aquatic and non-aquatic).

Table I. Project Mitigation Structure and Objectives Table				
Reedy Branch/EEP Project Number 301				
Project Segment or Reach ID	Mitigation Type	Approach	Linear Footage or Acreage Stationing	Comment
Reedy Branch	*	*	3,155 linear feet	*

“*” denotes raw data being acquired by EEP and will be included in the 2007 monitoring report for the site



Ecosystem Enhancement PROGRAM


EEP Monitoring Year 2
Reedy Branch

Figure 1
Alamance County, North Carolina


REEDY BRANCH

QUAKENBUSH RD.

ALAMANCE
COUNTY



PROJECT SITE



REEDY BRANCH
FIGURE 2

SEPI
ENGINEERING GROUP
1025 WADE AVENUE
RALEIGH, NC 27605
TEL: 919-789-9977 FAX: 789-9591



LOCATION:	
REEDY BRANCH STREAM MONITORING - YEAR 2	
PROJ #:	COUNTY:
301	ALAMANCE
PREPARED BY:	
WDY	
CHECKED BY:	DATE:
ATW	11/17/06

1.4 History and Background

Historically, cattle had access to all parts of the stream. This resulted in various negative effects to the stream in regards to overall structure, aquatic and non-aquatic habitat, and vegetation (See Monitoring Year 1 Report for more specific details).

Since completion of this project and fencing in of the floodplain and riparian buffer, cattle are no longer able to freely access the stream. There are two stable, stream crossings that the landowner uses to move the cattle between pastures.

Table II. Project Activity and Reporting History			
Reedy Branch/EEP Project Number 301			
Activity or Report	Scheduled Completion	Data Collection Complete	Actual Completion or Delivery
Restoration Plan			*
Final Design - 90%			*
Construction			November 1, 2003
Temporary S&E mix applied to entire project area			November 1, 2003
Permanent seed mix applied to entire project area			December 1, 2003
Vegetative Planting			January 1, 2003
Mitigation Plan/ As-built (Year 0 Monitoring - baseline)		February 2005	August 1, 2005
Repair Work			Fall 2004
Repair Work			May 1, 2005
Year 1 monitoring		May 2005	August 2005
Year 2 monitoring		June 2006	December 2006
Year 3 monitoring	December 2007		
Year 4 monitoring	December 2008		
Year 5 monitoring	December 2009		
Year 5+ monitoring			

“*” denotes raw data being acquired by EEP and will be included in the 2007 monitoring report for the site

Table III. Project Contract Table	
Reedy Branch/EEP Project Number 301	
Designer Mark Taylor	EcoLogic 218-4 Swing Road Greensboro, NC 27409 336-335-1108
Construction Contractor	Phillips and Jordan, Inc. 8245 Chapel Hill Road Cary, NC 27513 919-388-4222
Planting Contractor	*
Seeding Contractor	*
Monitoring Performers Amanda Todd	SEPI Engineering Group 1025 Wade Avenue Raleigh, NC 27605 919-789-9977
Stream Monitoring POC	Amanda Todd (919) 789-9977
Vegetation Monitoring POC	Phillip Todd (919) 789-9977
Wetland Monitoring POC	N/A

“*” denotes raw data being acquired by EEP and will be included in the 2007 monitoring report for the site

Table IV. Project Background Table	
Reedy Branch/EEP Project Number 301	
Project County	Alamance
Drainage Area	1.6 square miles
Drainage impervious cover estimate (%)	10%
Stream Order	Second
Physiographic Region	Piedmont
Ecoregion	Carolina Slate Belt
Rosgen Classification of As-built	C5
Cowardin Classification	N/A
Dominant soil types	Herndon
Reference site ID	Unknown
USGS HUC for Project and Reference	03030002 Haw River
NCDWQ Sub-basin for Project and Reference	03-06-04
NCDWQ classification for Project and Reference	*
Any portion of any project segment 303d listed?	No
Any portion of any project segment upstream of a 303d listed segment?	No
Reasons for 303d listing or stressor	N/A
% of project easement fenced	100%

“*” denotes raw data being acquired by EEP and will be included in the 2007 monitoring report for the site

2.0 PROJECT MONITORING METHODOLOGY

2.1 Vegetation Methodology

The following methodology was used for the stem count. The configuration of the vegetation plots were marked out with tape to measure 10 meters by 10 meters (or equivalent to 100 square meters) depending on buffer width. The planted material in the plot was marked with flagging. The targeted vegetation was then identified by species, and the number of each species was recorded in a field book.

2.2 Stream Methodology

The project monitoring for the stream channel included a longitudinal survey, cross-sectional surveys, pebble counts, and photo documentation. These measurements were taken along the entire length of the reach. The stationing was based on thalweg. Methodology for each portion of the stream monitoring is described in detail below.

2.2.1 Longitudinal Profile

The longitudinal profile of the restored stream was surveyed. The heads of features, such as riffles, runs, pools, maximum pool, and glides, were surveyed in the longitudinal profile. At each head of feature, the thalweg, water surface, edge of water, left and right bankfull, and left and right top of bank were surveyed. The average water-surface slope for each feature, pool length, and pool to pool spacing were calculated from this survey. The surveyed features also assisted in drawing out the plan view of the restored stream. Stream pattern data (i.e., meander length, radius of curvature, belt width, and sinuosity) were also measured from the plan view.

The pools that were constructed downstream of the cross vanes were surveyed in the longitudinal profile since they were included in Year 1 monitoring as well. These pools were grouped in to calculate the pool-to-pool spacing and the pool-to-pool spacing to bankfull width ratio calculations. The longitudinal profile for Year 2 was overlain on Year 1 data to note any changes.

2.2.2 Permanent Cross Sections

Six permanent cross sections (four riffles and two pools) were surveyed at Reedy Branch during Year 2 monitoring. Originally, there were only three permanent cross sections established over the total length of the project (two riffles and one pool). Given that the total length of the project exceeded 3000 linear feet, three additional cross sections were established during Year 2 monitoring (two riffles and one pool). The beginning and end of each previously established permanent cross section was originally marked with a metal rebar stake covered with an orange plastic cap. These original stakes were well marked and easy to find. Even so, during Year 2 monitoring, metal conduit stakes were provided on all six cross sections as required by the latest EEP protocol. Cross sections were located and installed perpendicular to the stream flow. The survey noted all changes in slopes, tops of both banks, left and right bankfull, edges of water, thalweg and water surface. The bankfull cross sectional areas were calculated for each cross section based on the drainage area and checked against the design parameters. The cross sections were plotted, and Year 1 monitoring data was overlain on top of Year 2 for comparison. The bankfull mean depth, cross-sectional area, width-to-depth ratios and entrenchment ratios were also compared from Year 1 to Year 2.

2.2.3 Pebble Counts

A modified Wolman pebble count (Rosgen 1993) consisting of 100 samples was taken at each permanent cross section. The cumulative percent was graphed and the D50 and D84 were calculated.

2.3 Photo Documentation

Permanent photo points were established during Year 1 monitoring. Photographs were taken at these points during the field surveys for Year 2 as noted from the monitoring Year 1 report. Directions of the photo points were followed from what was drawn on the Year 1 monitoring plan view sheets.

3.0 PROJECT CONDITIONS AND RESULTS

3.1 Vegetation

3.1.1 Soils Data

Series	Max Depth (in.)	% Clay on Surface	K	T	OM %
Herndon (HdB2)	68	5.0 - 27.0	0.48	*	0.5 - 1.0
Herndon (HeC3)	68	27.0 - 35.0	0.35	*	0.0 - 0.5
Herndon (HdC2)	68	5.0 - 27.0	0.48	*	0.5 - 1.0
Mixed alluvial (Mc)	<<<< High variability of data >>>>				

* the soils information was not available from the Natural Resources Conservation Service (NRCS)

3.1.2 Vegetative Problem Area Plan View

Feature/Issue	Station # / Range	Probable Cause	Photo # (Appendix A2)
Invasive/Exotic Populations	entire stream reach	likely remnant from pre-construction	1, 3 and 4
	23+50 - Right bank	dodder - unknown cause	2

There is good herbaceous vegetation growth along all of the monitored stream reach. Japanese grass (*Microstegium viminium*) has established along the entire stream reach with limited areas where it does not dominate. The plan sheets in Appendix D show the location of the vegetation plots.

In many areas along the stream and vegetation plots, Japanese honeysuckle (*Lonicera japonica*) and Japanese grass were prevalent. Japanese grass in many areas is likely limiting the establishment of the planted bare root trees.

Soft rush (*Juncus effuses*) is also prevalent along the stream and many of the vegetation plots, including Vegetation Plots #3, 4, 6, 7, 8, and 9. The thickness of the soft rush may be inhibiting some of the bare root tree establishment.

Another exotic, dodder (*Cuscuta* and *Grammica*), was noted at Station No. 23+50 right bank. This exotic is limited only to this area. However, this plant can overtake an area.

3.1.3 *Stem Counts*

At planting, the consultant was not notified to identify the planted bare root trees. Assuming a planting rate of 680 trees/acre, there has been great recruitment of trees into the vegetation plots.

Sweet-gum (*Liquidambar styraciflua*), red maple (*Acer rubrum*) and tulip poplar (*Liriodendrum tulipifera*) were not noted with flagging or counted in the vegetation plots. These species were noted in all of the Vegetation Plots except #8 and 9 (refer to Table VII).

3.2 **Stream**

3.2.1 *Longitudinal Profile*

Few conclusions can be made from the longitudinal survey data when overlaying Year 2 on Year 1. In Year 2, there were many more data points taken in comparison with Year 1. Also, there is a significant discrepancy in the stationing between Year 2 and Year 1 monitoring. Due to these discrepancies, it is difficult to make any conclusions regarding the longitudinal profile of the stream. Uncertainty in the location of some monitoring features and benchmarks has now been eliminated; therefore, subsequent annual comparisons will be fully consistent with the data collection in this report.

There is one significant aspect to note about the longitudinal profile for Year 2. There is a large stream segment distinguished as a run (Station No. 26+05 to 32+66). This accounts for an exceptionally large maximum pool spacing noted in Table XIII of Appendix B3.

3.2.2 *Permanent Cross Sections*

From a review of the cross-sectional survey data from Year 2 overlain on Year 1, it can be concluded that the three cross sections from Year 1 have not changed significantly. Comparisons of cross sections from Year 1 and Year 2 are plotted in Appendix B4. These comparisons show very minor changes, if any at all. Any minor differences are most likely due to differences in surveying data analysis between years. For instance, the number of points taken along the cross section is much greater in Year 2 than in Year 1. Also, in Year 2 monitoring, three additional cross sections were surveyed. Once Year 3 data is collected, a better comparison of all cross section problem areas can be made since the Year 2 and Year 3 data will be collected using the same equipment and staff.

3.2.3 *Pebble Counts*

The following table shows the substrate comparison of Year 1 and Year 2 pebble counts in two riffle cross sections and one pool cross section. As noted previously, three additional cross sections were surveyed in Year 2; therefore, there can be no comparison made for these until Year 3 monitoring.

3.3 **Photo Documentation**

Photos taken at the photo points and at the cross-sections are provided in Appendices A1 and B2. Comparisons from Year 1 to Year 2 can be made by referring back to the Year 1 Monitoring report.

3.4 Problem Areas

Problem areas were noted throughout the entire reach in regards to structure problems, bank erosion, aggradation, and bar formation. The plan view sheets (in Appendix D) show the location of the problem areas. The plan view sheets also show the structures on them and are color coded for the degree of instability or if the structure is in good condition. Table X in Appendix C describes for the reach the feature issue, station number, and suspected cause.

4.0 OVERALL CONCLUSION FOR YEAR 2 MONITORING

At this time it can be concluded that bare root tree growth may be inhibited by the heavy prevalence of Japanese grass, Japanese honeysuckle and also soft rush. As noted on the vegetation problem area plan sheets, these invasive/exotic species are present along the entire reach and in the designated vegetation plots.

The results of the longitudinal profile comparison of current data and Year 1 data are inconclusive. There is a large discrepancy in the stationing between Year 1 and Year 2 data. Results should be much more conclusive after the completion of Year 3 monitoring because of the uncertainty in the location of some monitoring features and benchmarks has now been eliminated.

In regards to cross sections, it is determined that there have been no significant changes in cross section from Year 1 to Year 2. Three additional cross sections were surveyed in Year 2 and will be compared with future Year 3 monitoring.

Conclusions from the Year 3 monitoring data should be more obtainable. With the establishment of the location of monitoring features, including additional cross sections, and benchmarks, uncertainty in these items has now been eliminated; therefore, subsequent annual comparisons will be fully consistent with the data collection in this report.

REFERENCES

- DeLorme. 1997. *The North Carolina Atlas and Gazateer*.
- Ecologic. February 2003. *Reedy Branch Stream Restoration (Design Plans)*.
- Ecologic. September 2003. *Reedy Branch Stream Restoration Planting Plan (Streamside Revegetation Plan)*.
- Ecologic. August 2005. *MY1 (2005) Reedy Branch Monitoring Report*.
- Harman, W.H., et al. 1999. *Bankfull Hydraulic Geometry Relationships for North Carolina Streams*. AWRRA Wildland Hydrology Symposium Proceedings. Edited by D.S. Olson and J.P. Potyondy. AWRRA Summer Symposium. Bozeman, MT.
- North Carolina Ecosystem Enhancement Program. September 2005. *Content, Format and Data Requirements for EEP Monitoring Reports*.
- Rosgen, D.L. 1994. *A Classification of Natural River*. Catena, Volume 22: 166-169, Elsevier Science, B.V. Amsterdam.
- U.S. Department of Agriculture, Soil Conservation Service. April 1960. *Soil Survey Alamance County, North Carolina*.
- U.S. Department of Army, Corps of Engineers. 2003. *Stream Mitigation Guidelines*.
http://www.saw.usace.army.mil/wetlands/Mitigation/stream_mitigation.html

APPENDIX A1

PHOTOLOG VEGETATION PROBLEM AREAS

APPENDIX A1
PHOTOLOG VEGETATION PROBLEM AREAS



Photo 1: Japanese grass along both banks near Vegetation Plot 10



Photo 4: Japanese grass



Photo 2: Dodder



Photo 3: Japanese grass

APPENDIX A2

PHOTOLOG VEGETATION PLOTS

**APPENDIX A2
PHOTOLOG – VEGETATION PLOTS**



Vegetation Plot 1



Vegetation Plot 4



Vegetation Plot 2



Vegetation Plot 5



Vegetation Plot 3



Vegetation Plot 6



Vegetation Plot 7



Vegetation Plot 10



Vegetation Plot 8



Vegetation Plot 11



Vegetation Plot 9



Vegetation Plot 12

APPENDIX A3

VEGETATION DATA TABLES

Table VI. Vegetative Problem Areas - Reedy Branch


Feature/Issue	Station # / Range	Probable Cause	Photo #
Bare Bank			
Bare Bench			
Bare Flood Plain	UT - Station 11+80	area washed from storm events	6
	UT - Station 12+50	area washed from storm events	5
	UT - Station 14+20	area washed from storm events	4
	UT - Station 18+50	area washed from storm events	2
Invasive/Exotic Populations	Reach 1 - Station # 20+50 Lt	Japanese grass overtaking area - from off site	8
	Reach 1 - down from Crest Gauge	Japanese grass overtaking area - from off site	1
	Reach 2 - Station #11-13	Japanese grass overtaking area - from off site	7

READY BRANCH

Table VII. Stem counts for each species arranged by plot

Species	Plots												Initial Totals*	Year 2 Totals	Survival %**		
	1	2	3	4	5	6	7	8	9	10	11	12					
Cornus amomum	1																
Shrubs																	
Salix nigra			III	III													
Trees																	
Betula nigra																	
Carpinus caroliniana	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Carya sp.	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Diospyros virginiana	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Hypericum sp.	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Juglans nigra	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Nyssa sylvatica																	
Platanus occidentalis	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Sambucus canadensis	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Quercus alba	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Quercus michauxii	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Quercus phellos	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III	III
Quercus sp.																	
Rhus copallinum																	
Ulmus alata																	
Total including live stake																	
Stems per acre																	
Total excluding live stake																	
Stems per acre																	

LS
C.A.
L.S



Appendix A3

Table VII. Stem counts for each species arranged by plot												
Species	Plots									Year 1 Totals	Year 2 Totals	Survival %
	1	2	3	4	5	6	7	8	9			
Shrubs												
<i>Cornus ammomum</i>			3	1	(7 LS)	(5 LS)	(1 LS)		1	11 (12 LS)	4 (13 LS)	36 (100)
Trees												
<i>Betula nigra</i>					3	2		2	2	10	9	90
<i>Carpinus caroliniana</i>					3	3	1	3		11	10	91
<i>Diospyros virginiana</i>										0	2	n/a
<i>Fraxinus pennsylvanica</i>						3	1		2	2	6	300
<i>Juglans nigra</i>	1	2	1	2	1	2	1		3	12	13	108
<i>Nyssa sylvatica</i>										1	0	0
<i>Platanus occidentalis</i>	1	1		1		3	1	5	4	22	16	73
<i>Salix nigra</i>							17			13	17	131
<i>Sambucus canadensis</i>										1	0	0
<i>Quercus michauxii</i>			1	3		1	3		1	16	9	56
<i>Quercus rubra</i>			2							2	2	100
<i>Quercus alba</i>		1		1	2					5	4	80
<i>Quercus marilandica</i>			1							1	1	100
Total including live stake	2	4	8	8	20	19	25	10	14	119	102	86
Stems per acre	95	190	381	364	1000	865	1190	500	667			
Total exluding live stake	2	4	8	9	14	11	21	10	17	107	89	83
Stems per acre	95.2	190.4	380.8	409.5	700	500.5	999.6	500	809.2			

APPENDIX B1

PHOTOLOG STREAM PROBLEM AREAS

NO PHOTOGRAPHS AVAILABLE

APPENDIX B2

PHOTOLOG OF CROSS-SECTIONS AND PHOTO POINTS

**APPENDIX B2
PHOTO LOG-CROSS-SECTIONS**



Cross-Section 1: Looking Downstream



Cross-Section 1: Looking Upstream



Cross-Section 2: Looking Downstream



Cross-Section 2: Looking Upstream



Cross-Section 3: Looking Downstream



Cross-Section 3: Looking Upstream



Cross-Section 4: Looking Downstream



Cross-Section 4: Looking Upstream



Cross-Section 5: Looking Downstream



Cross-Section 5: Looking Upstream



Cross-Section 6: Looking Downstream



Cross-Section 6: Looking Upstream

Problems



**APPENDIX B2
PHOTOLOG – GENERAL PHOTO POINTS**



Photo 1



Photo 2



Photo 3



Photo 4



Photo 5



Photo 6



Photo 7



Photo 8



Photo 9



Photo 10



Photo 11



Photo 12



Photo 13



Photo 14



Photo 15



Photo 16



Photo 17



Photo 18



Photo 19



Photo 20



Photo 21



Photo 22



Photo 23



Photo 24



Photo 25



Photo 26



Photo 27



Photo 28



Photo 29



Photo 30



Photo 31



Photo 32



Photo 33



Photo 34



Photo 35



Photo 36



Photo 37

APPENDIX B3

STREAM DATA TABLES

Table VIII. Verification of Bankfull Events - Reedy Branch

Date of Data Collection	Date of Occurrence	Method	Photo # (if available)
8-Aug-06	Unknown	Crest Stage Gauge measurement of approximately 2" on stick (bottom of stick at bkf)	
11-Jan-07	Unknown	Crest Stage Gauge measurement of approximately 6" on stick (bottom of stick at bkf)	

Table B2. Visual Morphological Stability Assessment						
Reedy Branch						
Segment/Reach: Reedy Branch (3097 feet)						
Feature Category	Metric (per As-built and reference baselines)	(#Stable) Number Performing as Intended	Total Number per As-built	Total Number / feet in unstable state	% Performing in Stable Condition	Feature Performance Mean or Total
A. Riffles	1. Present	21	21	NA	100%	
	2. Armor stable	12	21	NA	57%	
	3. Facet grade appears stable	12	21	NA	57%	
	4. Minimal evidence of embedding/fining	12	21	NA	57%	
	5. Length appropriate	12	21	NA	57%	66%
B. Pools	1. Present	24	24	NA	100%	
	2. Sufficiently deep	21	24	NA	88%	
	3. Length appropriate	16	24	NA	67%	85%
C. Thalweg	1. Upstream of meander bend (run/inflection) centering	11	13	NA	85%	
	2. Downstream of meander (glide/inflection) centering	12	13	NA	92%	88%
D. Meanders	1. Outer bend in state of limited/controlled erosion	7	13	NA	54%	
	2. Of those eroding, # w/concomitant point bar formation	3	6	NA	50%	
	3. Apparent Rc within specifications	8	13	NA	62%	
	4. Sufficient floodplain access and relief	10	13	NA	77%	61%
E. Bed General	1. General channel bed aggradation areas (bar formation)	NA	NA	21/244	92%	
	2. Channel bed degradation - areas of increasing down cutting or head cutting	NA	NA	0/0	100%	96%
F. Bank Condition	1. Actively eroding, wasting, or slumping bank	NA	NA	10/160	95%	95%
G. Vanes / J Hooks	1. Free of back or arm scour	17	23	NA	74%	
	2. Height appropriate	17	23	NA	74%	
	3. Angle and geometry appear appropriate	17	23	NA	74%	
	4. Free of piping or other structural failures	17	23	NA	74%	74%
H. Wads and Boulders	1. Free of scour	24	30	NA	80%	
	2. Footing stable	24	30	NA	80%	80%

Table X. Stream Problem Areas			
Reedy Branch (EEP Project #301)			
Feature Issue	Station numbers	Suspected Cause	Photo number
Aggradation (grasses)	10+40.33	Channel narrowing.	
	10+61.12		
Rock Cross Vane	10+87.12	Piping around structure.	
Rootwad	11+64.64	Perhaps placed too high. Dried out.	
Aggradation (Pickerelweed)	12+98.04	Narrow channel.	
	13+02.46		
Aggradation (Pickerelweed)	13+69.95	Soil deposits have built up with vegetation growing.	
	13+76.50		
Bank Erosion (left bank)	14+27.09	Lack of bank protection from directed flow onto bank.	
	14+37.75		
Aggradation (grasses)	16+60.65	There is a lot of bedrock in this area with soil settling on top and	
	16+64.93	grass growing.	
Rootwad	18+64.60	Placed too high. Dried out.	
Rootwad	18+69.89	Placed too high. Dried out.	
Bank Erosion (left bank)	19+38.54	Channel is coming out of a wide area and may be trying to narrow itself.	
	19+51.98		
Rock Cross Vane	19+63.53	Top rock placed too low.	
Aggradation (grasses)	19+94.69	Narrow channel.	
	20+23.51		
Rootwad	20+29.31	Placed too high. Dried out.	
Bank Erosion (left bank)	20+76.83	Back eddying behind rootwad.	
	20+82.26		
Aggradation (Pickerelweed)	20+87.81	Narrow channel.	
	20+95.10		
Aggradation (Pickerelweed)	21+30.50	Narrow channel.	
	21+35.37		
Bank Erosion (left bank)	22+15.18	Flow directed onto left bank before piping through rock cross vane.	
	22+23.05		
Rock Cross Vane	22+18.84	Piping around structure.	
Aggradation (cattails & grasses)	22+73.26	Narrow channel.	
	22+82.82		
Bank Erosion (right bank)	23+33.15	Lack of bank protection from directed flow onto bank.	
	23+59.51		
Aggradation (grasses)	23+75.63	Narrow channel after cattle crossing.	421,422
	23+89.29		
Undercut Bank (left bank)	24+23.74	Flow being piped around rock vane.	
	24+41.37		
Rock Vane	24+30.97	Piping around structure creating undercut bank.	
Rootwad	24+59.39	Placed too high. Dried out.	
Rootwad	24+65.21	Placed too high. Dried out.	
Undercut Bank (right bank)	25+16.11	Back eddying behind rootwads	
	25+47.70		
Rock Cross Vane	25+53.39	Piping around structure.	
Bank Erosion (left bank)	26+15.85	Flow directed onto left bank. Lack of bank protection.	
	26+25.23		
Rootwad	26+35.73	Placed too high. Dried out.	
Aggradation (Pickerelweed)	26+73.67	Channel narrowing.	
	26+96.85		
Aggradation (grasses)	27+03.71	Channel narrowing.	
	27+12.09		
Aggradation (Pickerelweed)	27+15.93	Channel narrowing.	
	27+22.42		
Aggradation (Pickerelweed)	27+35.33	Channel narrowing.	
	27+42.67		
Aggradation (grasses)	27+52.21	Channel narrowing.	
	27+66.55		
Aggradation (Pickerelweed)	27+73.71	Channel narrowing.	
	27+79.13		
Bank Erosion (left bank)	29+52.50	Flow directed onto left bank. Lack of bank protection.	
	29+65.55		
Rock Cross Vane	29+69.11	Piping around structure.	
Aggradation (grasses)	29+93.79	Very narrow channel.	
	30+02.22		
Undercut Bank (left bank)	30+62.47	Directed water flow and back eddying.	
	30+76.11		
Undercut Bank (right bank)	30+62.47	Directed water flow and back eddying.	
	30+76.11		
Undercut Bank (left bank)	30+85.79	Directed water flow and back eddying.	
	31+04.81		
Aggradation (grasses)	32+47.54	Channel starting to narrow.	
	32+55.00		
Rock Cross Vane	32+83.44	Filter fabric exposed.	
Aggradation (grasses)	33+44.42	Channel narrowing.	
	33+52.07		
Aggradation (grasses)	35+82.14	Channel narrowing.	
	35+99.28		
Aggradation (Pickerelweed)	37+34.73	Channel narrowing.	
	37+48.72		
Aggradation (Pickerelweed and grasses)	38+52.16	Channel is very wide in this bend. Soil deposits have built up with lots	
	38+72.37	of vegetation growing	
Rock Vane	38+77.57	Piping around structure.	
Rock Cross Vane	39+44.67	Piping around structure. Exposed filter fabric.	
Bank Erosion (right bank)	39+75.47	Channel is possibly too wide and is trying to narrow itself.	
	40+08.23		
Bank Erosion (left bank)	39+79.03	Channel is possibly too wide and is trying to narrow itself.	
	39+97.11		
Bank Erosion (left bank)	40+61.06	Channel is possibly too wide and is trying to narrow itself.	
	40+91.57		
Bank Erosion (right bank)	40+74.73	Channel is possibly too wide and is trying to narrow itself.	
	40+91.71		

Reedy Branch
Appendix B3

Table B1. Categorical Stream Feature Visual Stability Assessment						
Reedy Branch (EEP Project No. 301)						
Feature	Initial	MY-01	MY-02	MY-03	MY-04	MY-05
A. Riffles	Unknown	Unknown	66%			
B. Pools			85%			
C. Thalweg			88%			
D. Meanders			61%			
E. Bed General			96%			
F. Bank Condition			95%			
G. Vanes / J Hooks etc.			74%			
H. Wads and Boulders			80%			

Table XII Baseline Morphology and Hydraulic Summary

Reedy Branch (EEP Project No. 301)

Parameter	USGS Gage Data			Regional Curve Interval			Pre-Existing Condition			Project Reference Stream			Design			As-built		
	Min	Max	Med	Min	Max	Med	Min	Max	Med	Min	Max	Med	Min	Max	Med	Min	Max	Med
Dimension																		
BF Width (ft)																18.9	26.1	18.9
Floodprone Width (ft)																80	100	90
BF Cross Sectional Area (ft)																21.9	23.2	21.9
BF Mean Depth (ft)																0.9	1.2	1.16
Max Depth (ft)																2.1	2.7	2.7
Width/Depth Ratio																16.3	29.3	16.3
Entrenchment Ratio																3.1	5.3	4.8
Bank Heigh Ratio																n/a	n/a	n/a
Wetted Perimeter (ft)																19.9	46.5	31.1
Hydraulic Radius (ft)																0.9	1.4	1.1
Pattern																		
Channel Belthwidth (ft)																37	170	81
Radius of Curvature (ft)																10.9	24	17.1
Meander Wavelength (ft)																60	280	128
Meader Width Ratio																2	9	4.3
Profile																		
Riffle Length																7	35	16
Riffle Slope (ft/ft)																0.0011	0.0410	0.0100
Pool Length (ft)																16	41	29
Pool Spacing (ft)																29	150	59
Substrate																		
d50 (mm)																n/a	n/a	0.8
d84 (mm)																n/a	n/a	6.5
Additional Reach Parameters																		
Valley Length (ft)																n/a	n/a	2990
Channel Length (ft)																n/a	n/a	3090
Sinuosity																n/a	n/a	1.35
Water Surface Slope (ft/ft)																n/a	n/a	0.0033
BF Slope (ft/ft)																n/a	n/a	0.0031
Rosgen Classification																n/a	n/a	C5
*Habitat Index																n/a	n/a	n/a
*Macrobenthos																n/a	n/a	n/a

Reedy Branch
Appendix B3




Table XIII. Morphology and Hydraulic Monitoring Summary
Reedy Branch
Segment/Reach: Reedy Branch (EEP Project No. 301)

Parameter	Cross Section 1 Rifle						Cross Section 2 Pool						Cross Section 3 Rifle						Cross Section 4 Rifle						Cross Section 5 Pool						Cross Section 6 Rifle					
	MY1	MY2	MY3	MY4	MY5	MY+	MY1	MY2	MY3	MY4	MY5	MY+	MY1	MY2	MY3	MY4	MY5	MY+	MY1	MY2	MY3	MY4	MY5	MY+	MY1	MY2	MY3	MY4	MY5	MY+	MY1	MY2	MY3	MY4	MY5	MY+
Dimension																																				
BF Width (ft)	26.1	21.9					24.4						16.6						18.9	20.8					44.8	17.9					22.4					
Floodporne Width (ft)	80	>88					NA						>59						100	>85					NA	NA					>46					
BFCross Sectional Area (ft)	23.2	24.7					44.5						18.5						21.9	25.4					63	37.8					31.2					
BF Mean Depth (ft)	0.9	1.1					1.8						1.1						1.2	1.2					1.4	2.1					1.4					
Width/Depth Ratio	29.3	19.5					NA						14.8						16.3	17					NA	NA					16.1					
Entrenchment Ratio	3.1	>4.0					NA						>3.6						5.3	>4.0					NA	NA					>2.05					
Bank Height Ratio	1	1					NA						1						1	1					NA	NA					1					
Wetted Perimeter (ft)	27	24.3					26.5						23.7						19.9	38.3					46.5	21.3					25.5					
Hydraulic radius (ft)	0.9	1.1					1.7						0.8						1.1	0.7					1.4	1.8					1.2					
Substrate																																				
d50 (mm)	1	0.113					0.062						0.062						1.7	0.12					0.4	0.062					0.125					
d84 (mm)	17	6.5					0.25						0.25						11	0.4					9	0.17					32					




Parameter	MY-01 (2005)			MY-02 (2006)			MY-03 (2007)			MY-04 (2008)			MY-05 (2005)			MY+ (2009)		
	Min	Max	Med	Min	Max	Med	Min	Max	Med	Min	Max	Med	Min	Max	Med	Min	Max	Med
Pattern																		
Channel Beltwidth (ft)	37	170	80.87	13.68	165.2	44.32												
Radius of Curvature (ft)	10.9	24	17.1	18.36	106	40.3												
Meander Wavelength (ft)	60	280	128	80.54	273	156												
Meander Width Ratio	2	9	4.3	0.66	7.9	2.1												
Profile																		
Rifle length (ft)	8	38	17	2.6	93.5	11.3												
Rifle slope (ft/ft)	0.0011	0.05	0.015	0.000	0.05	0.02												
Pool length (ft)	16	40	29	3.9	155.3	44.35												
Pool spacing (ft)	27	152	59	9.1	744.9	64.7												
Additional Reach Parameters																		
Valley Length (ft)		2290		2550														
Channel Length (ft)		3090		3096														
Sinuosity		1.35		1.21														
Water Surface Slope (ft/ft)		0.0036		0.0036														
BF slope (ft/ft)		0.0051		0.0033														
Rosgen Classification		C5		C5														
*Habitat Index		N/A		N/A														
*Macrobenthos		N/A		N/A														

APPENDIX B4

STREAM CROSS-SECTIONS



* Cross Sections #2, 3 & 6 installed this year (Year 2). Therefore, there is no Year 1 data to compare.



* Cross Sections #2, 3 & 6 installed this year (Year 2). Therefore, there is no Year 1 data to compare.


Reedy Branch
Monitoring Year 2
Alamance County, NC

Field Crew: Wyatt Y., John P., David G.
River Basin: Cape Fear
Watershed: Reedy Branch
Stream Reach: Reedy Branch
Drainage Area: 1.6 sq. miles
Date: July, 2006
Station: 11+35.33
Feature: Riffle

STATION (Feet)	ELEVATION (Feet)	NOTES
0.00	584.77	
0.28	584.50	
7.88	584.68	
12.94	584.41	
16.42	583.81	
20.43	583.00	
22.83	583.12	
24.33	582.65	
26.20	582.87	
32.22	582.77	
34.90	582.91	lbkf / ltob
37.02	582.49	
40.02	582.24	
41.42	581.94	
42.87	581.73	
43.82	581.52	
44.49	581.06	
45.21	580.66	
45.60	580.47	
46.03	580.46	
46.48	580.25	
47.07	580.29	
47.66	580.38	
48.45	580.41	
49.06	580.50	
49.14	580.55	
49.63	580.72	
50.05	581.04	
50.43	581.45	
51.52	581.94	
52.76	582.25	
54.28	582.48	
56.84	582.89	rbkf / rtob
57.66	582.95	
59.25	583.57	
61.27	584.25	
64.33	584.27	
66.95	583.92	
69.08	583.11	
69.86	582.37	
71.39	582.00	
73.68	581.96	
74.81	582.16	
75.72	582.86	
77.49	583.96	
82.98	583.91	
87.99	584.89	

Bankfull Hydraulic Geometry		
Width (Feet)	Depth (Feet)	Area (Sq. Ft.)
0.0	0.0	0.0
2.1	0.4	0.4
3.0	0.7	1.6
1.4	1.0	1.1
1.4	1.2	1.6
0.9	1.4	1.2
0.7	1.8	1.1
0.7	2.3	1.5
0.4	2.4	0.9
0.4	2.5	1.0
0.5	2.7	1.2
0.6	2.6	1.6
0.6	2.5	1.5
0.8	2.5	2.0
0.6	2.4	1.5
0.1	2.4	0.2
0.5	2.2	1.1
0.4	1.9	0.9
0.4	1.5	0.6
1.1	1.0	1.3
1.2	0.7	1.0
1.5	0.4	0.8
2.6	0.0	0.6
TOTALS	21.9	24.7

SUMMARY DATA (BANKFULL)	
A(BKF)	24.7
W(BKF)	21.9
Max d	2.7
Mean d	1.1
W/D	19.5
Entrenchment	>4.0
Stream Type	C
W(FPA)	>88
Slope	0.004
Sinuosity	1.21
Area= A	
Width= W	
Depth= D	
Bankfull= BKF	
Area from Rural Regional Curve	30.1




Reedy Branch
Monitoring Year 2
Alamance County, NC

Field Crew: Wyatt Y. & David G.
River Basin: Cape Fear
Watershed: Reedy Branch
Stream Reach: Reedy Branch
Drainage Area: 1.6 sq. miles
Date: July 2006
Station: 22+41.18
Feature: Pool

STATION (Feet)	ELEVATION (Feet)	NOTES
0.00	578.87	
0.22	578.57	
1.69	578.55	
5.87	578.00	
10.72	578.88	
12.85	579.00	
15.37	578.33	
17.18	578.10	
18.31	577.72	
19.405	577.61	lbkf(int)/ltob
20.50	577.50	
24.48	576.52	
25.19	576.32	
26.38	575.83	
27.30	575.67	
28.35	575.14	
29.77	574.78	
31.70	574.23	
34.09	574.19	
35.88	574.28	
37.69	574.62	
37.69	575.63	
38.61	576.23	
40.04	576.44	
41.13	576.52	
41.60	576.98	
43.78	577.61	rbkf/rtb
52.59	577.85	
59.72	577.99	
64.51	579.48	
67.30	579.42	
69.28	579.73	
69.44	579.86	

Bankfull/Top of Bank Hydraulic Geometry		
Width (Feet)	Depth (Feet)	Area (Sq. Ft.)
0.0	0.0	0.0
1.1	0.1	0.1
4.0	1.1	2.4
0.7	1.3	0.8
1.2	1.8	1.8
0.9	1.9	1.7
1.0	2.5	2.3
1.4	2.8	3.8
1.9	3.4	6.0
2.4	3.4	8.2
1.8	3.3	6.0
1.8	3.0	5.7
0.0	2.0	0.0
0.9	1.4	1.6
1.4	1.2	1.8
1.1	1.1	1.2
0.5	0.6	0.4
2.2	0.0	0.7
TOTALS	24.4	44.5

SUMMARY DATA (TOB)	
A(BKF)	44.5
W(BKF)	24.4
Max d	3.4
Mean d	1.8




Reedy Branch
Monitoring Year 2
Alamance County, NC

Field Crew: Wyatt Y. & David G.
River Basin: Cape Fear
Watershed: Reedy Branch
Stream Reach: Reedy Branch
Drainage Area: 1.6 sq. miles
Date: July 2006
Station: 22+86.06
Feature: Riffle

STATION (Feet)	HI (Feet)	NOTES
0.00	579.11	
0.08	578.78	
2.67	578.41	
5.45	578.43	
7.73	577.70	
9.35	577.45	
17.03	577.51	
18.21	577.49	lbfk/ftob
19.12	577.21	
21.55	577.17	
25.97	576.12	
26.75	575.39	
27.41	575.28	
28.16	575.16	
28.80	575.17	
29.00	575.18	
29.15	575.25	
29.91	575.21	
30.15	575.34	
31.45	575.76	
32.50	576.57	
34.79	577.49	rbkf(int)/rtob
35.98	577.97	
36.98	578.14	
45.97	578.47	
48.10	578.28	
52.44	578.63	
54.80	578.70	
58.75	578.62	
58.86	578.99	

Bankfull/TOB Hydraulic Geometry		
Width (Feet)	Depth (Feet)	Area (Sq. Ft.)
0.0	0.0	0.0
0.9	0.3	0.1
2.4	0.3	0.7
4.4	1.4	3.7
0.8	2.1	1.4
0.7	2.2	1.4
0.8	2.3	1.7
0.6	2.3	1.5
0.2	2.3	0.5
0.2	2.2	0.4
0.8	2.3	1.7
0.2	2.1	0.5
1.3	1.7	2.5
1.1	0.9	1.4
2.3	0.0	1.0
TOTALS	16.6	18.5

SUMMARY DATA (BANKFULL)			
A(BKF)	18.5	W(FPA)	>59
W(BKF)	16.6	Slope	0.004
Max d	2.3	Sinuosity	1.21
Mean d	1.1	Area= A	
W/D	14.8	Width= W	
Entrenchment	>3.6	Depth= D	
Stream Type	C	Bankfull= BKF	
Area from Rural Regional Curve			30.1




Reedy Branch
Monitoring Year 2
Alamance County, NC

Field Crew: Wyatt Y. & David G.
River Basin: Cape Fear
Watershed: Reedy Branch
Stream Reach: Reedy Branch
Drainage Area: 1.6 sq. miles
Date: July 2006
Station: 25+84.85
Feature: Riffle

STATION (Feet)	HI (Feet)	NOTES
0.00	575.63	
0.03	575.15	
1.60	574.71	
11.59	574.53	
18.81	573.50	
24.83	573.32	lbf
36.06	573.47	
41.04	573.25	
43.75	572.69	
45.31	571.87	
45.91	571.78	
46.91	571.03	
48.11	571.02	
48.35	570.75	
49.01	570.70	
49.43	570.61	
50.13	570.61	
50.69	570.60	
51.58	571.39	
53.96	571.94	
55.92	573.13	
56.81	573.47	rbkf(int)
58.50	574.12	
62.21	574.59	
65.32	574.42	
68.09	574.65	
73.93	574.86	
84.78	574.88	
84.83	575.26	

Bankfull/TOB Hydraulic Geometry		
Width (Feet)	Depth (Feet)	Area (Sq. Ft.)
0.0	0.0	0.0
5.0	0.2	0.5
2.7	0.8	1.3
1.6	1.6	1.8
0.6	1.7	1.0
1.0	2.4	2.1
1.2	2.4	2.9
0.2	2.7	0.6
0.7	2.8	1.8
0.4	2.9	1.2
0.7	2.9	2.0
0.6	2.9	1.6
0.9	2.1	2.2
2.4	1.5	4.3
2.0	0.3	1.8
0.9	0.0	0.1
TOTALS	20.8	25.4

SUMMARY DATA (BANKFULL)			
A(BKF)	25.4	W(FPA)	>85
W(BKF)	20.8	Slope	0.004
Max d	2.9	Sinuosity	1.21
Mean d	1.2	Area= A	
W/D	17.0	Width= W	
Entrenchment	>4.0	Depth= D	
Stream Type	C	Bankfull= BKF	
Area from Rural Regional Curve			30.1




Reedy Branch
Monitoring Year 2
Alamance County, NC

Field Crew: Wyatt Y. & David G.
River Basin: Cape Fear
Watershed: Reedy Branch
Stream Reach: Reedy Branch
Drainage Area: 1.6 sq. miles
Date: July 2006
Station: 37+71.66
Feature: Pool

STATION (Feet)	ELEVATION (Feet)	NOTES
0.00	572.41	
0.06	571.93	
5.75	571.82	
13.76	571.60	
16.19	571.43	
27.99	571.60	
31.07	571.55	
34.40	571.05	
35.53	570.42	lbkf/tob
38.96	569.40	
39.15	569.39	
41.11	567.44	
42.25	566.80	
43.22	566.67	
44.25	566.57	
45.78	566.47	
46.80	566.88	
47.28	566.65	
48.50	567.12	
48.52	568.17	
49.14	568.57	
49.66	568.61	
50.03	569.29	
53.4	570.42	rbkf(int)/rtob
57.23	571.70	
62.70	572.05	
65.38	571.82	
77.72	571.95	
86.66	572.08	
94.34	572.18	
98.18	572.23	
99.30	572.20	
99.34	572.64	

Bankfull/Top of Bank Hydraulic Geometry		
Width (Feet)	Depth (Feet)	Area (Sq. Ft.)
0.0	0.0	0.0
3.4	1.0	1.7
0.2	1.0	0.2
2.0	3.0	3.9
1.1	3.6	3.7
1.0	3.8	3.6
1.0	3.9	3.9
1.5	4.0	6.0
1.0	3.5	3.8
0.5	3.8	1.8
1.2	3.3	4.3
0.0	2.3	0.1
0.6	1.9	1.3
0.5	1.8	1.0
0.4	1.1	0.5
3.4	0.0	1.9
TOTALS	17.9	37.8

SUMMARY DATA (TOB)	
A(BKF)	37.8
W(BKF)	17.9
Max d	4.0
Mean d	2.1




Reedy Branch
Monitoring Year 2
Alamance County, NC

Field Crew: Wyatt Y. & Amanda W.
River Basin: Cape Fear
Watershed: Reedy Branch
Stream Reach: Reedy Branch
Drainage Area: 1.6 sq. miles
Date: July 2006
Station: 39+68.21
Feature: Riffle

STATION (Feet)	HI (Feet)	NOTES
0.00	570.52	
0.00	569.94	
5.93	570.05	
7.86	569.97	lbfk/tob
12.46	569.42	
14.05	568.95	
14.14	568.95	
16.41	568.44	
17.71	567.97	
19.23	567.32	
20.17	567.16	
21.16	567.24	
22.56	567.01	
23.34	567.46	
24.97	568.46	
27.30	568.72	
30.28	569.93	rbkf/rtob
32.68	570.60	
38.69	570.96	
45.72	571.20	
45.84	571.74	

Bankfull/TOB Hydraulic Geometry		
Width (Feet)	Depth (Feet)	Area (Sq. Ft.)
0.0	0.0	0.0
4.6	0.5	1.3
1.6	1.0	1.2
0.1	1.0	0.1
2.3	1.5	2.9
1.3	2.0	2.3
1.5	2.7	3.5
0.9	2.8	2.6
1.0	2.7	2.7
1.4	3.0	4.0
0.8	2.5	2.1
1.6	1.5	3.3
2.3	1.3	3.2
3.0	0.0	1.9
TOTALS	22.4	31.2


SUMMARY DATA (BANKFULL)			
A(BKF)	31.2	W(FPA)	>46
W(BKF)	22.4	Slope	0.004
Max d	3.0	Sinuosity	1.21
Mean d	1.4	Area= A	
W/D	16.1	Width= W	
Entrenchment	>2.1	Depth= D	
Stream Type	C	Bankfull= BKF	
Area from Rural Regional Curve			30.1



APPENDIX B5


STREAM LONGITUDINAL PROFILE

Reedy Branch Longitudinal Profile (Year 2)




→ Thalweg → Water Surface * LBKF × RBKF △ LTOB △ RTOB

Reedy Branch Longitudinal Profile (Year 2)




→ Thalweg → Water Surface * LBKF × RBKF △ LTOB △ RTOB

Reedy Branch Longitudinal Profile (Year 2)




→ Thalweg → Water Surface * LBKF × RBKF △ LTOB △ RTOB

Year 1 & 2 Comparison




◆ Year 1 Thalweg ■ Year 2 Thalweg ▲ Year 2 Water Surface ▲ Year 1 Water Surface

Year 1 & 2 Comparison



◆ Year 1 Thalweg ■ Year 2 Thalweg ▲ Year 2 Water Surface ▲ Year 1 Water Surface

Year 1 & 2 Comparison








◆ Year 1 Thalweg ■ Year 2 Thalweg ▲ Year 2 Water Surface ▲ Year 1 Water Surface


APPENDIX B6

STREAM PEBBLE COUNTS


Reedy Branch
Stream Monitoring
Year 2: 2006
Alamance County, NC

PEBBLE COUNT							
Site: Reedy Branch							
Party: ATW and WDY							
Date: 10/20/2006							
Inches	Particle	Millimeters		Cross-Section 1 (Riffle)	TOT#	ITEM %	% CUM
	Silt/Clay	< 0.062	S/C	44	44	44%	44%
	Very Fine	.062-.125		7	7	7%	51%
	Fine	.125-.25		14	14	14%	65%
	Medium	.25-.50		8	8	8%	73%
	Coarse	.50-1.0		8	8	8%	81%
.04-.08	Very Coarse	1.0-2		1	1	1%	82%
.08-.16	Very Fine	2.0-4.0		0	0	0%	82%
.16-.22	Fine	4-5.7		1	1	1%	83%
.22-.31	Fine	5.7-8		4	4	4%	87%
.31-.44	Medium	8-11.3		4	4	4%	91%
.44-.63	Medium	11.3-16		3	3	3%	94%
.63-.89	Coarse	16-22.6		4	4	4%	98%
.89-1.26	Coarse	22.6-32		1	1	1%	99%
1.26-1.77	Very Coarse	32-45		0	0	0%	99%
1.77-2.5	Very Coarse	45-64		0	0	0%	99%
2.5-3.5	Small	64-90		1	1	1%	100%
3.5-5.0	Small	90-128		0	0	0%	100%
5.0-7.1	Large	128-180		0	0	0%	100%
7.1-10.1	Large	180-256		0	0	0%	100%
10.1-14.3	Small	256-362		0	0	0%	100%
14.3-20	Small	362-512		0	0	0%	100%
20-40	Medium	512-1024		0	0	0%	100%
40-80	Large	1024-2048		0	0	0%	100%
	Bedrock		BDRK	0	0	0%	100%
					100	100%	100%


Reedy Branch
Stream Monitoring
Year 2: 2006
Alamance County, NC

PEBBLE COUNT							
Site: Reedy Branch							
Party: ATW and WDY							
Date: 10/20/2006							
Inches	Particle	Millimeters		Cross-Section 2 (Pool)	TOT#	ITEM %	% CUM
	Silt/Clay	< 0.062	S/C	38	38	38%	38%
	Very Fine	.062-.125	S A N D	17	17	17%	55%
	Fine	.125-.25		27	27	27%	82%
	Medium	.25-.50		9	9	9%	91%
	Coarse	.50-1.0		6	6	6%	97%
.04-.08	Very Coarse	1.0-2		0	0	0%	97%
.08-.16	Very Fine	2.0-4.0	G R A V E L	0	0	0%	97%
.16-.22	Fine	4-5.7		0	0	0%	97%
.22-.31	Fine	5.7-8		1	1	1%	98%
.31-.44	Medium	8-11.3		1	1	1%	99%
.44-.63	Medium	11.3-16		0	0	0%	99%
.63-.89	Coarse	16-22.6		0	0	0%	99%
.89-1.26	Coarse	22.6-32		0	0	0%	99%
1.26-1.77	Very Coarse	32-45		1	1	1%	100%
1.77-2.5	Very Coarse	45-64		0	0	0%	100%
2.5-3.5	Small	64-90	C O B B L E	0	0	0%	100%
3.5-5.0	Small	90-128		0	0	0%	100%
5.0-7.1	Large	128-180		1	1	1%	101%
7.1-10.1	Large	180-256		0	0	0%	101%
10.1-14.3	Small	256-362	B O U L D E R	0	0	0%	101%
14.3-20	Small	362-512		0	0	0%	101%
20-40	Medium	512-1024		0	0	0%	101%
40-80	Large	1024-2048		0	0	0%	101%
	Bedrock		BDRK	0	0	0%	101%
					101	101%	101%


Reedy Branch
Stream Monitoring
Year 2: 2006
Alamance County, NC

PEBBLE COUNT							
Site: Reedy Branch							
Party: ATW and WDY							
Date: 10/20/2006							
Inches	Particle	Millimeters	Cross-Section 3 (Riffle)	TOT#	ITEM %	% CUM	
	Silt/Clay	< 0.062	S/C	38	38	38%	38%
	Very Fine	.062-.125	S A N D	28	28	28%	66%
	Fine	.125-.25		14	14	14%	80%
	Medium	.25-.50		12	12	12%	92%
	Coarse	.50-1.0		4	4	4%	96%
.04-.08	Very Coarse	1.0-2		0	0	0%	96%
.08-.16	Very Fine	2.0-4.0	G R A V E L	1	1	1%	97%
.16-.22	Fine	4-5.7		0	0	0%	97%
.22-.31	Fine	5.7-8		1	1	1%	98%
.31-.44	Medium	8-11.3		2	2	2%	100%
.44-.63	Medium	11.3-16		0	0	0%	100%
.63-.89	Coarse	16-22.6		0	0	0%	100%
.89-1.26	Coarse	22.6-32		0	0	0%	100%
1.26-1.77	Very Coarse	32-45		0	0	0%	100%
1.77-2.5	Very Coarse	45-64		0	0	0%	100%
2.5-3.5	Small	64-90	C O B B L E	0	0	0%	100%
3.5-5.0	Small	90-128		0	0	0%	100%
5.0-7.1	Large	128-180		0	0	0%	100%
7.1-10.1	Large	180-256		0	0	0%	100%
10.1-14.3	Small	256-362	B O U L D E R	0	0	0%	100%
14.3-20	Small	362-512		0	0	0%	100%
20-40	Medium	512-1024		0	0	0%	100%
40-80	Large	1024-2048		0	0	0%	100%
	Bedrock		BDRK	0	0	0%	100%
				100	100%	100%	


Reedy Branch
Stream Monitoring
Year 2: 2006
Alamance County, NC

PEBBLE COUNT							
Site: Reedy Branch							
Party: ATW and WDY							
Date: 10/20/2006							
Inches	Particle	Millimeters	Cross-Section 4 (Riffle)	TOT#	ITEM %	% CUM	
	Silt/Clay	< 0.062	S/C	28	28	28%	28%
	Very Fine	.062-.125	S A N D	24	24	24%	52%
	Fine	.125-.25		12	12	12%	64%
	Medium	.25-.50		8	8	8%	72%
	Coarse	.50-1.0		14	14	14%	86%
.04-.08	Very Coarse	1.0-2		0	0	0%	86%
.08-.16	Very Fine	2.0-4.0	G R A V E L	0	0	0%	86%
.16-.22	Fine	4-5.7		0	0	0%	86%
.22-.31	Fine	5.7-8		1	1	1%	87%
.31-.44	Medium	8-11.3		5	5	5%	92%
.44-.63	Medium	11.3-16		3	3	3%	95%
.63-.89	Coarse	16-22.6		4	4	4%	99%
.89-1.26	Coarse	22.6-32		0	0	0%	99%
1.26-1.77	Very Coarse	32-45		1	1	1%	100%
1.77-2.5	Very Coarse	45-64	0	0	0%	100%	
2.5-3.5	Small	64-90	C O B B L E	0	0	0%	100%
3.5-5.0	Small	90-128		0	0	0%	100%
5.0-7.1	Large	128-180		0	0	0%	100%
7.1-10.1	Large	180-256		0	0	0%	100%
10.1-14.3	Small	256-362	B O U L D E R	0	0	0%	100%
14.3-20	Small	362-512		0	0	0%	100%
20-40	Medium	512-1024		0	0	0%	100%
40-80	Large	1024-2048		0	0	0%	100%
	Bedrock		BDRK	0	0	0%	100%
				100	100%	100%	




Reedy Branch
Stream Monitoring
Year 2: 2006
Alamance County, NC

PEBBLE COUNT							
Site: Reedy Branch							
Party: ATW and WDY							
Date: 10/20/2006							
Inches	Particle	Millimeters	Cross-Section 5 (Pool)	TOT#	ITEM %	% CUM	
	Silt/Clay	< 0.062	S/C	52	52	52%	52%
	Very Fine	.062-.125	S A N D	27	27	27%	79%
	Fine	.125-.25		12	12	12%	91%
	Medium	.25-.50		4	4	4%	95%
	Coarse	.50-1.0		1	1	1%	96%
.04-.08	Very Coarse	1.0-2		0	0	0%	96%
.08-.16	Very Fine	2.0-4.0	G R A V E L	0	0	0%	96%
.16-.22	Fine	4-5.7		0	0	0%	96%
.22-.31	Fine	5.7-8		0	0	0%	96%
.31-.44	Medium	8-11.3		0	0	0%	96%
.44-.63	Medium	11.3-16		2	2	2%	98%
.63-.89	Coarse	16-22.6		0	0	0%	98%
.89-1.26	Coarse	22.6-32		0	0	0%	98%
1.26-1.77	Very Coarse	32-45		0	0	0%	98%
1.77-2.5	Very Coarse	45-64		0	0	0%	98%
2.5-3.5	Small	64-90	C O B B L E	0	0	0%	98%
3.5-5.0	Small	90-128		2	2	2%	100%
5.0-7.1	Large	128-180		0	0	0%	100%
7.1-10.1	Large	180-256		0	0	0%	100%
10.1-14.3	Small	256-362	B O U L D E R	0	0	0%	100%
14.3-20	Small	362-512		0	0	0%	100%
20-40	Medium	512-1024		0	0	0%	100%
40-80	Large	1024-2048		0	0	0%	100%
	Bedrock		BDRK	0	0	0%	100%
				100	100%	100%	

Reedy Branch
Stream Monitoring
Year 2: 2006
Alamance County, NC



PEBBLE COUNT							
Site: Reedy Branch							
Party: ATW and WDY							
Date: 10/20/2006							
Inches	Particle	Millimeters	S/C	Cross-Section 6 (Riffle)	TOT#	ITEM %	% CUM
	Silt/Clay	< 0.062	S/C	32	32	32%	32%
	Very Fine	.062-.125	S A N D	9	9	9%	41%
	Fine	.125-.25		14	14	14%	55%
	Medium	.25-.50		5	5	5%	60%
	Coarse	.50-1.0		10	10	10%	70%
.04-.08	Very Coarse	1.0-2		0	0	0%	70%
.08-.16	Very Fine	2.0-4.0	G R A V E L	0	0	0%	70%
.16-.22	Fine	4-5.7		0	0	0%	70%
.22-.31	Fine	5.7-8		0	0	0%	70%
.31-.44	Medium	8-11.3		1	1	1%	71%
.44-.63	Medium	11.3-16		5	5	5%	76%
.63-.89	Coarse	16-22.6		5	5	5%	81%
.89-1.26	Coarse	22.6-32		3	3	3%	84%
1.26-1.77	Very Coarse	32-45		2	2	2%	86%
1.77-2.5	Very Coarse	45-64	8	8	8%	94%	
2.5-3.5	Small	64-90	C O B B L E	3	3	3%	97%
3.5-5.0	Small	90-128		1	1	1%	98%
5.0-7.1	Large	128-180		1	1	1%	99%
7.1-10.1	Large	180-256		1	1	1%	100%
10.1-14.3	Small	256-362	B O U L D E R	0	0	0%	100%
14.3-20	Small	362-512		0	0	0%	100%
20-40	Medium	512-1024		0	0	0%	100%
40-80	Large	1024-2048		0	0	0%	100%
	Bedrock		BDRK	0	0	0%	100%
					100	100%	100%

Appendix B6
 Reedy Branch Pebble Counts
 Year 1 and 2 Comparisons



APPENDIX C

PLAN VIEW SHEETS



CROSS SECTION STAKING			
	NORTHING	EASTING	ELEVATION
XSC 1 LEFT	771025.3443	1879852.4770	584.7667
XSC 1 RIGHT	770943.7261	1879884.3740	584.8904




•NOTE: INVASIVE/EXOTIC (MICROSTEGIUM) IS PRESENT IN ALL AREAS WITHIN PLANTING BUFFER EXCEPT AS NOTED TO BE FREE FROM INVASIVE/EXOTIC SPECIES

REEDY BRANCH

LEGEND			
-----	THALWEG 2006		BANK EROSION (BARE BANK)
- - - - -	EDGE OF WATER 2006		SEVERE BANK EROSION
—————	BANKFULL & TOP OF BANK 2006		AGGRADATION (GRASSES)
-----	CROSS-SECTIONS		AGGRADATION (PICKERELWEED)
←	GENERAL PHOTO POINT		UNDERCUT BANKS
←●	VEGETATION PHOTO POINT		AREA FREE OF INVASIVE/EXOTIC SPECIES
STRUCTURE TYPES			
	ROCK CROSS VANE		J-HOOK VANE
	ROCK VANE		BEDROCK
	ROOTWAD		
COLOR CODE FOR STRUCTURES			
	GOOD STRUCTURE		STRUCTURE WITH POTENTIAL PROBLEM
	FAILING STRUCTURE		



LOCATION:	
REEDY BRANCH STREAM MONITORING - YEAR 2	
PROJ #:	COUNTY:
301	ALAMANCE
PREPARED BY:	
WDY	
CHECKED BY:	DATE:
ATW	11/17/06





*NOTE: INVASIVE/EXOTIC (MICROSTEGIUM) IS PRESENT IN ALL AREAS WITHIN PLANTING BUFFER EXCEPT AS NOTED TO BE FREE FROM INVASIVE/EXOTIC SPECIES

REEDY BRANCH

LEGEND			
	THALWEG 2006		BANK EROSION (BARE BANK)
	EDGE OF WATER 2006		SEVERE BANK EROSION
	BANKFULL & TOP OF BANK 2006		AGGRADATION (GRASSES)
	CROSS-SECTIONS		AGGRADATION (PICKERELWEED)
	GENERAL PHOTO POINT		UNDERCUT BANKS
	VEGETATION PHOTO POINT		AREA FREE OF INVASIVE/EXOTIC SPECIES
STRUCTURE TYPES			
	ROCK CROSS VANE		J-HOOK VANE
	ROCK VANE		ROOTWAD
			BEDROCK
COLOR CODE FOR STRUCTURES			
	GOOD STRUCTURE		STRUCTURE WITH POTENTIAL PROBLEM
	FAILING STRUCTURE		



LOCATION:	
REEDY BRANCH STREAM MONITORING - YEAR 2	
PROJ #:	COUNTY:
301	ALAMANCE
PREPARED BY:	
WDY	
CHECKED BY:	DATE:
ATW	11/17/06



CROSS SECTION STAKING			
	NORTHING	EASTING	ELEVATION
XSC 2 LEFT	770782.1022	1880574.5236	578.8664
XSC 2 RIGHT	770721.2748	1880608.5008	579.8611
XSC 3 LEFT	770788.7579	1880614.5106	579.1104
XSC 3 RIGHT	770743.0304	1880651.6428	578.9910
XSC 4 LEFT	770968.3605	1880727.1468	575.6349
XSC 4 RIGHT	770955.0930	1880810.9364	575.2575

*NOTE: INVASIVE/EXOTIC (MICROSTEGIUM) IS PRESENT IN ALL AREAS WITHIN PLANTING BUFFER EXCEPT AS NOTED TO BE FREE FROM INVASIVE/EXOTIC SPECIES



LEGEND

<p>----- THALWEG 2006</p> <p>- - - - - EDGE OF WATER 2006</p> <p>----- BANKFULL & TOP OF BANK 2006</p> <p>----- CROSS-SECTIONS</p> <p>← GENERAL PHOTO POINT</p> <p>←● VEGETATION PHOTO POINT</p>	<p>▨ BANK EROSION (BARE BANK)</p> <p>▨ SEVERE BANK EROSION</p> <p>▨ AGGRADATION (GRASSES)</p> <p>▨ AGGRADATION (PICKERELWEED)</p> <p>▨ UNDERCUT BANKS</p> <p>▨ AREA FREE OF INVASIVE/EXOTIC SPECIES</p>	<p>STRUCTURE TYPES</p> <p>⌋ ROCK CROSS VANE</p> <p>⌋ J-HOOK VANE</p> <p>⌋ ROCK VANE</p> <p>⌋ ROOTWAD</p> <p>⌋ BEDROCK</p>	<p>COLOR CODE FOR STRUCTURES</p> <p>■ GOOD STRUCTURE</p> <p>■ STRUCTURE WITH POTENTIAL PROBLEM</p> <p>■ FAILING STRUCTURE</p>
--	---	---	---

REEDY BRANCH



LOCATION:	
REEDY BRANCH STREAM MONITORING - YEAR 2	
PROJ #:	COUNTY:
301	ALAMANCE
PREPARED BY:	
WDY	
CHECKED BY:	DATE:
ATW	11/17/06



*NOTE: INVASIVE/EXOTIC (MICROSTEGIUM) IS PRESENT IN ALL AREAS WITHIN PLANTING BUFFER EXCEPT AS NOTED TO BE FREE FROM INVASIVE/EXOTIC SPECIES




REEDY BRANCH

LEGEND

-----	THALWEG 2006		BANK EROSION (BARE BANK)	<u>STRUCTURE TYPES</u>			COLOR CODE FOR STRUCTURES
.....	EDGE OF WATER 2006		SEVERE BANK EROSION		ROCK CROSS VANE		GOOD STRUCTURE
————	BANKFULL & TOP OF BANK 2006		AGGRADATION (GRASSES)		J-HOOK VANE		STRUCTURE WITH POTENTIAL PROBLEM
-----●-----	CROSS-SECTIONS		AGGRADATION (PICKERELWEED)		ROCK VANE		FAILING STRUCTURE
←	GENERAL PHOTO POINT		UNDERCUT BANKS		ROOTWAD		
←●	VEGETATION PHOTO POINT		AREA FREE OF INVASIVE/EXOTIC SPECIES		BEDROCK		



LOCATION: REEDY BRANCH STREAM MONITORING - YEAR 2	
PROJ #: 301	COUNTY: ALAMANCE
PREPARED BY: WDY	
CHECKED BY: ATW	DATE: 11/17/06



CROSS SECTION STAKING			
	NORTHING	EASTING	ELEVATION
XSC 5 LEFT	771655.7440	1881190.6814	572.4095
XSC 5 RIGHT	771596.7893	1881270.3239	572.6393
XSC 6 LEFT	771737.2562	1881187.0696	570.5211
XSC 6 RIGHT	771773.7453	1881214.5737	571.7398

*NOTE: INVASIVE/EXOTIC (MICROSTEGIUM) IS PRESENT IN ALL AREAS WITHIN PLANTING BUFFER EXCEPT AS NOTED TO BE FREE FROM INVASIVE/EXOTIC SPECIES

REEDY BRANCH

LEGEND

<p>----- THALWEG 2006</p> <p>- - - - - EDGE OF WATER 2006</p> <p>----- BANKFULL & TOP OF BANK 2006</p> <p>----- CROSS-SECTIONS</p> <p>← GENERAL PHOTO POINT</p> <p>←● VEGETATION PHOTO POINT</p>	<p> BANK EROSION (BARE BANK)</p> <p> SEVERE BANK EROSION</p> <p> AGGRADATION (GRASSES)</p> <p> AGGRADATION (PICKERELWEED)</p> <p> UNDERCUT BANKS</p> <p> AREA FREE OF INVASIVE/EXOTIC SPECIES</p>	<p>STRUCTURE TYPES</p> <p> ROCK CROSS VANE</p> <p> J-HOOK VANE</p> <p> ROCK VANE</p> <p> ROOTWAD</p> <p> BEDROCK</p>	<p>COLOR CODE FOR STRUCTURES</p> <p> GOOD STRUCTURE</p> <p> STRUCTURE WITH POTENTIAL PROBLEM</p> <p> FAILING STRUCTURE</p>
--	---	---	---



LOCATION:	
REEDY BRANCH	
STREAM MONITORING - YEAR 2	
PROJ #:	COUNTY:
301	ALAMANCE
PREPARED BY:	
WDY	
CHECKED BY:	DATE:
ATW	11/17/06