

| | | | |
|--------------------------------|---|---------------------------------|-----------------------------|
| Mitigation Project Name | St Clair Creek Restoration Project | USACE Action ID | 2008-02655 |
| DMS ID | 95015 | DWR Permit | 2013-0379 |
| River Basin | Tar-Pamlico | Date Project Instituted | 7/18/2011 |
| Cataloging Unit | 03020104 | Date Prepared | 4/23/2020 |
| County | Beaufort | Stream/Wet. Service Area | Tar-Pamlico 03020104 |


Signature & Date of Official Approving Credit Release

1 - For NCDMS, no credits are released during the first milestone
2 - For NCDMS projects, the initial credit release milestone occurs automatically when the as-built report (baseline monitoring report) has been made available to the IRT by posting it to the DMS portal, provided the following have been met:

- 1) Approved of Final Mitigation Plan
 - 2) Recordation of the preservation mechanism, as well as a title opinion acceptable to the USACE covering the property.
 - 3) Completion of all physical and biological improvements to the mitigation site pursuant to the mitigation plan.
 - 4) Receipt of necessary DA permit authorization or written DA approval for projects where DA permit issuance is not required.
- 3 - A 10% reserve of credits is to be held back until the bankfull event performance standard has been met.

| Credit Release Milestone | Warm Stream Credits | | | | | | |
|---------------------------------|----------------------|---------------------|---------------------|-------------------------|------------------|--------------------------|---------------------|
| | Scheduled Releases % | Proposed Releases % | Proposed Released # | Not Approved # Releases | Approved Credits | Anticipated Release Year | Actual Release Date |
| 1 - Site Establishment | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| 2 - Year 0 / As-Built | 30.00% | 30.00% | 982.200 | 0.000 | 982.200 | 2014 | 7/21/2014 |
| 3 - Year 1 Monitoring | 10.00% | 10.00% | 327.400 | 0.000 | 327.400 | 2015 | 4/23/2015 |
| 4 - Year 2 Monitoring | 10.00% | 10.00% | 327.400 | 163.700 | 163.700 | 2016 | 7/8/2016 |
| 5 - Year 3 Monitoring | 10.00% | 10.00% | 327.400 | 0.000 | 491.100 | 2017 | 4/3/2017 |
| 6 - Year 4 Monitoring | 5.00% | 5.00% | 163.700 | 0.000 | 163.700 | 2018 | 4/25/2018 |
| 7 - Year 5 Monitoring | 10.00% | 10.00% | 327.400 | 327.400 | 0.000 | 2019 | 6/24/2019 |
| 8 - Year 6 Monitoring | 5.00% | 5.00% | 491.100 | 0.000 | 491.100 | 2020 | 4/23/2020 |
| 9 - Year 7 Monitoring | 10.00% | | | | | 2021 | |
| Stream Bankfull Standard | 10.00% | 10.00% | 327.400 | 0.000 | 327.400 | 2018 | 4/25/2018 |
| | | | Totals | | 2,946.600 | | |

| | |
|---|-----------|
| Total Gross Credits | 3,274.000 |
| Total Unrealized Credits to Date | 0.000 |
| Total Released Credits to Date | 2,946.600 |
| Total Percentage Released | 90.00% |
| Remaining Unreleased Credits | 327.400 |

| Credit Release Milestone | Riparian Credits | | | | | | |
|---------------------------------|----------------------|---------------------|---------------------|-------------------------|------------------|--------------------------|---------------------|
| | Scheduled Releases % | Proposed Releases % | Proposed Released # | Not Approved # Releases | Approved Credits | Anticipated Release Year | Actual Release Date |
| 1 - Site Establishment | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| 2 - Year 0 / As-Built | 30.00% | 30.00% | 0.840 | 0.000 | 0.840 | 2014 | 7/21/2014 |
| 3 - Year 1 Monitoring | 10.00% | 10.00% | 0.280 | 0.000 | 0.280 | 2015 | 4/23/2015 |
| 4 - Year 2 Monitoring | 10.00% | 10.00% | 0.280 | 0.000 | 0.280 | 2016 | 7/8/2016 |
| 5 - Year 3 Monitoring | 15.00% | 15.00% | 0.420 | 0.420 | 0.000 | 2017 | 4/3/2017 |
| 6 - Year 4 Monitoring | 5.00% | 5.00% | 0.140 | 0.140 | 0.000 | 2018 | 4/25/2018 |
| 7 - Year 5 Monitoring | 15.00% | 15.00% | 0.980 | 0.000 | 0.980 | 2019 | 6/24/2019 |
| 8 - Year 6 Monitoring | 5.00% | 5.00% | 0.140 | 0.000 | 0.140 | 2020 | 4/23/2020 |
| 9 - Year 7 Monitoring | 10.00% | | | | | 2021 | |
| Stream Bankfull Standard | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| | | | Totals | | 2.520 | | |

| | |
|---|--------|
| Total Gross Credits | 2.800 |
| Total Unrealized Credits to Date | 0.000 |
| Total Released Credits to Date | 2.520 |
| Total Percentage Released | 90.00% |
| Remaining Unreleased Credits | 0.280 |

| | | | |
|--------------------------------|---|---------------------------------|-----------------------------|
| Mitigation Project Name | St Clair Creek Restoration Project | USACE Action ID | 2008-02655 |
| DMS ID | 95015 | DWR Permit | 2013-0379 |
| River Basin | Tar-Pamlico | Date Project Instituted | 7/18/2011 |
| Cataloging Unit | 03020104 | Date Prepared | 4/23/2020 |
| County | Beaufort | Stream/Wet. Service Area | Tar-Pamlico 03020104 |

Notes

7/8/2016: IRT approved the release of half of the potential stream credits (scheduled release was 10% of the total stream credits) for Monitoring Year 2

4/3/2017: IRT withheld the release of the wetland credits for Monitoring Year 3.

4/25/2018: IRT withheld the release of the wetland credits for Monitoring Year 4

6/24/2019: IRT approved release of wetland credits for Monitoring Years 3, 4 and 5. Due to concerns on the supper section of UT 2, the IRT withheld the release of Monitoring Year 5 stream credits.

Contingencies (if any)**Project Quantities**

| Mitigation Type | Restoration Type | Physical Quantity |
|-----------------|------------------|-------------------|
| Warm Stream | Restoration | 3,274.000 |
| Riparian | Restoration | 2.800 |

Debits

| | | | | | | | Stream Restoration Credits | Riparian Restoration |
|---|------------|---------|---|----------------|--------------|--------------|----------------------------------|-------------------------|
| Beginning Balance (mitigation credits) | | | | | | | 3,274.000 | 2.800 |
| Released Credits | | | | | | | 2,946.600 | 2.520 |
| Unrealized Credits | | | | | | | 0.000 | 0.000 |
| Owning Program | Req. Id | TIP # | Project Name | USACE Permit # | DWR Permit # | DCM Permit # | | |
| Statewide Stream & Wetland ILF Program | REQ-003055 | R-2510A | DOT - US 17 (Washington Bypass): Second Request | 1999-301143 | 2005-0785 | | 163.700 | |
| Statewide Stream & Wetland ILF Program | REQ-003055 | R-2510A | DOT - US 17 (Washington Bypass): Second Request | 1999-301143 | 2005-0785 | | 491.100 | |
| Statewide Stream & Wetland ILF Program | REQ-003055 | R-2510A | DOT - US 17 (Washington Bypass): Second Request | 1999-301143 | 2005-0785 | | 982.200 | |
| Statewide Stream & Wetland ILF Program | REQ-003055 | R-2510A | DOT - US 17 (Washington Bypass): Second Request | 1999-301143 | 2005-0785 | | 327.400 | |
| Statewide Stream & Wetland ILF Program | REQ-003055 | R-2510A | DOT - US 17 (Washington Bypass): Second Request | 1999-301143 | 2005-0785 | | 491.100 | |
| Statewide Stream & Wetland ILF Program | REQ-006470 | | Woolard-McCoy Project | 2015-01937 | 2015-0929 | 17-16 | | 0.250 |
| NCDOT Stream & Wetland ILF Program | REQ-007731 | B-5302 | Replace Bridge 3 over Norfolk Southern RR | 2018-02324 | | | | 0.750 |
| Total Credits Debited | | | | | | | 2,455.500 | 2.380 |
| Remaining Available balance (mitigation credits) | | | | | | | 491.100 | 0.140 |
| Remaining Credits (Unreleased credits) | | | | | | | 327.400 | 0.280 |

January 25, 2021

Jeremiah Dow
Project Manager
NCDEQ Division of Mitigation Services
1652 Mail Service Center
Raleigh, NC 27699-1652

Subject: Task 13: Response Letter to DMS review comments regarding the Draft Year 7 Monitoring Report for the St. Clair Creek Restoration Project (DMS #95015)
Beaufort County, North Carolina, Cape Fear Basin – CU#03020104, Baker No. 125116

Mr. Dow,

As per your request, please find enclosed one hardcopy of the Final Year 7 Monitoring Report for the St. Clair Creek Restoration Project located in Beaufort County, NC. The final revised digital documents will be sent via a secure ftp link. Our responses to your review comments received on January 8, 2021 are provided below:

1. Digital Files

- a. The following stream features do not match reported lengths in the asset table, and are outlined below as feature length vs. asset table length. Please provide DMS with features that accurately represent the assets reported in the "Restoration Footage or Acreage" column of the asset table.
- UT2: 2,309 vs. 2,133
 - UT3: 1,184 vs. 1,141

Response: Baker has provided the revised stream shapefile as requested.

- b. Please submit a separate stream shapefile that excludes the length of stream no longer receiving credit.

Response: Baker has also included this separate shapefile with the length of upper UT2 removed that has IRT concerned and which was not approved for credit release in MY6.

2. Due to IRT concerns with the upper portions of UT2 an eighth year of monitoring (MY8) is required. DMS recommends requesting permission from the IRT for discontinuation of monitoring vegetation plots, wetland gauges, and UT3 flow gauges since all have met required project success criteria.

Response: Given the IRT's concerns with upper UT2 as previously discussed at the virtual credit release meeting last April, Baker has been preparing for an additional monitoring year (MY8) as stated. Baker would welcome a discontinuation of monitoring on the other features mentioned, which as noted have met the project success criteria, and for which there has been no expressed IRT concern.

If you have any questions or require additional information, please feel free to contact me at 919-219-6339 or via email at Scott.King@mbakerintl.com.

Sincerely,

A handwritten signature in blue ink that reads "Scott King". The signature is written in a cursive style with a light blue shadow effect behind the text.

Scott King, LSS, PWS

St. Clair Creek Restoration Project Year 7 Final Monitoring Report

Beaufort County, North Carolina

DMS Project ID No. 95015

Tar-Pamlico River Basin: 03020104-040040

Report Prepared and Submitted by Michael Baker International

NC Professional Engineering License # F-1084



TABLE OF CONTENTS

| | |
|---|----------|
| 1.0 EXECUTIVE SUMMARY | 1 |
| 2.0 METHODOLOGY | 3 |
| 2.1 Stream Assessment – Reaches UT2 and UT3 | 3 |
| 2.1.1 Hydrology | 3 |
| 2.1.2 Photographic Documentation | 3 |
| 2.2 Wetland Assessment | 4 |
| 2.2.1 Wetlands Modifications Review | 4 |
| 2.3 Vegetation Assessment | 5 |
| 2.3.1 Vegetation Concerns | 5 |
| 3.0 REFERENCES | 5 |

APPENDICES

| | |
|-------------------|---|
| Appendix A | <i>Project Vicinity Map and Background Tables and Files</i> |
| Figure | 1 Vicinity Map and Directions |
| Table | 1 Project Components and Mitigation Credits |
| Table | 2 Project Activity and Reporting History |
| Table | 3 Project Contacts Table |
| Table | 4 Project Attribute Table |
| | Site Viability for Buffer Mitigation memo (1/7/16) |
| | IRT Field Meeting Minutes (5/16/19) |
| Appendix B | <i>Visual Assessment Data</i> |
| Figure | 2 Current Condition Plan View (CCPV) |
| Table | 5a Visual Stream Morphology Stability Assessment |
| Table | 5b Stream Problem Areas (SPAs) |
| Table | 6a Vegetation Condition Assessment |
| Table | 6b Vegetation Problem Areas (VPAs) |
| | Stream Photo Points |
| | Vegetation Plot Photos |
| | Hydrology Monitoring Stations |
| Appendix C | <i>Vegetation Plot Data</i> |
| Table | 7 Vegetation Plot Criteria Attainment |
| Table | 8 CVS Vegetation Metadata |
| Table | 9a CVS Stem Count of Planted Stems by Plot and Species |
| Table | 9b Stem Count for All Species (Planted and Volunteer) Arranged by Plot |
| Table | 9c Yearly Density by Plot |
| Table | 9d Vegetation Summary and Totals |

Appendix D *Hydrologic Data*

| | | |
|---|----|---|
| Table | 10 | Wetland Restoration Well Success |
| Figure | 3 | Wetland Gauge Graphs |
| Table | 11 | Flow Gauge Success |
| Figure | 4 | Flow Gauge Graphs |
| Figure | 5 | St. Clair Creek Observed Rainfall versus Historic Average |
| Channel Cross-Section Analysis for UT2 Flow | | |

1.0 EXECUTIVE SUMMARY

Michael Baker Engineering, Inc. (Baker) restored 3,274 linear feet of perennial and intermittent headwater stream, 2.8 acres of riparian wetlands, and planted 17.5 acres of native riparian vegetation within the entire conservation easement along two unnamed tributaries (UT2 and UT3) to St. Clair Creek in Beaufort County, North Carolina (NC) (Figure 1). The St. Clair Creek Restoration Project (Site) is located in Beaufort County, approximately five miles east of the Town of Bath. The Site is located in the NC Division of Water Resources (NCDWR) subbasin 03-03-07 and the NC Department of Environmental Quality (NC DEQ) Division of Mitigation Services (DMS) Targeted Local Watershed (TLW) 03020104-040040 of the Tar-Pamlico River Basin. The project involved the restoration of a Coastal Plain Headwater Small Stream Swamp system (Schafale and Weakley 1990) from impairments within the project area due to past agricultural conversion and silviculture.

The primary restoration goals of the project were to improve ecological functions to the impaired areas within the Tar-Pamlico River Basin as described below:

- Create geomorphically stable conditions along the unnamed tributaries across the project,
- Implement agricultural BMPs to reduce nonpoint source inputs to the downstream estuary,
- Protect and improve water quality by reducing nutrient and sediment inputs,
- Restore stream and wetland hydrology by connecting historic flow paths and promoting natural flood processes, and
- Restore and protect riparian buffer functions and corridor habitat in perpetuity by establishing a permanent conservation easement.

To accomplish these goals, the following objectives were identified:

- Restore existing channelized streams by restoring the relic headwater valley and allowing diffuse flow, providing the streams access to their floodplains,
- Increase aquatic habitat value by allowing natural microtopography to form,
- Plant native species riparian buffer vegetation within the headwater valley and floodplain areas, and within the wetland areas, protected by a permanent conservation easement, to increase stormwater runoff filtering capacity, decrease erosion, and shade the stream to decrease water temperature,
- Improve aquatic and terrestrial habitat through improved substrate and in-stream cover, addition of woody debris, and reduction of water temperature, and
- Control invasive species vegetation within the project area and if necessary continue treatments during the monitoring period.

During Year 7 monitoring, the planted acreage performance categories were functioning at 100 percent with no bare areas or low stem density areas to report. The average density of total planted stems, based on data collected from the nine monitoring plots during Year 7 monitoring, is 594 stems per acre. Thus, the Year 7 data demonstrate that the Site has met the final success criteria of 210 stems per acre.

During the previous Year 7 monitoring, *Pinus taeda* (loblolly pine) saplings were thinned throughout the buffer on UT2, in particular in the middle and upper sections. However, during Year 7 monitoring, new, rapidly growing loblolly pine seedlings and short saplings were again found scattered throughout the riparian buffer of the UT2 area. It should be noted that the pines do not appear to be suppressing planted species survival or

growth as vegetation density appears strong throughout the project, even in areas with pine presence. Nevertheless, these pines will again be treated and heavily thinned during the winter or spring of 2021 prior to any IRT site closeout visits using hand/power tools and/or chemical applications. The project will continue to be observed for pine growth throughout the remaining monitoring period.

Year 7 wetland groundwater monitoring demonstrated that all 8 of the groundwater monitoring wells located in the wetland credited areas along UT2 and UT3 met the success criteria by recording water levels within 12 inches of the ground surface for a consecutive period greater than 12% of the growing season (33 days for the Site). The Year 7 hydroperiods ranged from 15.6% to 26.6%. All of the wells passed the success criteria early in the year, just after the growing season began. All wetland restoration well data and reference well data collected during Year 7 monitoring are located in Appendix D.

Additionally, there are two groundwater monitoring wells (SCAW9 and SCAW10) installed on 3/16/17 in areas located outside the project's currently approved mitigation plan wetland restoration areas. Well SCAW9 met the 12% hydroperiod success criteria with 17.7%, though SCAW10 did not with only 7.8%. Both well locations certainly appear quite wet. Please note these areas are not being requested for any credits of any kind at this time. Baker is simply conducting exploratory monitoring within *potential* future wetland restoration areas. The three potential areas total 1.1 acres and are all located outside the 50 ft buffer from the stream channel but within the conservation easement (see Figure 2 in Appendix B). Baker is not presenting this information here for formal approval or acceptance, but to simply inform DMS and the IRT of all project activity.

On-site flow through the restored headwater valleys of UT2 and UT3 was recorded through the use of seven installed pressure transducers as flow gauges. Each one met the success criteria in Year 7 by recording a consecutive flow event of 30 days or longer in 2020. Of note, Flow gauge SCFL#4 located at the top of UT2 met the success criteria, recording its longest single duration flow event of 45 days in February and March. This is of particular significance as flow in the upper portion of UT2 and the results of Flow Gauge #4 have been the subject of IRT concern in the past. The flow gauge success summary Table 11 and all individual flow gauge graphs are found in Appendix D.

Additionally, during MY7 two cross-section transects were conducted in the upper portion of Reach UT2 to help demonstrate flow and channel formation. Please see the Memorandum included in Appendix D for more details.

In addition, currently contracted riparian buffer credits have been included as part of the project as referenced by the "Site Viability for Buffer Mitigation" memo from Karen Higgins (NCDWR) dated 1/7/16 and included as an asset in this report (as found in Appendix A). As part of the St. Clair Creek Restoration project, Riparian Buffer credits in excess of the contracted 6.8 acres (296,208 square feet) will be provided. Monitoring for success of riparian buffers will continue to follow the existing vegetation monitoring protocol and success criteria as stated in the approved mitigation plan for stream and wetland vegetation success. Only vegetation plots 1-6 are located within the approved buffer credit areas and no additional vegetation monitoring plots are required to monitor buffer success as these existing plots serve to monitor the success of the vegetation of the headwater coastal plain stream and the associated riparian buffer. The Year 7 monitoring results demonstrate that the site has met the success criteria requirements for Riparian Buffer credits in each of vegetation plots 1-6 as described in the buffer memo, and with an overall average density of 492 stems/acre.

Summary information/data related to the Site and statistics related to performance of various project and monitoring elements can be found in the tables and figures in the report Appendices. Narrative background and supporting information formerly found in these reports can be found in the Baseline Monitoring Report and in the Mitigation Plan available on the North Carolina Division of Mitigation Services (NCDMS) website. All raw data supporting the tables and figures in the Appendices are available from NCDMS upon request.

2.0 METHODOLOGY

The seven-year monitoring plan for the Site includes criteria to evaluate the success of the stream, wetland and vegetation components of the project. The methodology and report template used to evaluate these components adheres to the NCDMS monitoring guidance document dated 11/7/11, which will continue to serve as the template for subsequent monitoring years. The specific locations of monitoring features, such as vegetation plots, flow gauges and wells are shown on the CCPV sheets found in Appendix B.

The growing season for the Beaufort County ends on December 6th, and the final well and flow data were collected on 12/10/20. The visual site assessment data contained in Appendix B were also collected in December 2020 as noted.

2.1 Stream Assessment – Reaches UT2 and UT3

The UT2 and UT3 mitigation approach involved the restoration of historic flow patterns and flooding functions in a multi-thread headwater stream system, monitoring efforts will focus on visual observations to document stability and the use of water level monitoring gauges to document saturation and flooding functions. The methods used and any related success criteria are described below for each parameter. Monitoring efforts focus on visual observations and in-channel flow gauges/pressure transducers to document stream success.

As-built Stream survey data was collected to a minimum of Class C Vertical and Class A Horizontal Accuracy using Leica TS06 Total Station and was georeferenced to the NAD83 State Plane Coordinate System, FIPS3200 in US Survey Feet, which was derived from the As-built Survey. This survey system collects point data with an accuracy of less than one tenth of a foot.

2.1.1 Hydrology

Total observed area rainfall for the previous 12-month period from December 2019 through November 2020 was 60.5 inches, as compared to the Beaufort County WETS table for the same period of 50.0 inches annually (see Figure 5 in Appendix D).

Four automated flow gauges (pressure transducers) were originally installed in the UT2 channel along with two flow gauges installed in the UT3 channel. The gauges were installed approximately 500 feet apart within the restored systems to document flow duration. Additionally, a fifth flow gauge (SCFL#7) was installed approximately halfway between SCFL#4 and SCFL#3 on 6/6/18 in the upper portion of UT2. As stated in the mitigation plan, annual success criteria are considered to have been met if 30 consecutive days of flow were observed at any point during the monitoring year, with two such 30-day flow events having been documented in separate monitoring years. The individual flow gauge graphs and the flow gauge success summary Table 11 are all located in Appendix D.

Additionally, during MY7 two cross-section transects were conducted in the upper portion of Reach UT2 to help demonstrate flow and channel formation. Please see the Memorandum included in Appendix D for more details.

2.1.2 Photographic Documentation

The reaches were photographed longitudinally beginning at the downstream end of both reaches, moving upstream to the beginning of each reach. Photographs were taken looking at established locations throughout the restored stream valley. Points were close enough together to provide an overall view of the reach lengths and valley crenulations. Photographs of the stream photo points, wetland wells, and flow gauges are all located in Appendix B.

2.2 Wetland Assessment

Wetland monitoring is conducted using eight automated groundwater-monitoring stations that are installed within the UT-2 and UT-3 wetland restoration areas, as well as two additional reference wells installed in the downstream portion of the UT-3 wetland restoration area. Installation of these groundwater monitoring stations follow Corps of Engineers Wetlands Research Program Technical Note VN-rs-4.1 (USACE 1997) and the water table monitoring standards follow Technical Note ERDC TN-WRAP-05-2 (USACE 2005). All wetland restoration well data collected during Year 7 monitoring are located in Appendix D.

The automated loggers are programmed to collect data to document groundwater levels in the restored wetland areas. The success criteria for wetland hydrology are considered to have been met when the site has groundwater within 12 inches of the soil surface for a consecutive number of days equal to a minimum of 12% of the growing season. For Beaufort County, the growing season is from February 28 to December 6 (282 days), so 12% is a minimum of 33.8 consecutive days for the Site.

It should also be noted that while the success criteria stated in the mitigation plan for wetland hydroperiod is 12%, the 10/24/16 Wilmington District Stream and Wetland Compensatory Mitigation Update document states that for the Tomotley soils series (which is mapped on the project site) the wetland hydroperiod range is 10% to 12%.

Two more groundwater monitoring wells (SCAW9 and SCAW10) were installed on 3/16/17 in areas located outside the project's currently approved mitigation plan wetland restoration areas (see Figure 2 in Appendix B). Please note these areas are not being requested for any credits of any kind at this time. Baker is simply conducting exploratory monitoring in potential future wetland restoration areas. The three potential areas total 1.1 acres and are all located outside the 50 ft buffer from the stream channel but within the conservation easement. Baker is not presenting this information here for formal approval or acceptance, but simply wishes to inform NCDMS and the IRT of all project activity.

Additionally, during Year 7 monitoring, the connection pins on the wetland reference well SCAWREF2 degraded to the point where Baker was unable to connect and download the device. It has been sent to the manufacturer (In-Situ) for their processing.

2.2.1 Wetlands Modifications Review

A brief summary of previous wetlands modifications is presented here as a review of relevant project history. A more detailed description of this work was presented in the Year 3 report.

In the fall of 2015, the restoration site landowner cut a network of drainage ditches adjacent to the easement boundaries of both UT2 and UT3 with the intent to drain water away from his nearby pine plantation. The work was implemented without the knowledge of Baker and was discovered in the fall of 2015 during monitoring activities. To help remedy the situation, Baker oversaw three areas of drainage modifications to the project in March of 2016: 1) Three French drains were installed under the farm road along the northern portion of UT2 and were linked to wide, shallow swales cut into the buffer to reconnect water flow from the adjacent landowner's field that routinely ponded water behind the road. 2) The drainage ditch running parallel to the easement boundary along the western portion of UT2 was filled, and three wide, shallow swales were cut to connect the existing drainages within the pine plantation to the project wetlands and buffer. 3) The drainage ditch running parallel to the easement boundary along the western edge of UT3 was filled, and a shallow swale was cut to connect drainage from the pine plantation into an existing shallow depression located within the existing wetland.

It was observed during the Year 7 monitoring that diffuse flow does move through all of the installed swales, and all remain stable and vegetated. Additional groundwater monitoring wells 5-8 were installed in April of 2016 specifically to observe the wetland restoration areas potentially affected by these modifications. The locations of this previous work are provided in Figure 2 in Appendix B.

2.3 Vegetation Assessment

In order to determine if the criteria are achieved, vegetation-monitoring quadrants were installed and are monitored across the restoration site in accordance with the CVS-NCDMS Protocol for Recording Vegetation, Version 4.1 (Lee 2007) and the CVS-NCDMS data entry tool v 2.3.1 (CVS 2012). The vegetation monitoring plots are a minimum of 2 percent of the planted portion of the Site with nine plots established randomly within the Site's planted riparian buffer areas per Monitoring Levels 1 and 2. The sizes of individual quadrants are 100 square meters for woody tree species.

Complete Year 7 vegetation assessment information is provided in Appendix C.

2.3.1 Vegetation Concerns

During Year 7 monitoring, *Pinus taeda* (loblolly pine) seedlings and short saplings were again found scattered throughout the riparian buffer of the UT2 restoration area. It should be noted that the pines do not appear to be suppressing planted species survival or growth as vegetation density appears strong throughout the project, even in areas with pine presence. However, these pines will be treated and thinned again during the winter and/or spring of 2021 using hand/power tools and/or chemical applications. The entire project will continue to be closely observed for pine growth throughout the remaining monitoring period.

3.0 REFERENCES

Carolina Vegetation Survey (CVS) and NC Division of Mitigation Services (DMS). CVS-DMS Data Entry Tool v. 2.3.1. University of North Carolina, Raleigh, NC. 2012.

Lee, M., Peet R., Roberts, S., Wentworth, T. 2007. CVS-DMS Protocol for Recording Vegetation, Version 4.1.

North Carolina Division of Mitigation Services (DMS). 2011. Monitoring Requirements and Performance Standards for Stream and/or Wetland Mitigation. November 7, 2011.

Schafale, M. P., and A. S. Weakley. 1990. Classification of the natural communities of North Carolina, Third Approximation. North Carolina Natural Heritage Program. Division of Parks and Recreation, NC DEQ. Raleigh, NC.


United States Army Corps of Engineers. 1997. Corps of Engineers Wetlands Research Program. Technical Note VN-rs-4.1. Environmental Laboratory. U.S. Army Engineer Waterways Experiment Station. Vicksburg, MS.

_____. 2005. "Technical Standard for Water-Table Monitoring of Potential Wetland Sites," WRAP Technical Notes Collection (ERDC TN-WRAP-05-2), U.S. Army Engineer Research and Development Center. Vicksburg, MS.

Appendix A

Project Vicinity Map and Background Tables and Files

The subject project site is an environmental restoration site of the NCDEQ Division of Mitigation Services (DMS) and is encompassed by a recorded conservation easement, but is bordered by land under private ownership. Accessing the site may require traversing areas near or along the easement boundary and therefore access by the general public is not permitted. Access by authorized personnel of state and federal agencies or their designees/contractors involved in the development, oversight and stewardship of the restoration site is permitted within the terms and timeframes of their defined roles. Any intended site visitation or activity by any person outside of these previously sanctioned roles and activities requires prior coordination with DMS.




Project Location

Site Directions
 To access the site from Raleigh, follow Interstate 40 southeast and take the NC Highway 24 Exit East/NC Highway 903 North, Exit 373 toward Kenansville and Magnolia. From Exit 373, continue on the Kenansville Bypass for 6 miles before turning right onto NC Highway 24 East. After turning right onto NC Highway 24 (Beulaville Highway), continue for 23 miles before turning left onto US Highway 258 (Kinston Highway). Once on US Highway 258, travel for approximately 1.2 miles before turning right onto Warren Taylor Road. Then proceed 0.5 miles and turn left while heading north through a large field. The site is located where the farm road intersects UT to Mill Swamp at a downstream culvert crossing.

Note: Site is located within targeted local watershed 03020104040040.



Beaufort County




Project Location

Figure 1
Project Vicinity Map
St. Clair Creek Restoration Site

NCDEQ -
 Division of Mitigation Services

Michael Baker
 INTERNATIONAL



| Table 1. Project Components and Mitigation Credits | | | | | | | | |
|--|--------------------------|---------------------------|--------------|---------------------------|-------------------------------------|--------------------------------|--------------------------|----------------------------|
| St. Clair Creek Restoration Project: DMS Project No ID. 95015 | | | | | | | | |
| Mitigation Credits | | | | | | | | |
| | Stream | Riparian Wetland | | Non-riparian Wetland | | Buffer | Nitrogen Nutrient Offset | Phosphorus Nutrient Offset |
| Type | R | R | RE | | | | | |
| Totals | 2,946.6 SMU / 327.4 SMU* | 2.8 WMU | 0 | | | 363,577 BMU | | |
| Project Components | | | | | | | | |
| Project Component or Reach ID | Stationing/ Location | Existing Footage/ Acreage | | Approach | Restoration/ Restoration Equivalent | Restoration Footage or Acreage | Mitigation Ratio | |
| UT2 Stream | 12+64 – 34+00 | 2,660 LF | | Headwater Restoration | 1,805.6 SMU / 327.4 SMU* | 2,133 LF | 1:1 | |
| UT3 Stream | 10+66 – 22+82 | 1,075 LF | | Headwater Restoration | 1,141 SMU | 1,141 LF | 1:1 | |
| UT2 Wetland | See plan sheets | 0.0 AC | | Restoration | 1.1 WMU | 1.1 WMU | 1:1 | |
| UT3 Wetland | See plan sheets | 0.0 AC | | Restoration | 1.7 WMU | 1.7 WMU | 1:1 | |
| UT2 Buffer | 12+64 – 34+00 | NA | | Restoration | 363,577 BMU | 8.3 AC | 1:1 | |
| Component Summation | | | | | | | | |
| Restoration Level | Stream (LF) | Riparian Wetland (AC) | | Non-riparian Wetland (AC) | Buffer (ft ²) / (AC) | Upland (AC) | | |
| | | Riverine | Non-Riverine | | | | | |
| Restoration | 3,274 | 2.8 | | | | | | |
| Enhancement I | | | | | | | | |
| Enhancement II | | | | | | | | |
| Creation | | | | | | | | |
| Preservation | | | | | | | | |
| High Quality Preservation | | | | | | | | |
| Buffer Zone A: 0-50 ft | | | | | 226002 / 5.2 | | | |
| Buffer Zone B: 51-100 ft | | | | | 137575 / 3.1 | | | |
| BMP Elements | | | | | | | | |
| Element | Location | Purpose/Function | | Notes | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| BMP Elements: BR= Bioretention Cell; SF= Sand Filter; SW= Stormwater Wetland; WDP= Wet Detention Pond; DDP= Dry Detention Pond; FS= Filter Strip; S= Grassed Swale; LS= Level Spreader; NI=Natural Infiltration Area | | | | | | | | |

*The SMU credits shown here differ from those presented in previous monitoring reports. They have been reduced by 327.4 SMU that have been deemed potentially at-risk in the uppermost section of Reach UT2.

| Table 2. Project Activity and Reporting History | | | |
|--|-----------------------------|---------------------------------|--------------------------------------|
| St. Clair Creek Restoration Project: DMS Project No ID. 95015 | | | |
| Activity or Report | Scheduled Completion | Data Collection Complete | Actual Completion or Delivery |
| Mitigation Plan Prepared | N/A | N/A | Jul-13 |
| Mitigation Plan Amended | N/A | N/A | Sep-13 |
| Mitigation Plan Approved | N/A | N/A | Oct-13 |
| Final Design – (at least 90% complete) | N/A | N/A | Nov-13 |
| Construction Begins | N/A | N/A | Dec-13 |
| Permanent seed mix applied to entire project area | N/A | N/A | Mar-14 |
| Planting of live stakes | N/A | N/A | N/A |
| Planting of bare root trees | N/A | N/A | Apr-14 |
| End of Construction | N/A | N/A | Apr-14 |
| Survey of As-built conditions (Year 0 Monitoring-baseline) | N/A | May-14 | Jun-14 |
| | | | |
| Year 1 Monitoring (2014) | Nov-14 | Dec-14 | Dec-14 |
| Year 2 Monitoring (2015) | Nov-15 | Nov-15 | Mar-16 |
| Year 3 Monitoring (2016) | Nov-16 | Dec-16 | Jan-17 |
| Pines thinned in Upper UT2 | March 2016 | | |
| Ditches cut by landowner adjacent to easement were filled and new swales cut to connect drainage onto project. | Conducted in March 2016 | | |
| Additional groundwater wells #5-8 installed within credited area near newly cut swales. | Installed in April 2016 | | |
| Year 4 Monitoring (2017) | Nov-17 | Dec-17 | Jan-18 |
| Additional groundwater wells #9 and #10 installed in non-credited areas. | Installed in March 2017 | | |
| Pines thinned in Upper UT2 and UT3. Privet treated on Upper UT2 | May 2017 | | |
| Year 5 Monitoring (2018) | Nov-18 | Jan-19 | Jan-19 |
| Additional flow gauge #7 installed | Installed in June 2018 | | |
| Year 6 Monitoring (2019) | Nov-19 | Dec-19 | Jan-20 |
| Supplemental planting in Upper UT2 | February 2019 | | |
| Pines thinned in Upper UT2 | April 2019 | | |
| Year 7 Monitoring (2020) | Nov-20 | Dec-20 | Jan-21 |
| Pines thinned in Upper UT2 | May and December 2020 | | |

| Table 3. Project Contacts Table | |
|--|--|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | |
| Designer | |
| Michael Baker International | 8000 Regency Parkway, Suite 600 Cary, NC 27518 <u>Contact:</u> Katie McKeithan, Tel. 919-481-5703 |
| Construction Contractor | |
| KBS Earthworks | 5616 Coble Church Rd Julian, NC 27283 <u>Contact:</u> Chris Sizemore, Telephone: 336-362-0289 |
| Planting Contractor | |
| KBS Earthworks | 5616 Coble Church Rd Julian, NC 27283 <u>Contact:</u> Chris Sizemore, Telephone: 336-362-0289 |
| Seeding Contractor | |
| KBS Earthworks | 5616 Coble Church Rd Julian, NC 27283 <u>Contact:</u> Chris Sizemore, Telephone: 336-362-0289 |
| Seed Mix Sources | Green Resources, Tel. 336-855-6363 |
| Nursery Stock Suppliers | Mellow Marsh Farm, 919-742-1200 ArborGen, 843-528-3204 Superior Tree, 850-971-5159 |
| Monitoring Performers | |
| Michael Baker International | 8000 Regency Parkway, Suite 600 Cary, NC 27518 <u>Contact:</u> |
| Stream Monitoring Point of Contact | Scott King, Tel. 919-481-5731 |
| Vegetation Monitoring Point of Contact | Scott King, Tel. 919-481-5731 |
| Wetland Monitoring Point of Contact | Scott King, Tel. 919-481-5731 |

Table 4. Project Attributes

St. Clair Creek Restoration Project: DMS Project ID No. 95015

| Project Information | | | |
|---|--|---|------------------------------------|
| Project Name | St. Clair Creek Restoration Project | | |
| County | Beaufort | | |
| Project Area (acres) | 17.5 | | |
| Project Coordinates (latitude and longitude) | 35.452835 N, -76.76726215 W | | |
| Watershed Summary Information | | | |
| Physiographic Province | Outer Coastal Plain | | |
| River Basin | Tar-Pamlico | | |
| USGS Hydrologic Unit 8-digit and 14-digit | 03020104 / 03020104040040 | | |
| DWQ Sub-basin | 03 03 07 | | |
| Project Drainage Area (AC) | 89 (UT2), 30 (UT3) | | |
| Project Drainage Area Percentage of Impervious Area | <1% | | |
| CGIA Land Use Classification | 3.02, Passively Managed Forest Stands, 2.01.01.07, Annual Row Crop Rotation; | | |
| Stream Reach Summary Information | | | |
| Parameters | Reach UT2 | Reach UT3 | |
| Length of Reach (LF) | 2,133 (proposed) 2,660 (existing) | 1,141 (proposed) 1,075 (existing) | |
| Valley Classification (Rosgen) | X | X | |
| Drainage Area (AC) | 89 | 30 | |
| NCDWQ Stream Identification Score | 36 | 20 | |
| NCDWQ Water Quality Classification | C; Sw, NSW | C; Sw, NSW | |
| Morphological Description (Rosgen stream type)* | Channelized Headwater System (Perennial) | Channelized Headwater System (Intermittent) | |
| Evolutionary Trend ** | Restored G | Restored G | |
| Underlying Mapped Soils | To, Hy, Ro | To, At | |
| Drainage Class | Very poorly drained, poorly drained | Poorly drained, somewhat poorly drained | |
| Soil Hydric Status | Hydric | Hydric | |
| Average Channel Slope (ft/ft) | 0.0006 | 0.0009 | |
| FEMA Classification | SFHA, AE | SFHA, AE | |
| Native Vegetation Community | Coastal Plain Small Stream Swamp | Coastal Plain Small Stream Swamp | |
| Percent Composition of Exotic/Invasive Vegetation | <5% | <5% | |
| Wetland Summary Information | | | |
| Parameters | Wetland Along UT2 | | |
| Size of Wetland (AC) | 1.1 | | |
| Wetland Type | Riparian Riverine | | |
| Mapped Soil Series | To – Tomotley fine sandy loam | | |
| Drainage Class | Poorly drained | | |
| Soil Hydric Status | Hydric | | |
| Source of Hydrology | Groundwater | | |
| Hydrologic Impairment | Disconnected floodplain from ditches, lowered water table | | |
| Native Vegetation Community | Coastal Plain Small Stream Swamp | | |
| Percent Composition of Exotic/Invasive Vegetation | <5% | | |
| Parameters | Wetland Along UT3 | | |
| Size of Wetland (AC) | 1.7 | | |
| Wetland Type | Riparian Riverine | | |
| Mapped Soil Series | To – Tomotley fine sandy loam | | |
| Drainage Class | Poorly drained | | |
| Soil Hydric Status | Hydric | | |
| Source of Hydrology | Groundwater | | |
| Hydrologic Impairment | Disconnected floodplain from ditches, lowered water table | | |
| Native Vegetation Community | Coastal Plain Small Stream Swamp | | |
| Percent Composition of Exotic/Invasive Vegetation | <5% | | |
| Regulatory Considerations | | | |
| Regulation | Applicable | Resolved | Supporting Documentation** |
| Waters of the United States – Section 404 | Yes | Yes | (Appendix B) |
| Waters of the United States – Section 401 | Yes | Yes | (Appendix B) |
| Endangered Species Act | No | N/A | Categorical Exclusion (Appendix B) |
| Historic Preservation Act | No | N/A | Categorical Exclusion (Appendix B) |
| Coastal Zone Management Act (CZMA)/ Coastal Area Management Act (CAMA) | No | N/A | Categorical Exclusion (Appendix B) |
| FEMA Floodplain Compliance | Yes | Yes | (Appendix B) |
| Essential Fisheries Habitat | No | N/A | Categorical Exclusion (Appendix B) |
| Notes: | | | |
| * Due to its channelized nature, the stream would most appropriately be classified as a Rosgen G stream type but use of this classification system on this channel is questionable due to its highly altered state. ** Supporting documentation is including in the approved Final Mitigation Plan. | | | |



PAT MCCRORY

Governor

DONALD R. VAN DER VAART

Secretary

S. JAY ZIMMERMAN

Director

January 7, 2016

Kristin Miguez
DEQ-Division of Mitigation Services
1652 Mail Service Center
Raleigh, NC 27699-1652
(via electronic mail)

DWR# 2013-0739

Re: Site Viability for Buffer Mitigation – St. Clair Creek Headwater Stream Site
off Peoples Road, Bath, NC
Beaufort County

Dear Ms. Miguez,

On October 5, 2015, Katie Merritt, with the Division of Water Resources (DWR), received a request from Jake Byers with Michael Baker Engineering, for a site visit at the St. Clair Creek Restoration Site located off Peoples Road in Bath, NC to determine the potential for Tar-Pamlico Neuse riparian buffer mitigation. On December 3, 2015, Ms. Merritt performed a site assessment of the subject site. Karen Higgins and Mac Haupt with the DWR along with you and Mr. Byers were also present. If approved, mitigating this site could provide riparian buffer mitigation credits within the 8-digit Hydrologic Unit Code 03020104 of the Tar-Pamlico River Basin and as allowed under 15A NCAC 02B .0295 (f).

Ms. Merritt's evaluation of the site as an alternative buffer mitigation option for buffer mitigation pursuant to Rule 15A NCAC 02B .0295 (o) (1) and (2) (effective November 1, 2015) is provided below:

UT2

- UT2 was approved as part of a Coastal Headwater Stream Mitigation Site (DWR# 2013-0739) by the IRT in 2013 and is in its second year of monitoring. A copy of the approved mitigation plan has been provided to the DWR.
- Preliminary site conditions along with the onsite visit in December 2015 suggests that the entire area along UT2 (0-100') is viable for riparian restoration and suitable for buffer mitigation credit at 1:1. Preliminary photos and documentation have been provided to the DWR.
- The buffer must be measured perpendicular to the length of the valley being restored. Approximately 8.35 acres (363,577 ft²) have been planted and restored. A copy of the proposed restoration site has been provided to DWR.
- An agricultural ditch is present within the proposed riparian restoration and isn't planned to be removed. The presence of this ditch does not comply with the diffuse flow requirement of Rule .0295. However, DMS can apply Clarification Memo #2008-019 to

this project in order to calculate the deduction of buffer credit where diffuse flow cannot be attained.

- According to the St. Clair Creek Restoration Project Year 1 Monitoring Report submitted in April 2015, all 6 vegetative monitoring plots within the riparian areas are meeting the success criteria identified in Rule .0295. A copy of the Year 1 Monitoring Report has been provided to the DWR.
- A conservation easement of the proposed area, dated June 24th, 2013 has been provided to the DWR and is more accurately described as CE-1 and containing 11.55 acres, more or less. The easement document is located in the Beaufort County Register of Deeds, Book 1821, Pages 53-64.

A map showing the project site and the buffer mitigation areas assessed is provided and signed by Ms. Merritt on January 6, 2016. DWR did not assess this site for viability of nutrient offset and therefore only buffer mitigation is approved. DMS shall provide an annual monitoring report to Ms. Merritt for review and approval each year for four more years and until the performance standards have been met. The performance standards for buffer mitigation under Rule .0295 are the following:

(n) (2) (B) - A minimum of four native hardwood tree species or four native hardwood tree and native shrub species, where no one species is greater than 50 percent of the stems.

(o) (2) -All success criteria specified in the approval of the stream mitigation site by the Division shall be met.

Please provide an As-Built survey verifying the acreage proposed for buffer mitigation credit and a buffer credit ledger for this site to Ms. Merritt within 30 days from receipt of this letter. If you have any questions regarding this correspondence contact Katie Merritt at (919)-807-6371.

Sincerely,



Karen Higgins, Supervisor
401 and Buffer Permitting Unit

KAH/km

Attachments: Site Aerial Map, DWR Clarification Memo #2008-019

cc:File Copy (Katie Merritt)

Conservation Easement

Vegetation Plots

Coastal Headwater Stream Design

Buffer Zone A: 0-50 ft (226,002 ft² or 5.2 ac; 1:1 ratio = 226,002 BMUs)
Buffer Zone B: 51-100 ft (137,575 ft² or 3.1 ac; 1:1 ratio = 137,575 BMUs)

UT2

Ditch/non-diffuse flow

Wetland Area
1.1 acres

Not for buffer credit

Kym
1/16/2015

Aerial Photo Date: 2012

NC OneMap. NC Center for Geographic Information and Analysis, NC 941 Board

Michael Baker
INTERNATIONAL

Buffer Asset Map
St. Clair Creek Site
Beaufort County, NC



Michael F. Easley
Governor

William G. Ross, Jr., Secretary
Department of Environment and Natural Resources

Coleen, H. Sullins, Director
Division of Water Quality

August 19, 2008
Buffer Interpretation/Clarification #2008-019

MEMORANDUM

Re: The Division of Water Quality's (DWQ's) stance on whether diffuse flow of stormwater through the newly restored buffers on mitigation sites should be a requirement. Diffuse flow is a requirement for buffer restoration or enhancement in the Neuse River Basin Buffer Rule 15A NCAC 02B.0242(9)(d)(iii), the Tar-Pamlico River Basin Buffer Rule 15A NCAC 02B.0260(9)(d)(iii), and the Catawba River Basin Buffer Rule 15A NCAC 02B.0244 (9)(d)(iii).

Diffuse flow is a requirement for all sites in a buffered basin for buffer mitigation and for sites providing nutrient offset credit as well.


Current Policy: According to the Mitigation rules in the Neuse, Tar-Pamlico and Catawba buffer rules, a grading plan must be provided for buffer mitigation sites. In addition, those rules state that "The site shall be graded in a manner to ensure diffuse flow through the riparian buffer".

Problem: The question has been raised as to whether stormwater carried by lateral ditches that enter buffered streams should provide diffuse flow prior to that stormwater entering the restored buffers.

Solution: The Neuse, Tar-Pamlico and Catawba buffer rules with respect to buffer mitigation sites contain a very clear requirement that states that diffuse flow of stormwater must be maintained through the buffer. Unless otherwise approved by DWQ, all buffer mitigation sites must provide diffuse flow of stormwater from ditches and similar conveyances through the restored buffer.

Where such diffuse flow cannot be attained and where DWQ agrees that such treatment is not possible, deduction of buffer credit will be calculated as follows:

SCENARIO 1



A, B and C are angles. a, b, and c are distances (lengths)

DWQ believes that using an immediate drainage area extending at a 60-degree angle from the point of discharge to the stream is a reasonable approach to the issue of determining the area which is not draining through the restored buffer. To calculate the area of buffer being "short-circuited" by the ditch, the area of the right triangles shown in the figure above must be determined.

$$\begin{aligned} a &= 50' \\ A &= 30^\circ \\ B &= 60^\circ \end{aligned}$$

$$\begin{aligned} b &= a \cot A \\ b &= 50 (1.732) \\ b &= 86.6' (87') \end{aligned}$$


The area to be excluded from credit would be the area of the two right triangles:

$$\begin{aligned} \text{Area} &= (a \times b)/2 \\ \text{Area} &= (50 \text{ feet} \times 87 \text{ feet})/2 \\ \text{Area} &= 2,175 \text{ SF} \end{aligned}$$

Total deducted area = $2,175 \times 2 = 4,350 \text{ SF}$ or 0.1 acres.


The example shown above assumes a buffer width of 50 feet from the top of bank (riparian buffer mitigation site). For nutrient offset sites, credit can be generated out to 200 feet from the top of bank. The policy applies to sites with larger buffers as follows:

SCENARIO 2




If a ditch leading to a buffered stream is buffered, then no credit is deducted from the stream buffer. If the upstream origin of the ditch is within the buffer, no credit is deducted. If the upstream origin of the ditch is not buffered (e.g. if the ditch begins upstream offsite), the credit deduction is applied to the most upstream portion of the ditch on the property.

SCENARIO 3



Where a network of interconnecting ditches occurs on a site, and all of the ditches are buffered, the only credit deduction would be at the point where an unbuffered ditch enters the project:


SCENARIO 4



One
North Carolina
Naturally

Where a natural stream enters the project site, no deduction of credit will occur. Also, when a natural stream or a modified natural stream flow into a buffered stream, no deduction of credit will occur. The modified natural stream must be subject to the buffer rules, and must be verified to be a modified natural stream (as opposed to a ditch) through an on-site determination by DWQ personnel.

SCENARIO 5



For any additional questions or clarifications on this issue, please contact Eric Kulz or Amy Chapman at (919) 733-1786.

Signature: Matt Matthews Date: 8/19/2008

Signature: Paul Ross Date: 8/19/2008

Meeting Minutes

St. Clair RESTORATION PROJECT

DMS Project ID. 95015
DWR Project# 13-0739, Beaufort County
USACE Action ID: 2008-02655
Tar-Parmlico River Basin: 03020104-040040

| | |
|-------------------------------|---|
| Date Prepared: | May 20, 2019 |
| Meeting Date, Time, Location: | May 16, 2019, 10:30 am On-site (Beaufort County, NC) |
| Attendees: | USACE – Kim Browning DMS – Jeff Schaffer, Jeremiah Dow, Melanie Allen DWR – Erin Davis WRC – Travis Wilson, Maria Dunn Baker – Drew Powers, Katie McKeithan |
| Subject: | Credit release site walkover with IRT |
| Recorded By: | Drew Powers |

An on-site meeting was held on May 16th, 2019 at 10:30 am to discuss St.Clair Restoration Project (Full Delivery) in Beaufort County, NC. The purposes of this meeting were to:

1. Discuss credits to be released and to get ready for project closeout; and
2. Identify and discuss potential concerns/issues based on field observations.

General recent weather conditions have been hot and dry in the area.

UT2

The group met at the entrance of the path leading to the site off Peoples Road in Bath, NC. A general site overview and map orientation was provided and discussed. The group then started walking into the site near monitoring well 5 where Melanie and Erin took a soil sample within the wetland boundary. The soils showed mottling and developing hydric features. The group walked upstream.

Both Kim and Erin questioned if the site had previous supplemental planting due to the height of some of the trees they encountered. Katie replied that there had been supplemental planting (40 containerized plants were installed in early 2019). Erin mentioned that the vigor of the trees looked good for the most part and noticed an effort to control the pine tree population. Kim mentioned, with the surrounding pine tree population, that the elimination of all pine trees is inevitable but was glad to see that efforts have been made. Another soil sample was taken near monitoring well 2. Melanie and Erin both were more pleased with the results of this sample as it showed more distinct hydric indicators.

The group continued up UT2 towards flow gauge 3. As a group, we inspected the stream area looking at signs of water, flow, veg, and overall conditions of the stream. The stream was dry but had evidence of water and the group all agreed that water flows in this area. Katie shared all the flow gauges have already met 30 days of continuous flow this year (2019) and the Mitigation Plan's success criteria calls for two years with 30 consecutive days to be accepted. At this time the group separated and headed up to the main area of concern flow gauges 4 and 7. Along the way, Jeff referenced the coastal headwater streams guidance and how bed and bank formation is not the design for this Rosgen DA stream type. Kim seemed to recall the Mitigation Plan stating that and agreed with the design. She said she was more concerned with the flow of the water and amount of water that was moving through the system. Jeff mentioned that he has visited the site on many occasions and it typically has wet channel conditions with water up to his ankles. As the group made it to flow gauge 7 they noticed a small hole in the ground about 1" in diameter about 6" downstream of the gauge, that some believed could be tampering with the results. Both Kim and Travis questioned our results of 84 consecutive days as of March 26th this year considering how different flow gauge 7 and 3 were from each other. Travis mentioned that it might be appropriate to check the gauges and confirm that the gauges are reading properly. The group then headed to flow gauge 4 still looking at veg and channel condition. Melanie and Erin took another soil sample right by the gauge and confirmed the hydric soils and could see a difference in the wetland soils compared to the stream soils. Out of curiosity Erin took a soil sample on the floodplain outside of the swale. This confirmed that these soils were upland and much different than both the stream and wetlands previous. This concluded the UT2 portion of the walk through and the group decided to continue to UT3.

UT3

The group congregated at the top of UT3 at monitoring well 8 to orient themselves with the map and discuss the area. Erin mentioned that the veg looked good and could notice pine and sweetgum removal. Maria and Travis began looking at the ditches in the easement and outside the easement while Jeremiah, Erin, and Melanie took a soil sample by monitoring well 7. The soils were dry but showed good hydric indicators throughout the soil. After this the group fast tracked to the culverts at the bottom of UT3 to look for flow and culvert placement. On the way, Erin asked Drew if invasive have been treated and he replied that no invasive species have been an issue on this site. Once the group got to the culvert they made their way in the stream towards flow gauge 5. Kim saw no issues with the gauge or stream and Travis was fine with the culverts. This concluded the UT3 walk through.

This concluded the walkover and below are a few notes that were discussed back at the vehicles before departure.

Erin summarized soils:

- soils look better than expected, seeing hydric indicators except near veg plot 5 which was showing mottling and developing hydric indicators.
- dark surface soil
- wetlands were a sandy/loam and the reach turned silt
- stream soils differed from the wetland and upland soils

Travis commented:

- flow gauges should be checked for proper installation and maintenance to make sure they are accurately matching the onsite evidence of flow

Kim's summary:

- USACE will be looking for a stream JD at close out. UT3 looks OK; however, the upper section of UT2 is questionable.
- Ditch manipulations from the adjacent ag fields (currently drained and being maintenance) may not be helping the site.
- Vegetation along UT3 does not look like a wetland with evidence of black berry and ant hills. Soils do appear to be wetting.
- Some of the vegetation onsite is a little short. There is a strong pine seed source, but Michael Baker has worked on the population on-site.
- Release:
 - o At risk at top of UT2, recommend holding.
 - o Wetlands held at MY 3 and 4, OK with releasing this year.
 - o Melanie will make a recommendation for release.

This represents Baker Engineering's best interpretation of the meeting discussions. If anyone should find any information contained in these meeting notes to be in error and/or incomplete based on individual comments or conversations, please notify me with corrections/additions as soon as possible.


Most sincerely,




Andrew Powers
Michael Baker Engineering, Inc.
8000 Regency Parkway, Suite 600
Cary, NC 27518
Phone: 919-481-5732
Email: Andrew.Powers@mbakerintl.com

- Conservation Easement
- Drainage Modification Installed 2016 (10 ft wide, 1 ft deep, length to scale)
- Drainages Filled (March 2016)
- Drainage Not Filled
- ▲ Photo Points
- Groundwater Monitoring Wells (All Passed)
- Vegetation Plot Meeting Criteria (with MY5 Stem Densities)
- Temporary Vegetation Transects (with Stem Densities)
- Wetland Restoration Areas (2.87 acres total)
- Potential New Wetland Restoration Areas (1.05 acres total)

- Flow Gauge Meeting Criteria
- Flow Gauge Not Meeting Criteria
- As-Built Streams**
- Restoration: Headwater Valley
- No Credit
- Buffer Zone A: 0-50 ft (226,002 ft² or 5.2 ac, 1:1 ratio = 226,002 BMUs)
- Buffer Zone B: 51-100 ft (137,575 ft² or 3.1 ac, 1:1 ratio = 137,575 BMUs)



NC Center for Geographic Information & Analysis, NC OneMap, NC Center for Geographic Information and Analysis, NC 911 Board



NCDEQ - Division of Mitigation Services
Project # 95015



Figure 2
Current Conditions Plan View: MY5
St. Clair Creek Site
Beaufort County, NC

Appendix B

Visual Assessment Data





Figure 2
Current Conditions Plan View: MY7
St. Clair Creek Site
Beaufort County, NC

| Table 5a. Visual Stream Morphology Stability Assessment | | | | | | | | | | |
|---|--|--|--|---------------------------|-----------------------------|----------------------------|----------------------------------|------------------------------------|-------------------------------------|---------------------------------------|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | | | | | | | | | | |
| Reach ID: UT2 | | | | | | | | | | |
| Assessed Length (LF): 2,133 | | | | | | | | | | |
| Major Channel Category | Channel Sub-Category | Metric | Number Stable (Performing as Intended) | Total Number per As-built | Number of Unstable Segments | Amount of Unstable Footage | % Stable, Performing as Intended | Number with Stabilizing Woody Veg. | Footage with Stabilizing Woody Veg. | Adjusted % for Stabilizing Woody Veg. |
| 1. Bed | 1. Vertical Stability | 1. Aggradation | | | 0 | 0 | 100% | | | |
| | | 2. Degradation | | | 0 | 0 | 100% | | | |
| | 2. Riffle Condition | 1. Texture Substrate | NA | NA | | | | | | |
| | | 1. Depth | NA | NA | | | | | | |
| | 3. Meander Pool Condition | 2. Length | NA | NA | | | | | | |
| | | 4. Thalweg Position | 1. Thalweg centering at upstream of meander bend (Run) | NA | NA | | | | | |
| | 2. Thalweg centering at downstream of meander bend (Glide) | | NA | NA | | | | | | |
| 3. Thalweg centering along valley | Yes | | 2,133 LF | | | | | | | |
| 2. Bank | 1. Scoured/Eroding | Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion | | | 0 | 0 | 100% | 0 | 2,133 | 100% |
| | 2. Undercut | Banks undercut/overhanging to the extent that mass wasting appears likely | | | 0 | 0 | 100% | 0 | 2,133 | 100% |
| | 3. Mass Wasting | Banks slumping, caving or collapse | | | 0 | 0 | 100% | 0 | 2,133 | 100% |
| | | Totals | | | | 0 | 0 | 100% | 0 | 2,133 |
| 3. Engineering Structures | 1. Overall Integrity | Structures physically intact with no dislodged boulders or logs | NA | NA | | | | | | |
| | 2. Grade Control | Grade control structures exhibiting maintenance of grade across the sill | NA | NA | | | | | | |
| | 2a. Piping | Structures lacking any substantial flow underneath sill or arms | NA | NA | | | | | | |
| | 3. Bank Position | Bank erosion within the structures extent of influence does not exceed 15% | NA | NA | | | | | | |
| | 4. Habitat | Pool forming structures maintaining - Max Pool Depth | NA | NA | | | | | | |

| Table 5a. Visual Stream Morphology Stability Assessment | | | | | | | | | | |
|---|--|--|--|---------------------------|-----------------------------|----------------------------|----------------------------------|------------------------------------|-------------------------------------|---------------------------------------|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | | | | | | | | | | |
| Reach ID: UT3 | | | | | | | | | | |
| Assessed Length (LF): 1,141 | | | | | | | | | | |
| Major Channel Category | Channel Sub-Category | Metric | Number Stable (Performing as Intended) | Total Number per As-built | Number of Unstable Segments | Amount of Unstable Footage | % Stable, Performing as Intended | Number with Stabilizing Woody Veg. | Footage with Stabilizing Woody Veg. | Adjusted % for Stabilizing Woody Veg. |
| 1. Bed | 1. Vertical Stability | 1. Aggradation | | | 0 | 0 | 100% | | | |
| | | 2. Degradation | | | 0 | 0 | 100% | | | |
| | 2. Riffle Condition | 1. Texture Substrate | NA | NA | | | | | | |
| | | 1. Depth | NA | NA | | | | | | |
| | 3. Meander Pool Condition | 2. Length | NA | NA | | | | | | |
| | | 4. Thalweg Position | 1. Thalweg centering at upstream of meander bend (Run) | NA | NA | | | | | |
| | 2. Thalweg centering at downstream of meander bend (Glide) | | NA | NA | | | | | | |
| 3. Thalweg centering along valley | Yes | | 1,141 LF | | | | | | | |
| 2. Bank | 1. Scoured/Eroding | Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion | | | 0 | 0 | 100% | 0 | 1,141 | 100% |
| | 2. Undercut | Banks undercut/overhanging to the extent that mass wasting appears likely | | | 0 | 0 | 100% | 0 | 1,141 | 100% |
| | 3. Mass Wasting | Banks slumping, caving or collapse | | | 0 | 0 | 100% | 0 | 1,141 | 100% |
| | Totals | | | | | 0 | 0 | 100% | 0 | 1,141 |
| 3. Engineering Structures | 1. Overall Integrity | Structures physically intact with no dislodged boulders or logs | NA | NA | | | | | | |
| | 2. Grade Control | Grade control structures exhibiting maintenance of grade across the sill | NA | NA | | | | | | |
| | 2a. Piping | Structures lacking any substantial flow underneath sill or arms | NA | NA | | | | | | |
| | 3. Bank Position | Bank erosion within the structures extent of influence does not exceed 15% | NA | NA | | | | | | |
| | 4. Habitat | Pool forming structures maintaining - Max Pool Depth | NA | NA | | | | | | |

| Table 5b. Stream Problem Areas | | | |
|--|-----------------------|------------------------|---------------------|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | | | |
| Feature Issue | Station Number | Suspected Cause | Photo Number |
| None Observed | -- | -- | -- |

| Table 6a. Vegetation Conditions Assessment | | | | | | |
|--|--|----------------------------------|-----------------------|---------------------------|-------------------------|-----------------------------|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | | | | | | |
| Reach ID: UT2 | | | | | | |
| Planted Acreage: 11.6 | | | | | | |
| Vegetation Category | Defintions | Mapping Threshold (acres) | CCPV Depiction | Number of Polygons | Combined Acreage | % of Planted Acreage |
| 1. Bare Areas | Very limited cover both woody and herbaceous material. | 0.1 | NA | 0 | 0.00 | 0.0% |
| 2. Low Stem Density Areas | Woody stem densities clearly below target levels based on MY3, 4 or 5 stem count criteria. | 0.1 | NA | 0 | 0.00 | 0.0% |
| Total | | | | 0 | 0.00 | 0.0% |
| 3. Areas of Poor Growth Rates or Vigor | Areas with woody stems or a size class that are obviously small given the monitoring year. | 0.25 | NA | 0 | 0.00 | 0.0% |
| Cumulative Total | | | | 0 | 0.00 | 0.0% |
| Easement Acreage: | | | | | | |
| Vegetation Category | Defintions | Mapping Threshold | CCPV Depiction | Number of Polygons | Combined Acreage | % of Planted Acreage |
| 5. Invasive Areas of Concern | Areas or points (if too small to render as polygons at map scale) | 1000 ft ² | NA | 0 | 0.00 | 0.0% |
| 6. Easement Encroachment Areas | Areas or points (if too small to render as polygons at map scale) | none | NA | 0 | 0.00 | 0.0% |

| Table 6a. Vegetation Conditions Assessment | | | | | | |
|--|--|----------------------------------|-----------------------|---------------------------|-------------------------|-----------------------------|
| St. Clair Restoration Project: DMS Project ID No. 95015 | | | | | | |
| Reach ID: UT3 | | | | | | |
| Planted Acreage: 5.9 | | | | | | |
| Vegetation Category | Defintions | Mapping Threshold (acres) | CCPV Depiction | Number of Polygons | Combined Acreage | % of Planted Acreage |
| 1. Bare Areas | Very limited cover both woody and herbaceous material. | 0.1 | NA | 0 | 0.00 | 0.0% |
| 2. Low Stem Density Areas | Woody stem densities clearly below target levels based on MY3, 4 or 5 stem count criteria. | 0.1 | NA | 0 | 0.00 | 0.0% |
| Total | | | | 0 | 0.00 | 0.0% |
| 3. Areas of Poor Growth Rates or Vigor | Areas with woody stems or a size class that are obviously small given the monitoring year. | 0.25 | NA | 0 | 0.00 | 0.0% |
| Cumulative Total | | | | 0 | 0.00 | 0.0% |
| Easement Acreage: | | | | | | |
| Vegetation Category | Defintions | Mapping Threshold | CCPV Depiction | Number of Polygons | Combined Acreage | % of Planted Acreage |
| 4. Invasive Areas of Concern | Areas or points (if too small to render as polygons at map scale) | 1000 ft ² | NA | 0 | 0.00 | 0.0% |
| 5. Easement Encroachment Areas | Areas or points (if too small to render as polygons at map scale) | none | NA | 0 | 0.00 | 0.0% |

| Table 6b. Vegetation Problem Areas | | | |
|--|---|------------------------------|---|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | | | |
| Feature Issue | Station Number | Suspected Cause | Resolution |
| Loblolly Pine (<i>Pinus taeda</i>) | Scattered throughout buffer on upper UT-2 | Post-restoration seed source | Will be treated in 2021 with power tools and/or chemical application. |

St. Clair Restoration Site: Stream Photo Points (12/10/20)



Photo Point 1 – UT2



Photo Point 2 – UT2



Photo Point 3 – UT2



Photo Point 4 – UT2



Photo Point 5 – UT2



Photo Point 6 – UT2

St. Clair Restoration Site: Stream Photo Points (12/10/20)



Photo Point 7 – UT2



Photo Point 8 – UT2



Photo Point 9 – UT2



Photo Point 10 – UT2



Photo Point 11 – UT2



Photo Point 12 – UT2

St. Clair Restoration Site: Stream Photo Points (12/10/20)



Photo Point 13 – UT2



Photo Point 14 – UT2



Photo Point 15 – UT2



Photo Point 16 – UT3



Photo Point 17 – UT3



Photo Point 18 – UT3

St. Clair Restoration Site: Stream Photo Points (12/10/20)



Photo Point 19 – UT3



Photo Point 20 – UT3



Photo Point 21 – UT3



Photo Point 22 – UT3



Photo Point 23 – UT3



Photo Point 24 – UT3

St. Clair Restoration Site: Stream Photo Points (12/10/20)



Flow Hydrology at Flow Gauge #4



Flow Hydrology at Flow Gauge #4 (close-up)



Flow Hydrology at Flow Gauge #7

St. Clair Restoration Site: Vegetation Plot Photos (12/10/20)



Vegetation Plot 1



Vegetation Plot 2



Vegetation Plot 3



Vegetation Plot 4



Vegetation Plot 5



Vegetation Plot 6

St. Clair Restoration Site: Vegetation Plot Photos (12/10/20)



Vegetation Plot 7



Vegetation Plot 8



Vegetation Plot 9

St. Clair Restoration Site: Hydrology Monitoring Stations (12/10/2020)



Auto Well – SCAW1



Auto Well – SCAW2



Auto Well – SCAW3



Auto Well – SCAW4



Supplemental Auto Well – SCAW5



Supplemental Auto Well – SCAW6

St. Clair Restoration Site: Hydrology Monitoring Stations (12/10/2020)



Supplemental Auto Well – SCAW7



Supplemental Auto Well – SCAW8



Supplemental Auto Well – SCAW9



Supplemental Auto Well – SCAW10



Reference Auto Well – SCREF2

St. Clair Restoration Site: Hydrology Monitoring Stations (12/10/2020)



Flow Logger (UT2) – SCFL1



Flow Logger (UT2) – SCFL2



Flow Logger (UT2) – SCFL3



Flow Logger (UT2) – SCFL4




Flow Logger (UT3) – SCFL5



Flow Logger (UT3) – SCFL6

St. Clair Restoration Site: Hydrology Monitoring Stations (12/10/2020)



Flow Logger (UT2) – SCFL7

Appendix C

Vegetation Plot Data

| Table 7. Vegetation Plot Criteria Attainment | | | |
|---|---|---|-------------------|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | | | |
| Plot ID | Vegetation Survival Threshold Met? | MY7 Planted Density / As-built Planted Stem Density* | Tract Mean |
| 1 | Y | 445/728 | 594 |
| 2 | Y | 647/648 | |
| 3 | Y | 647/688 | |
| 4 | Y | 607/728 | |
| 5 | Y | 526/688 | |
| 6 | Y | 364/486 | |
| 7 | Y | 931/1,174 | |
| 8 | Y | 445/728 | |
| 9 | Y | 728/769 | |
| <p>Note: *MY7 Planted Density / As-built Planted Stem Density - reflects the changes in stem density based on the current total density of planted stems as compared to the original planted stem density from the As-built conditions.</p> | | | |

| Table 8. CVS Vegetation Metadata | |
|--|---|
| St. Clair Creek Restoration Project: DMS Project ID No. 95015 | |
| Report Prepared By | Andrew Powers |
| Date Prepared | 12/18/2020 12:00 |
| database name | MichaelBaker_MY7_2020_StClair_95015.mdb |
| database location | C:\Users\Andrew.Powers\Desktop |
| computer name | CARYLAPOWERS1 |
| file size | 48177152 |
| DESCRIPTION OF WORKSHEETS IN THIS DOCUMENT----- | |
| Metadata | Description of database file, the report worksheets, and a summary of project(s) and project data. |
| Proj, planted | Each project is listed with its PLANTED stems per acre, for each year. This excludes live stakes. |
| Proj, total stems | Each project is listed with its TOTAL stems per acre, for each year. This includes live stakes, all planted stems, and all natural/volunteer stems. |
| Plots | List of plots surveyed with location and summary data (live stems, dead stems, missing, etc.). |
| Vigor | Frequency distribution of vigor classes for stems for all plots. |
| Vigor by Spp | Frequency distribution of vigor classes listed by species. |
| Damage | List of most frequent damage classes with number of occurrences and percent of total stems impacted by each. |
| Damage by Spp | Damage values tallied by type for each species. |
| Damage by Plot | Damage values tallied by type for each plot. |
| Planted Stems by Plot and Spp | A matrix of the count of PLANTED living stems of each species for each plot; dead and missing stems are excluded. |
| ALL Stems by Plot and spp | A matrix of the count of total living stems of each species (planted and natural volunteers combined) for each plot; dead and missing stems are excluded. |
| PROJECT SUMMARY----- | |
| Project Code | 95015 |
| project Name | St Clair Creek Restoration Project |
| Description | |
| River Basin | Tar-Pamlico |
| length(ft) | |
| stream-to-edge width (ft) | |
| area (sq m) | |
| Required Plots (calculated) | |
| Sampled Plots | 9 |

Table 9a. CVS Stem Count of Planted Stems by Plot and Species
St. Clair Creek Restoration Project: DMS Project ID No. 95015

| Comment | Species | Species Type | Common Name | Total Planted Stems | # plots | avg# stems | plot 95015-01-0001-year:7 | plot 95015-01-0002-year:7 | plot 95015-01-0003-year:7 | plot 95015-01-0004-year:7 | plot 95015-01-0005-year:7 | plot 95015-01-0006-year:7 | plot 95015-01-0007-year:7 | plot 95015-01-0008-year:7 | plot 95015-01-0009-year:7 | |
|----------------|-------------------------------|--------------|-------------------------|---------------------|-----------|------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---|
| | <i>Aronia arbutifolia</i> | Shrub | Red Chokeberry | 5 | 2 | 2.5 | | 4 | | | | | | | | 1 |
| | <i>Carpinus caroliniana</i> | Shrub Tree | American hornbeam | 5 | 4 | 1.25 | | 1 | | | | | 1 | | 1 | 2 |
| | <i>Clethra alnifolia</i> | Shrub | coastal sweetpepperbush | 1 | 1 | 1 | 1 | | | | | | | | | |
| | <i>Fraxinus pennsylvanica</i> | Tree | green ash | 5 | 4 | 1.25 | 2 | | | 1 | | | 1 | | | 1 |
| | <i>Morella cerifera</i> | Shrub Tree | wax myrtle | 2 | 2 | 1 | | | | | | 1 | | | | 1 |
| | <i>Nyssa sylvatica</i> | Tree | blackgum | 7 | 3 | 2.33 | | 1 | | | | | | 4 | | 2 |
| | <i>Persea palustris</i> | Tree | swamp bay | 6 | 2 | 3 | | | | | | | | | | 2 |
| | <i>Quercus laurifolia</i> | Tree | laurel oak | 9 | 3 | 3 | 1 | | 3 | | 5 | | | | | |
| | <i>Quercus lyrata</i> | Tree | overcup oak | 15 | 7 | 2.14 | 4 | 2 | 1 | | 2 | | | | 2 | 3 |
| | <i>Quercus michauxii</i> | Tree | swamp chestnut oak | 27 | 6 | 4.5 | 1 | 4 | | 4 | 5 | 5 | 8 | | | |
| | <i>Quercus phellos</i> | Tree | willow oak | 11 | 5 | 2.2 | | | 5 | 1 | 1 | 1 | 3 | | | |
| | <i>Taxodium distichum</i> | Tree | bald cypress | 15 | 4 | 3.75 | | 4 | 3 | 7 | | 1 | | | | |
| | <i>Ulmus americana</i> | Tree | American elm | 19 | 6 | 3.17 | 1 | | 4 | 2 | | 1 | 4 | | | 7 |
| | <i>Vaccinium corymbosum</i> | Shrub | highbush blueberry | 1 | 1 | 1 | | | | | | | | | | 1 |
| | <i>Viburnum dentatum</i> | Shrub Tree | southern arrowwood | 4 | 2 | 2 | 1 | | | | | | | | | 3 |
| Totals: | | | | 132 | 15 | | 11 | 16 | 16 | 15 | 13 | 9 | 23 | 11 | 18 | |

Table 9b. Stem Count for All Species (Planted and Volunteer) Arranged by Plot
St. Clair Creek Restoration Project: DMS Project ID No. 95015

| Botanical Name | Common Name | Plots | | | | | | | | | Average Stems Per Acre |
|--|-------------------------|-------|------|------|------|------|-----|------|-----|------------------------|------------------------|
| | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | |
| Tree Species | | | | | | | | | | | |
| <i>Acer rubrum</i> | red maple | 2 | 1 | | | 6 | | 3 | | 2 | |
| <i>Fraxinus pennsylvanica</i> | green ash | 2 | | | 1 | | | 1 | | 1 | |
| <i>Liquidambar styraciflua</i> | sweetgum | 2 | 1 | 4 | 3 | 1 | 1 | 5 | 3 | 5 | |
| <i>Nyssa sylvatica</i> | blackgum | | 1 | | | | | 4 | 2 | | |
| <i>Pinus taeda</i> | loblolly pine | 2 | 2 | 2 | 2 | 6 | 2 | 4 | 4 | 5 | |
| <i>Quercus laurifolia</i> | laurel oak | 6 | | 3 | | 5 | | | | | |
| <i>Quercus lyrata</i> | overcup oak | 4 | 2 | 1 | 1 | 2 | | 2 | 1 | 3 | |
| <i>Quercus michauxii</i> | swamp chestnut oak | 1 | 4 | | 4 | 5 | 5 | 8 | | | |
| <i>Quercus phellos</i> | willow oak | | | 5 | 1 | 1 | 1 | 4 | | | |
| <i>Taxodium distichum</i> | bald cypress | | 4 | 3 | 7 | | 1 | | | | |
| <i>Ulmus americana</i> | American elm | 1 | | 4 | 2 | | 2 | 4 | | 7 | |
| Shrub Species | | | | | | | | | | | |
| <i>Aronia arbutifolia</i> | Red Chokeberry | | 4 | | | | | | | 1 | |
| <i>Baccharis</i> | Salt myrtle | 3 | 1 | 2 | 3 | 4 | 8 | | 3 | | |
| <i>Carpinus caroliniana</i> | American hornbeam | | 1 | | | | | 1 | 1 | 2 | |
| <i>Clethra alnifolia</i> | coastal sweetpepperbush | 1 | | | | | | | | | |
| <i>Morella cerifera</i> | wax myrtle | 2 | 3 | 2 | 2 | 2 | 1 | | 3 | 2 | |
| <i>Persea palustris</i> | swamp bay | | | | | | | | 2 | 5 | |
| <i>Rhus copallinum</i> | flameleaf sumac | | 5 | 5 | 3 | 2 | 1 | 1 | | | |
| <i>Vaccinium corymbosum</i> | highbush blueberry | | | | | | | | 1 | | |
| <i>Viburnum dentatum</i> | southern arrowwood | 1 | | | | | | | 3 | | |
| | | | | | | | | | | Average Stems Per Acre | |
| Stems Per Plot (December 2020) | | 27 | 29 | 31 | 29 | 34 | 22 | 37 | 23 | 33 | |
| Total Stems/Acre Year 7 (December 2020) | | 1093 | 1174 | 1255 | 1174 | 1376 | 890 | 1497 | 931 | 1335 | 1192 |
| Total Stems/Acre Year 6 (December 2019) | | 769 | 728 | 648 | 769 | 688 | 607 | 1012 | 486 | 809 | 724 |
| Total Stems/Acre Year 5 (December 2018) | | 809 | 688 | 728 | 647 | 607 | 445 | 1012 | 486 | 809 | 692 |
| Total Stems/Acre Year 4 (October 2017) | | 1052 | 1052 | 809 | 850 | 769 | 405 | 1133 | 680 | 728 | 831 |
| Total Stems/Acre Year 3 (December 2016) | | 567 | 648 | 648 | 648 | 526 | 364 | 850 | 526 | 688 | 607 |
| Total Stems/Acre Year 2 (November 2015) | | 607 | 648 | 648 | 648 | 526 | 405 | 1012 | 607 | 688 | 643 |
| Total Stems/Acre Year 1 (December 2014) | | 688 | 648 | 648 | 648 | 648 | 445 | 1052 | 648 | 728 | 683 |
| Total Stems/ Acre for Year 0 As-Built (Baseline Data) | | 728 | 648 | 688 | 728 | 688 | 486 | 1174 | 728 | 769 | 737 |

Table 9d. Vegetation Summary and Totals
St. Clair Creek Restoration Project: DMS Project ID No. 95015

St Clair Creek Restoration Project (#95015)
Year 7 (10-Dec-2020)

Vegetation Plot Summary Information

| Plot # | Riparian Buffer Stems ¹ | Stream/ Wetland Stems ² | Live Stakes | Invasives | Volunteers ³ | Total ⁴ | Unknown Growth Form |
|--------|------------------------------------|------------------------------------|-------------|-----------|-------------------------|--------------------|---------------------|
| 1 | 9 | 11 | 0 | 0 | 16 | 27 | 0 |
| 2 | 12 | 16 | 0 | 0 | 13 | 29 | 0 |
| 3 | 16 | 16 | 0 | 0 | 15 | 31 | 0 |
| 4 | 15 | 15 | 0 | 0 | 14 | 29 | 0 |
| 5 | 13 | 13 | 0 | 0 | 21 | 34 | 0 |
| 6 | 8 | 9 | 0 | 0 | 13 | 22 | 0 |
| 7 | n/a | 23 | 0 | 0 | 14 | 37 | 0 |
| 8 | n/a | 11 | 0 | 0 | 12 | 23 | 0 |
| 9 | n/a | 18 | 0 | 0 | 15 | 33 | 0 |

Wetland/Stream Vegetation Totals
(per acre)

| Plot # | Stream/ Wetland Stems ² | Volunteers ³ | Total ⁴ | Success Criteria Met? |
|--------------------|------------------------------------|-------------------------|--------------------|-----------------------|
| 1 | 445 | 647 | 1093 | Yes |
| 2 | 647 | 526 | 1174 | Yes |
| 3 | 647 | 607 | 1255 | Yes |
| 4 | 607 | 567 | 1174 | Yes |
| 5 | 526 | 850 | 1376 | Yes |
| 6 | 364 | 526 | 890 | Yes |
| 7 | 931 | 567 | 1497 | Yes |
| 8 | 445 | 486 | 931 | Yes |
| 9 | 728 | 607 | 1335 | Yes |
| Project Avg | 594 | 598 | 1192 | Yes |

Riparian Buffer Vegetation Totals
(per acre)

| Plot # | Riparian Buffer Stems ¹ | Success Criteria Met? |
|--------------------|------------------------------------|-----------------------|
| 1 | 364 | Yes |
| 2 | 486 | Yes |
| 3 | 647 | Yes |
| 4 | 607 | Yes |
| 5 | 526 | Yes |
| 6 | 324 | Yes |
| 7* | n/a | n/a |
| 8* | n/a | n/a |
| 9* | n/a | n/a |
| Project Avg | 492 | Yes |

*These plots are not located in areas receiving riparian buffer credits

| Stem Class | Characteristics | Color for Density |
|------------------------------------|---|--|
| ¹ Buffer Stems | Native planted hardwood stems including trees and native shrub species. No pines. No vines. | Exceeds requirements by 10% |
| ² Stream/ Wetland Stems | Native planted woody stems. Includes shrubs, does NOT include live stakes. No vines | |
| ³ Volunteers | Native woody stems. Not planted. No vines. | Exceeds requirements, but by less than 10% |
| ⁴ Total | Planted + volunteer native woody stems. Includes live stakes. Excl. exotics. Excl. vines. | |

Appendix D

Hydrologic Data

Table 10. Wetland Restoration Area Well Success

St. Clair Creek Restoration Project: Project ID No. 95015

| Well ID | Percentage of Consecutive Days <12 inches from Ground Surface ¹ | | | | | | | Most Consecutive Days Meeting Criteria ² | | | | | | | Percentage of Cumulative Days <12 inches from Ground Surface | | | | | | | Cumulative Days Meeting Criteria ³ | | | | | | |
|---|--|---------------|---------------|---------------|---------------|---------------|---------------|---|---------------|---------------|---------------|---------------|---------------|---------------|--|---------------|---------------|---------------|---------------|---------------|---------------|---|---------------|---------------|---------------|---------------|---------------|---------------|
| | Year 1 (2014) | Year 2 (2015) | Year 3 (2016) | Year 4 (2017) | Year 5 (2018) | Year 6 (2019) | Year 7 (2020) | Year 1 (2014) | Year 2 (2015) | Year 3 (2016) | Year 4 (2017) | Year 5 (2018) | Year 6 (2019) | Year 7 (2020) | Year 1 (2014) | Year 2 (2015) | Year 3 (2016) | Year 4 (2017) | Year 5 (2018) | Year 6 (2019) | Year 7 (2020) | Year 1 (2014) | Year 2 (2015) | Year 3 (2016) | Year 4 (2017) | Year 5 (2018) | Year 6 (2019) | Year 7 (2020) |
| Wetland Monitoring Wells (Installed September 2013) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SCAW1 | 1.0 | 12.3 | 13.1 | 33.7 | 23.0 | 13.1 | 17.7 | 3 | 35 | 37 | 95 | 65 | 37 | 50 | 8.5 | 39.3 | 61.7 | 68.1 | 68.1 | 40.1 | 46.8 | 24 | 111 | 174 | 192 | 192 | 113 | 132 |
| SCAW2 | 3.8 | 3.3 | 9.2 | 10.6 | 13.1 | 12.8 | 17.7 | 11 | 9 | 26 | 30 | 37 | 36 | 50 | 30.6 | 16.1 | 19.9 | 51.1 | 59.9 | 41.1 | 52.5 | 86 | 46 | 56 | 144 | 169 | 116 | 148 |
| SCAW3 | 2.3 | 13.4 | 9.6 | 11.0 | 13.1 | 12.4 | 17.7 | 7 | 38 | 27 | 31 | 37 | 35 | 50 | 9.4 | 37.5 | 44.3 | 26.2 | 47.2 | 33.0 | 44.7 | 27 | 106 | 125 | 74 | 133 | 93 | 126 |
| SCAW4 | 7.8 | 12.3 | 6.0 | 11.0 | 22.3 | 13.1 | 17.4 | 22 | 35 | 17 | 31 | 63 | 37 | 49 | 17.3 | 20.3 | 35.8 | 25.9 | 57.8 | 25.5 | 34.4 | 49 | 57 | 101 | 73 | 163 | 72 | 97 |
| Supplemental Wetland Monitoring Wells (Installed April 2016)** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SCAW5* | -- | -- | 12.8 | 11.3 | 23.4 | 21.6 | 26.6 | -- | -- | 36 | 32 | 66 | 61 | 75 | -- | -- | 46.8 | 69.9 | 68.1 | 47.9 | 73.0 | -- | -- | 132 | 197 | 192 | 135 | 206 |
| SCAW6* | -- | -- | 3.9 | 10.3 | 12.4 | 12.8 | 15.6 | -- | -- | 11 | 29 | 35 | 36 | 44 | -- | -- | 19.9 | 32.6 | 53.9 | 33.0 | 37.9 | -- | -- | 56 | 92 | 152 | 93 | 107 |
| SCAW7* | -- | -- | 9.6 | 11.3 | 22.3 | 13.1 | 17.7 | -- | -- | 27 | 32 | 63 | 37 | 50 | -- | -- | 33.0 | 38.3 | 55.0 | 27.3 | 44.7 | -- | -- | 93 | 108 | 155 | 77 | 126 |
| SCAW8* | -- | -- | 4.6 | 11.3 | 12.8 | 12.4 | 16.0 | -- | -- | 13 | 32 | 36 | 35 | 45 | -- | -- | 22.0 | 23.8 | 50.0 | 19.1 | 31.6 | -- | -- | 62 | 67 | 141 | 54 | 89 |
| Supplemental Wetland Monitoring Wells (Installed March 2017)** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SCAW9* | -- | -- | -- | 9.9 | 12.1 | 11.0 | 17.7 | -- | -- | -- | 28 | 34 | 31 | 50 | -- | -- | -- | 45.4 | 55.0 | 36.2 | 48.9 | -- | -- | -- | 128 | 155 | 102 | 138 |
| SCAW10* | -- | -- | -- | 9.9 | 12.4 | 8.2 | 7.8 | -- | -- | -- | 28 | 35 | 23 | 22 | -- | -- | -- | 28.7 | 36.5 | 20.9 | 33.3 | -- | -- | -- | 81 | 103 | 59 | 94 |
| Reference Wells (Installed September 2013) | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SCAWREF1 | 24.8 | 57.9 | 40.9 | 41.1 | -- | -- | -- | 70 | 163 | 115 | 116 | -- | -- | -- | 46.4 | 93.7 | 77.9 | 70.1 | -- | -- | -- | 131 | 264 | 220 | 198 | -- | -- | -- |
| SCAWREF2** | 27.0 | 60.1 | 43.8 | 40.9 | 38.2 | 21.6 | 0.0 | 66 | 170 | 124 | 115 | 108 | 61 | 0 | 44.5 | 94.1 | 76.9 | 67.1 | 66.5 | 26.6 | 0.0 | 126 | 257 | 217 | 189 | 188 | 75 | 0 |

¹Indicates the percentage of the single greatest consecutive number of days within the monitored growing season with a water table 12 inches or less from the soil surface.

²Indicates the single greatest consecutive number of days within the monitored growing season with a water table 12 inches or less from the soil surface.

³Indicates the total number of days within the monitored growing season with a water table 12 inches or less from the soil surface.

Growing season for Beaufort County is from February 28 to December 6 and is **282** days long. 12% of the growing season is **33.8** days.


Note: The hydric Tomotley soil series present in the wetlands on site is listed as having an average hydroperiod of between **10-12%** in the IRT monitoring guidance document issued Oct. 2016

HIGHLIGHTED indicates wells that *did not* meet the success criteria for the most consecutive number of days within the monitored Year 7 growing season with a water 12 inches or less from the soil surface. For Year 7 wetland monitoring, all eight wells located in currently credited wetland areas exhibited hydroperiods greater than 12% during the 2020 growing season.


*To gather additional well data in the wetland restoration area, In-Situ groundwater monitoring dataloggers SCAW5 - SCAW 8 were installed in April 2016, several weeks after the growing season had begun. Two additional In-Situ groundwater monitoring dataloggers SCAW9 and SCAW10 were installed in March 2017, just over two weeks past the start of the growing season in 2017.

**REF2 well gauge connections have degraded and it has been sent to In-Situ for additional MY7 data retrieval. A new gauge will be installed in the winter of 2021.


Figure 3. Wetland Well Graphs




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT2) (As-Built Well - SCAW2)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT3) (As-Built Well - SCAW3)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT3) (As-Built Well - SCAW4)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT2) (Supplemental Well - SCAW5)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT2) (Supplemental Well - SCAW6)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT3) (Supplemental Well - SCAW7)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT3) (Supplemental Well - SCAW8)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT2) (Supplemental Well - SCAW9)




St. Clair Creek Rain (2020)




St. Clair Creek Wetland Restoration Well (UT3) (Supplemental Well - SCAW10)



St. Clair Creek Rain (2020)




St. Clair Creek Wetland Reference Well (UT3) (REF2)




| Table 11. Flow Gauge Success | | | | | | | | | | | | | | |
|---|---|------------------|------------------|------------------|------------------|------------------|------------------|---|------------------|------------------|------------------|------------------|------------------|------------------|
| St. Clair Restoration Project: DMS Project ID No. 95019 | | | | | | | | | | | | | | |
| Flow Gauge ID | Most Consecutive Days Meeting Criteria ¹ | | | | | | | Cumulative Days Meeting Criteria ² | | | | | | |
| | Year 1 (2014) | Year 2 (2015) | Year 3 (2016) | Year 4 (2017) | Year 5 (2018) | Year 6 (2019) | Year 7 (2020) | Year 1 (2014) | Year 2 (2015) | Year 3 (2016) | Year 4 (2017) | Year 5 (2018) | Year 6 (2019) | Year 7 (2020) |
| UT2 Flow Gauges (Installed March 21, 2014) | | | | | | | | | | | | | | |
| SCFL1 | 71 | 43 | 83 | 63 | 152 | 224 | 227 | - | 206 | 224 | 328 | 363 | 342 | 343 |
| SCFL2 | 64 | 43 | 84 | 60 | 121 | 121 | 89 | - | 201 | 232 | 204 | 270 | 214 | 253 |
| SCFL3 | 61 | 25 | 86 | 35 | 63 | 120 | 88 | - | 174 | 203 | 287 | 328 | 271 | 255 |
| SCFL4 | 24 | 17 | 46 | 29* | 20 | 38 | 45 | - | 118 | 124 | 86 | 146 | 85 | 106 |
| UT3 Flow Gauges (Installed July 17, 2015) | | | | | | | | | | | | | | |
| SCFL5 | 57 | 44 | 62 | 30 | 57 | 74 | 73 | NA | 174 | 162 | 79 | 214 | 327 | 108 |
| SCFL6 | 5 | 42 | 62 | 30 | 35 | 40 | 52 | NA | 116 | 180 | 191 | 214 | 103 | 87 |
| UT2 Flow Gauge (Installed June 6, 2018)³ | | | | | | | | | | | | | | |
| SCFL7 | NA | NA | NA | NA | 60 | 117 | 78 | NA | NA | NA | NA | 162 | 167 | 180 |
| Notes: | | | | | | | | | | | | | | |
| ¹ Indicates the single greatest number of consecutive days within the monitoring year where flow was measured. | | | | | | | | | | | | | | |
| ² Indicates the number of total number of days within the monitoring year where flow was measured. | | | | | | | | | | | | | | |
| *SCFL4 also recorded a 28-day consecutive flow event in 2017, in addition to the 29-day flow event shown above. | | | | | | | | | | | | | | |
| ³ SCFL7 was installed June 6th 2018 to gather additional flow data for upper UT2. | | | | | | | | | | | | | | |
| Success Criteria per St. Clair Creek Mitigation Plan: Two surface water flow events (when flow duration occurs for a minimum of 30 days) must be documented within a five-year monitoring period; otherwise, monitoring will continue for seven years or until two flow events have been documented in separate years. The automated gauges should document the occurrence of extended periods of shallow surface ponding, indicative of flow. | | | | | | | | | | | | | | |
| Surface water flow is estimated to have occurred when the pressure transducer reading is equal to or above 0.25 inches. | | | | | | | | | | | | | | |

Figure 4. Flow Gauge Graphs




*0.25 inches denotes level at which flow occurs along the UT2 valley thalweg

St. Clair Rain (2020)




St. Clair Creek Flow Gauge SCFL2 (Downstream UT2)




*0.25 inches denotes level at which flow occurs along the UT2 valley thalweg

St. Clair Rain (2020)




St. Clair Creek Flow Gauge SCFL3 (Upstream UT2)




*0.25 inches denotes level at which flow occurs along the UT2 valley thalweg

St. Clair Rain (2020)




St. Clair Creek Flow Gauge SCFL4 (Upstream UT2)




*0.25 inches denotes level at which flow occurs along the UT2 valley thalweg

St. Clair Rain (2020)




St. Clair Creek Flow Gauge SCFL5 (Downstream UT3)




*0.25 inches denotes level at which flow occurs along the UT3 valley thalweg

St. Clair Rain (2020)




St. Clair Creek Flow Gauge SCFL6 (Upstream UT3)




*0.25 inches denotes level at which flow occurs along the UT3 valley thalweg

St. Clair Rain (2020)




St. Clair Creek Flow Gauge SCFL7 (Upstream UT2)



*0.25 inches denotes level at which flow occurs along the UT2 valley thalweg

**Figure 5. Observed Rainfall versus Historic Average
St. Clair Restoration Project (DMS No. 95015) MY7 2020**



Note: Beaufort County historic average rainfall is 50.0 in, while observed previous 12 months rainfall total recorded onsite was 60.5 in.

Memorandum

St. Clair Creek Restoration Project: Channel Cross-Section Analysis for UT2 Flow

DMS Project ID. 95015
NC DEQ Contract# 003986
USACE Action ID: SAW-2008-02655, DWR# 13-0739
Tar-Pamlico River Basin: 03020104-040040

| | |
|----------------|---|
| Date Prepared: | December 13, 2020 |
| Subject: | Channel Cross-Section Analysis for UT2 Flow |
| Recorded By: | Scott King |

During the monitoring period for the St Clair Creek project, the IRT has expressed reservations regarding the seasonal flow present in the upper section of Reach UT2. Specifically, whether or not there is enough flow present to develop an appropriate channel or channels common to headwater coastal plain systems.

The entire reach is seasonally thick with herbaceous vegetation, which serves to mask both the presence of water in the reach in photographs as well as the development of a threaded channel system. Even during field inspections it can be difficult to discern the level of scour and channel formation present in the reach. As such, Baker took two cross-section transects in the upper portion of UT2 on May 1, 2020 to better illustrate the current conditions in these locations.

Please find attached the results of these cross-sections. They reveal the presence of a distinct multi-thread channel with shallow water present in the two primary threads at the time of the survey in the upper transect, and larger channel development with shallow water present in the lower transect. Both transects show signs of channel scour and evolution, with rough, irregular rutting and scour found all across the transects, even along the relatively gentle adjacent side slopes draining into the channel.

As the tree canopy matures and generates more shade for the reach, it is expected that this will depress the extent of the herbaceous growth, which will in turn allow for even more scour and channel development as this growth certainly provides substantial protection during storm events. Even during the winter, the presence of dead or quiescent vegetation acts as a stabilizing influence. Furthermore, this entire headwater system is low-gradient as is common in this portion of the low-lying Coastal Plain, and during heavy storm events much of the entire surrounding landscape is often inundated, which in turn inhibits the presence of a higher-velocity scouring flow that might be found in steeper gradient systems.

If the IRT finds these transects helpful for their evaluation of the upper portion of UT2, Baker would be happy to take several more transects for their future review.


Most sincerely,


A handwritten signature in blue ink that reads "Scott King". The signature is written in a cursive style with a large, looped 'S' and a 'K' that extends upwards.

Scott King, LSS, PWS

Scott.King@mbakerintl.com
919-219-6339 [M]

St Clair Cross Sections (collected 5/1/20):





Cross-Section / Transect Location Map:




Figure 2
Current Conditions Plan View: MY6
St. Clair Creek Site
Beaufort County, NC